

PROJECT TITLE

MOOSONEE, ONTARIO
PUBLIC SERVICES AND PROCUREMENT CANADA
BUILDING DEMOLITION
MISTIK BLVD. & MEECHIM ST.

Addendum No.2, dated 2019-09-03

LIST OF CHANGES

1. The demolition scope of work shall exclude the demolition of Pedestrian Bridge #6 and the concrete manhole structures. In addition to this, the property boundary denoted on drawings C100 and C200 marks the area not included within the project scope of work.
2. The demolition scope of work shall include the removal of various existing concrete elements, general debris and gravel/earth piles as indicated on drawings C100 and C200.
3. Disposal of hazardous waste at the local landfill is permissible, as indicated in Specification Section 01 74 21, item 1.9. All waste disposal shall be in strict accordance with local regulatory requirements and authorities having jurisdiction.
4. Crushed concrete may be utilized as granular backfill material, as indicated in Specification Section 31 00 99, item 2.1. Material and gradation of crushed concrete must comply with requisite physical properties.

END OF ADDENDUM NO.2