

Parks Canada Agency 15003-20-C Sept 6, 2019 Page 1 of 1

"SENT VIA E-MAIL"

Parks Canada Agency Terra Nova National Park General Delivery Glovertown, NL AOG 2L0

ATTENTION: Mr. Gonzo Wells, Project Manager - Project Delivery Services

Dear Gonzo,

Terra Nova National Park
Terra Nova National Park Utility Systems Recapitalization - Phase 1
Clarifications for Tender Notice 5P201-19-0084/A

Please add the following clarifications to the tender for the above noted project (Tender #5P201-19-0084/A):

- The first step for the Contractor shall be to complete the water main repair beneath the main road to the Newman Sound Campground (as shown on CW01) to allow for the by-pass in order to install the water main between the Administration Building and the Maintenance Compound.
- 2. The existing water mains to the Administration Building, Eco-Science Centre, Housing Area and Maintenance Compound must remain live during the installation of the new water main. The by-pass (mentioned above) can be used to facilitate the water main installation between the Administration Building and Maintenance Compound. Service switch-overs can take place after the mains are installed in a timely manner while ensuring service disruptions are well coordinated. Notice to Parks Canada staff for a planned water service outage shall be given at least 48 hours in advance.
- 3. All pipe, backfill and paving structure (including asphalt) in the Maintenance Compound Area must be completed before November 15, 2019 with the exception of the water and sewer service connection switch-overs near the buildings and the areas to be paved directly above them, which can take place after November 15, 2019. Notice to Parks Canada staff for a planned water service outage shall be given at least 48 hours in advance.
- 4. The STC-2000 or approved equal is acceptable as the oil-grit separator at the Maintenance Compound.