

The following changes to the tender documents are effective immediately and will form part of the contract documents:

Clarifications:

1. A cofferdam will be required if the river is open as no debris will be allowed to enter the water. If the river is frozen, the contractor can work off the ice, if it is demonstrated to be safe to do so, but all debris must be contained and removed. As this is weather dependent, it is the responsibility of the contractor to schedule and stage their work and price it accordingly.
2. Metalizing is not required for the DYWIDAG anchors.
3. Referencing Section 2.3 Schedule of the Environmental Effects Evaluation Report: delete this section in its entirety.

END OF ADDENDUM NO. 2