

Part 1 General

1.1 INSTALLATION AND REMOVAL

- .1 Install 1.8-meter-high modular steel temporary construction fencing around exterior work areas. Fencing to have access gates as required to gain access to the work area, and to be secured each night to prevent access.
- .2 Ensure Temporary fencing does not disrupt normal site operations and access, and advise Departmental Representative of any conflicts.
- .3 Provide temporary controls in order to execute Work expeditiously.
- .4 Remove from site all such work after use.

1.2 ACCESS TO SITE

- .1 Provide and maintain access roads, sidewalk crossings, ramps and construction runways as may be required for access to Work.

1.3 FIRE ROUTES

- .1 Maintain access to property including overhead clearances for use by emergency response vehicles.

1.4 PROTECTION FOR OFF-SITE AND PUBLIC PROPERTY

- .1 Protect surrounding private and public property from damage during performance of Work.
- .2 Be responsible for damage incurred.

1.5 PROTECTION OF BUILDING FINISHES

- .1 Provide protection for finished and partially finished building finishes and equipment during performance of Work.
- .2 Provide necessary screens, covers, and hoardings.
- .3 Confirm with Departmental Representative locations and installation schedule 5 days prior to installation.
- .4 Be responsible for damage incurred due to lack of or improper protection.

END OF SECTION