

L'ENTREPRENEUR DEVRA VÉRIFIER TOUTES LES DIMENSIONS ET LES CONDITIONS SUR LE CHANTIER ET AVISER SANS DÉLAI LE REPRÉSENTANT DU MINISTÈRE DE TOUTE ANOMALIE.  
Contractor to verify all dimensions and conditions on site and immediately notify the departmental representative of all discrepancies.

revisions	description	date
6		
5	ISSUED FOR TENDER	2018/07/12
4	ISSUED FOR TENDER	2018/03/15
3	ISSUED FOR FINAL REVIEW	2018/03/08
2	ISSUED FOR 99% REVIEW	2018/08/29
1	ISSUED FOR DESIGN DEVELOPMENT	2018/05/30

A	A detail no. du detail	A
C	B location drawing no. sur dessin no.	B
	C drawing no. dessin no.	C

project / projet  
**The Re-Fit of L'Esplanade Laurier for Swing Space**


140 O'CONNOR ST., OTTAWA, ONTARIO

drawing / dessin  
**MECHANICAL  
10TH FLOOR  
HVAC  
NEW WORK**

Designed By	C.L.	Conçu par
Date	MAR/17	(yyyy/mm/dd)
Drawn By	C.L.	Dessiné par
Date	MAR/17	(yyyy/mm/dd)
Reviewed By	E.P.	Examiné par
Date	MAR/17	(yyyy/mm/dd)
Approved By	E.P.	Approuvé par
Date	MAR/17	(yyyy/mm/dd)
Tender		Soumission

AHMAD KHODR / Administrateur de projets  
Project Manager / Administrateur de projets  
Project no. / No. du projet  
**R.081640.020.**

Drawing no. / No. du dessin  
**M1004**



**DESCRIPTION OF WORK: NEW WORK**

- 1 PROVIDE NEW VAV BOXES AS INDICATED C/W TEMPERATURE SENSOR AND LOW VOLTAGE WIRING. PROVIDE NEW DUCTWORK TO CONNECT EXISTING DUCTWORK TO VAV BOX AS INDICATED.
- 2 RELOCATE EXISTING VAV THERMOSTAT AS INDICATED. EXTEND PNEUMATIC TUBING AS REQUIRED.
- 3 RELOCATE EXISTING TEMPERATURE SENSOR AS INDICATED. EXTEND CONTROL WIRING AS REQUIRED.
- 4 PROVIDE NEW RETURN GRILLES AS INDICATED. SIZE TO BE 600mm x 200mm UNLESS OTHERWISE NOTED.
- 5 PROVIDE NEW FAN POWERED TERMINALS AS INDICATED C/W DUCTWORK, DIFFUSERS, TEMPERATURE SENSOR AND ASSOCIATED CONTROLS. ELECTRICAL 120V CONNECTION BY ELECTRICAL CONTRACTOR. COORDINATE WITH ELECTRICAL CONTRACTOR.
- 6 CAP AND INSULATE ALL UN-USED DUCT OPENINGS.
- 7 PROVIDE BALANCING FOR ALL DIFFUSERS WHERE SHOWN. ADJUST FAN POWERED BOXES AND VAV BOXES AS INDICATED. SUBMIT BALANCING REPORT FOR DEPARTMENTAL REPRESENTATIVE'S REVIEW.

**10TH FLOOR  
HVAC - NEW WORK**  
1 / M1004 1:100