

L'ENTREPRENEUR DEVRA VÉRIFIER TOUTES LES DIMENSIONS ET LES CONDITIONS SUR LE CHANTIER ET AVISER SANS DÉLAI LE REPRÉSENTANT DU MINISTÈRE DE TOUTE ANOMALIE.
 Contractor to verify all dimensions and conditions on site and immediately notify the departmental representative of all discrepancies.

revisions	description	date
6		
5	ISSUED FOR TENDER	2019/07/12
4	ISSUED FOR TENDER	2019/03/19
3	ISSUED FOR FINAL REVIEW	2019/03/08
2	ISSUED FOR 99% REVIEW	2018/08/29
1	ISSUED FOR DESIGN DEVELOPMENT	2018/09/30

A detail no. / no. du détail
 B location drawing no. / sur dessin no.
 C drawing no. / dessin no.

project / projet
The Re-Fit of L'Esplanade Laurier for Swing Space


140 O'CONNOR ST., OTTAWA, ONTARIO

drawing / dessin
MECHANICAL
10TH FLOOR
FIRE PROTECTION & PLUMBING
DEMOLITION

Designed By	C.L. MAR/17	Conçu par	
Date	MAR/17	(yyyy/mm/dd)	
Drawn By	C.L. MAR/17	Dessiné par	
Date	MAR/17	(yyyy/mm/dd)	
Reviewed By	E.P. MAR/17	Examiné par	
Date	MAR/17	(yyyy/mm/dd)	
Approved By	E.P. MAR/17	Approuvé par	
Date	MAR/17	(yyyy/mm/dd)	
Tender		Soumission	
Project Manager	AHMAD KHODR	Administrateur de projets	
Project no.	R.081640.020.	No. du projet	
Drawing no.	M1001	No. du dessin	

DESCRIPTION OF WORK: DEMOLITION

- CONTRACTOR SHALL BE RESPONSIBLE FOR DEACTIVATION, DRAINING AND REFILLING OF WET PIPE SPRINKLER SYSTEM ON A DAILY BASIS. COORDINATE WITH DEPARTMENTAL REPRESENTATIVE. FIRE ALARM BYPASSING BY DEPARTMENTAL REPRESENTATIVE. ALL SPRINKLER WORK TO BE PERFORMED AFTER-HOURS.
- REMOVE EXISTING SPRINKLERS C/W ASSOCIATED BRANCH PIPING. CAP AND SEAL UN-USED BRANCH PIPING AT MAIN.
- REMOVE EXISTING KITCHEN SINK. REMOVE PLUMBING SERVICES BACK TO WALL FOR FUTURE SINK CONNECTION. PROVIDE TEMPORARY CAPS AS REQUIRED.



10TH FLOOR
FIRE PROTECTION - DEMOLITION
 1:100
 M1001

