

PART 1 - GENERAL**1.1 RELATED REQUIREMENTS**

- .1 Section 09 91 23 - Interior Painting.
- .2 Section 23 05 93 - Testing, Adjusting and Balancing for HVAC.

1.2 ACTION AND INFORMATIONAL SUBMITTALS

- .1 Submit in accordance with Section 01 33 00 - Submittal Procedures.
- .2 Product Data:
 - .1 Submit manufacturer's instructions, printed product literature and data sheets for and include product characteristics, performance criteria, physical size, finish and limitations.
- .3 Shop drawings:
 - .1 Submit drawings stamped and signed by professional engineer registered or licensed in Province of Ontario, Canada.
 - .2 Drawings to show:
 - .1 Mounting arrangements.
 - .2 Operating and maintenance clearances.
 - .3 Drawings and product data accompanied by:
 - .1 Detailed drawings of bases, supports, and anchor bolts.
 - .2 Acoustical sound power data, where applicable.
 - .3 Points of operation on performance curves.
 - .4 Manufacturer to certify current model production.
 - .5 Certification of compliance to applicable codes.
 - .4 In addition to transmittal letter referred to in Section 01 33 00 - Submittal Procedures: use MCAC "Shop Drawing Submittal Title Sheet". Identify section and paragraph number.

1.3 CLOSEOUT SUBMITTALS

- .1 Submit in accordance with Section 01 78 00 - Closeout Submittals.
- .2 Operation and Maintenance Data: submit operation and maintenance data for for incorporation into manual.
 - .1 Operation and maintenance manual approved by, and final copies deposited with, Departmental Representative before final inspection.
 - .2 Operation data to include:
 - .1 Control schematics for systems including environmental controls.
 - .2 Description of systems and their controls.
 - .3 Description of operation of systems at various loads together with reset schedules and seasonal variances.
 - .4 Operation instruction for systems and component.

- .5 Description of actions to be taken in event of equipment failure.
- .3 Maintenance data to include:
 - .1 Servicing, maintenance, operation and trouble-shooting instructions for each item of equipment.
 - .2 Data to include schedules of tasks, frequency, tools required and task time.
- .4 Performance data to include:
 - .1 Equipment manufacturer's performance datasheets with point of operation as left after commissioning is complete.
 - .2 Equipment performance verification test results.
 - .3 Special performance data as specified.
 - .4 Testing, adjusting and balancing reports as specified in Section 23 05 93 - Testing, Adjusting and Balancing for HVAC.
- .5 Approvals:
 - .1 Submit 2 copies of draft Operation and Maintenance Manual to Departmental Representative for approval. Submission of individual data will not be accepted unless directed by Departmental Representative.
 - .2 Make changes as required and re-submit as directed by Departmental Representative.
- .6 Additional data:
 - .1 Prepare and insert into operation and maintenance manual additional data when need for it becomes apparent during specified demonstrations and instructions.
- .7 Submit copies of as-built drawings for inclusion in final TAB report.

1.4 MAINTENANCE MATERIAL SUBMITTALS

- .1 Submit in accordance with Section 01 78 00 - Closeout Submittals.
- .2 Provide one set of special tools required to service equipment as recommended by manufacturers.

1.5 DELIVERY, STORAGE AND HANDLING

- .1 Deliver, store and handle materials in accordance with Section 01 61 00 - Common Product Requirements and with manufacturer's written instructions.
- .2 Delivery and Acceptance Requirements: deliver materials to site in original factory packaging, labelled with manufacturer's name and address.
- .3 Storage and Handling Requirements:
 - .1 Store materials off ground, indoors, in dry location and in accordance with manufacturer's recommendations in clean, dry, well-ventilated area.
 - .2 Store and protect from nicks, scratches, and blemishes.
 - .3 Replace defective or damaged materials with new.

PART 2 - PRODUCTS**2.1 NOT USED**

- .1 Not used.

PART 3 - EXECUTION**3.1 EXAMINATION**

- .1 Verification of Conditions: verify that conditions of substrate previously installed under other Sections or Contracts are acceptable for installation in accordance with manufacturer's written instructions.
 - .1 Visually inspect substrate in presence of Departmental Representative.
 - .2 Inform Departmental Representative of unacceptable conditions immediately upon discovery.
 - .3 Proceed with installation only after unacceptable conditions have been remedied and after receipt of written approval to proceed from Departmental Representative.

3.2 PAINTING REPAIRS AND RESTORATION

- .1 Do painting in accordance with Section 09 91 23 - Interior Painting.
- .2 Prime and touch up marred finished paintwork to match original.
- .3 Restore to new condition, finishes which have been damaged.

3.3 CLEANING

- .1 Progress Cleaning:
 - .1 Leave Work area clean at end of each day.
- .2 Final Cleaning: upon completion remove surplus materials, rubbish, tools and equipment.
- .3 At completion of project, vacuum clean all perimeter heating/cooling units. Include brushing of all coils. Coordinate with building operations for exact schedule & procedure.

3.4 PROTECTION

- .1 Protect equipment and systems openings from dirt, dust, and other foreign materials with materials appropriate to system.

END OF SECTION

PART 1 - GENERAL**1.1 REFERENCES**

- .1 National Fire Prevention Association (NFPA)
 - .1 NFPA (Fire) 13, Standard for the Installation of Sprinkler Systems, 2016 Edition.
 - .2 NFPA (Fire) 20, Standard for the Installation of Stationary Pumps for Fire Protection, 2016
 - .3 NFPA (Fire) 25, Standard for the Inspection, Testing, and Maintenance of Water-Based Fire Protection Systems, 2017 Edition.

1.2 ACTION AND INFORMATIONAL SUBMITTALS

- .1 Provide submittals in accordance with Section 01 33 00 - Submittal Procedures.
- .2 Product Data:
 - .1 Provide manufacturer's printed product literature and data sheets, and include product characteristics, performance criteria, physical size, finish and limitations.
- .3 Shop Drawings:
 - .1 Submit drawings stamped and signed by professional engineer registered or licensed in Province of Ontario, Canada.
 - .2 Indicate:
 - .1 Materials.
 - .2 Finishes.
 - .3 Method of anchorage
 - .4 Number of anchors.
 - .5 Supports.
 - .6 Reinforcement.
 - .7 Assembly details.
 - .8 Accessories.
- .4 Samples:
 - .1 Submit samples of following:
 - .1 Each type of sprinkler head.
 - .2 Signs.
- .5 Test reports:
 - .1 Submit certified test reports for wet pipe fire protection sprinkler systems from approved independent testing laboratories, indicating compliance with specifications for specified performance characteristics and physical properties.
- .6 Certificates:
 - .1 Submit certificates signed by manufacturer certifying that materials comply with specified performance characteristics and physical properties.

- .7 Manufacturers' Instructions:
 - .1 Provide manufacturer's installation instructions.
- .8 Field Quality Control Submittals:
 - .1 Manufacturer's Field Reports: manufacturer's field reports specified.

1.3 CLOSEOUT SUBMITTALS

- .1 Provide operation, maintenance and engineering data for incorporation into manual specified in Section 01 78 00 - Closeout Submittals in accordance with NFPA (Fire) 20.
- .2 Manufacturer's catalogue Data, including specific model, type, and size for:
 - .1 Pipe and fittings.
 - .2 Sprinkler heads.
 - .3 Pipe hangers and supports.
 - .4 Mechanical couplings.
- .3 Records:
 - .1 As-built drawings of each system.
 - .1 After completion, but before final acceptance, submit complete set of as-built drawings of each system for record purposes.
- .4 Operation and Maintenance Manuals:
 - .1 Provide detailed hydraulic calculations including summary sheet, and Contractors Material and Test Certificate for aboveground and underground piping and other documentation for incorporation into manual in accordance with NFPA (Fire) 13.

1.4 QUALITY ASSURANCE

- .1 Qualifications:
 - .1 Installer: company or person specializing in wet sprinkler systems with documented experience.
- .2 Supply grooved joint couplings, fittings, grooving tools and specialties from a single manufacturer. Use date stamped castings for coupling housings, fittings for quality assurance and traceability.

1.5 MAINTENANCE MATERIAL SUBMITTALS

- .1 Extra Materials:
 - .1 Provide maintenance materials in accordance with Section 01 78 00 - Closeout Submittals.
 - .2 Provide spare sprinklers and tools in accordance with NFPA (Fire) 13.

1.6 DELIVERY, STORAGE AND HANDLING

- .1 Deliver, store and handle materials in accordance with Section 01 61 00 - Common Product Requirements and with manufacturer's written instructions.
- .2 Delivery and Acceptance Requirements:
 - .1 Deliver materials to site in original factory packaging, labelled with manufacturer's name, address.
- .3 Storage and Protection:
 - .1 Store materials indoors in dry location.
 - .2 Store and protect materials from exposure to harmful weather conditions and at temperature and humidity conditions recommended by manufacturer.
- .4 Packaging Waste Management: remove for reuse and return by manufacturer of pallets, crates, padding, and packaging materials in accordance with Section 01 74 21 - Construction/Demolition Waste Management and Disposal.

PART 2 - PRODUCTS

2.1 DESIGN REQUIREMENTS

- .1 Design automatic wet pipe fire suppression sprinkler systems in accordance with required and advisory provisions of NFPA (Fire) 13, by pipe schedules for light hazard occupancy or hydraulic calculations for uniform distribution of water over design area.
- .2 Include with each system materials, accessories, and equipment inside and outside building to provide each system complete and ready for use.
- .3 Design and provide each system to give full consideration to blind spaces, piping, electrical equipment, ducts, and other construction and equipment in accordance with detailed shop drawings.
- .4 Locate sprinkler heads in consistent pattern with ceiling grid, lights, and air supply diffusers.
- .5 Devices and equipment for fire protection service: ULC approved for use in wet pipe sprinkler systems.
- .6 Location of Sprinkler Heads:
 - .1 Locate heads in relation to ceiling and spacing of sprinkler heads not to exceed that permitted by NFPA (Fire) 13 for light hazard occupancy.
 - .2 Uniformly space sprinklers on branch.

2.2 ABOVE GROUND PIPING SYSTEMS

- .1 Provide fittings for changes in direction of piping and for connections.
 - .1 Make changes in piping sizes through tapered reducing pipe fittings, bushings will not be permitted.
- .2 Perform welding in shop; field welding will not be permitted.
- .3 Conceal piping in areas with suspended ceiling.

2.3 PIPE, FITTINGS AND VALVES

- .1 Pipe:
 - .1 Ferrous: to NFPA (Fire) 13.
 - .2 Copper tube: to NFPA (Fire) 13.
- .2 Fittings and joints to NFPA (Fire) 13:
 - .1 Ferrous: screwed, welded, flanged or roll grooved.
 - .1 Grooved joints designed with two ductile iron housing segments, pressure responsive gasket, and zinc-electroplated steel bolts and nuts. Cast with offsetting angle-pattern bolt pads for rigidity and visual pad-to-pad offset contact.
 - .2 Copper tube: screwed, soldered, brazed, grooved.
 - .3 Provide welded, threaded, grooved-end type fittings into which sprinkler heads, sprinkler head riser nipples, or drop nipples are threaded.
 - .4 Plain-end fittings with mechanical couplings and fittings which use steel gripping devices to bite into pipe when pressure is applied will not be permitted.
 - .5 Rubber gasketed grooved-end pipe and fittings with mechanical couplings are permitted in pipe sizes 32 mm and larger.
 - .6 Fittings: ULC approved for use in wet pipe sprinkler systems.
 - .7 Ensure fittings, mechanical couplings, and rubber gaskets are supplied by same manufacturer.
 - .8 Side outlet tees using rubber gasketed fittings are not permitted.
 - .9 Sprinkler pipe and fittings: metal.
- .3 Pipe hangers:
 - .1 ULC listed for fire protection services in accordance with NFPA.

2.4 SPRINKLER HEADS

- .1 General: to NFPA (Fire) 13 and ULC listed for fire services.
- .2 Sprinkler Head Type:
 - .1 Type A: Pendant chrome glass bulb type.

PART 3 - EXECUTION**3.1 MANUFACTURER'S INSTRUCTIONS**

- .1 Compliance: comply with manufacturer's written recommendations or specifications, including product technical bulletins, handling, storage and installation instructions, and datasheet.

3.2 INSTALLATION

- .1 Install, inspect and test to acceptance in accordance with NFPA (Fire) 13 and NFPA (Fire) 25.

3.3 PIPE INSTALLATION

- .1 Install piping straight and true to bear evenly on hangers and supports. Do not hang piping from plaster ceilings.
- .2 Keep interior and ends of new piping and existing piping thoroughly cleaned of water and foreign matter.
- .3 Keep piping systems clean during installation by means of plugs or other approved methods. When work is not in progress, securely close open ends of piping to prevent entry of water and foreign matter.
- .4 Inspect piping before placing into position.

3.4 CONNECTIONS TO EXISTING WATER SUPPLY SYSTEMS

- .1 Notify Contracting Officer in writing at least 15 days prior to connection date.
- .2 Use tapping or drilling machine valve and mechanical joint type sleeves for connections to be made under pressure.
- .3 Bolt sleeves around main piping.
- .4 Bolt valve to branch connection. Open valve, attach drilling machine, make tap, close valve, and remove drilling machine, without interruption of service.
- .5 Furnish materials required to make connections into existing water supply systems.

3.5 FIELD QUALITY CONTROL

- .1 Site Test, Inspection:
 - .1 Perform test to determine compliance with specified requirements in presence of Departmental Representative.
 - .2 Test, inspect, and approve piping before covering or concealing.
 - .3 Preliminary Tests:
 - .1 Hydrostatically test each system at 200 psig for a 2 hour period with no leakage or reduction in pressure.
 - .2 Flush piping with potable water in accordance with NFPA (Fire) 13.
 - .3 Piping above suspended ceilings: tested, inspected, and approved before installation of ceilings.
 - .4 Test alarms and other devices.
 - .5 Test water flow alarms by flowing water through inspector's test connection. When tests have been completed and corrections made, submit signed and dated certificate in accordance with NFPA (Fire) 13.
 - .4 Formal Tests and Inspections:
 - .1 Do not submit request for formal test and inspection until preliminary test and corrections are completed and approved.
 - .2 Submit written request for formal inspection at least 15 days prior to inspection date.
 - .3 Repeat required tests as directed.
 - .4 Correct defects and make additional tests until systems comply with contract requirements.
 - .5 Furnish appliances, equipment, instruments, connecting devices, and personnel for tests.
 - .6 Authority of Jurisdiction, will witness formal tests and approve systems before they are accepted.

3.6 CLEANING

- .1 Remove surplus materials, excess materials, rubbish, tools and equipment.

END OF SECTION