

1 - GENERAL

1.01 DESCRIPTION

- .1 This section specifies requirements for demolishing and removing wholly or in part various items designated to be removed or partially removed.
- .2 Demolition and removal will consist of, but not necessarily be limited to, the following:
 - .1 Disconnection of existing electrical located on the existing H pile floating wharves anchor system. Reinstallation of the electrical on the Newly installed steel wale system.
 - .2 Installation of the existing aluminum gangway stored on the floating wharves to the existing anchor connections on the reinforced concrete wharf deck.
- .3 Mobilization and Demobilization of all equipment necessary to make work progress for the entire contract.

1.02 GENERAL REQUIREMENTS

- .1 A Notice to Shipping is to be issued prior to commencement and upon completion of work.
- .2 During construction, any vessels or barges utilized must be marked in accordance with the provisions of the Canada Shipping Act Collision Regulations.
- .3 Upon completion of the project, a written Notice to Mariners must be issued.

1.03 PROTECTION

- .1 Protect existing objects designated to remain. In event of damage, immediately replace or make repairs to approval of and at no additional cost to Canada.
- .2 Remove all floating debris from water on a routine and timely basis.

1.04 MEASUREMENT FOR PAYMENT

- .1 Removal and Reinstallation or disposal for construction operations will include:
 - .1 Disconnection of existing floating wharves from the H pile anchor system. Secure the floating wharves at a location to be able to access the yokes for their replacement.
 - .2 Disconnection of existing electrical, located on top of the H pile anchor system, reinstallation of electrical on New Steel Wale

System as indicated on the drawings.

- .3 Installation of the gangway to the existing anchor located on the concrete reinforced deck of the wharf. Please note that the aluminum gangway is currently stored on the floating wharves
- .4 All items as specified in this section will be paid by lump sum.
- .2 Removal of all other items required for the progress of the work will not be measured separately for payment, it will be considered incidental to this contract.
- .3 Mobilization and Demobilization of all equipment necessary to make work progress for the entire contract will be included in the lump sum price under this section.

2 - PRODUCTS

NOT APPLICABLE

3 - EXECUTION

3.01 EXECUTION

- .1 Inspect site and verify with Departmental Representative objects designated for removal.
- .2 Locate and protect utility lines. Preserve in operating condition active utilities traversing site.

3.02 REMOVAL

- .1 Remove in their entirety all materials and objects specified for removal.
- .2 Do not disturb adjacent work designated to remain in place.

3.03 DISPOSAL OF MATERIAL

- .1 All demolished materials, except materials designated to be reused, will become property of contractor and will be removed from site and disposed of to the satisfaction of Departmental Representative and in accordance with environmental guidelines. It is the sole responsibility of the contractor to dispose of all demolished materials at an approved disposal site. Ensure that disposal site is approved and willing to accommodate any materials disposed of from work site.
- .2 Contractor shall obtain and pay for all necessary permits and disposal fees for use of an approved waste disposal site.

3.04 RESTORATION

PWGSC
FLOATING WHARF ANCHOR
SYSTEM REPLACEMENT
STUARTTOWN WHARF
DEER ISLAND, N.B.
PROJECT NO. R.104006.001

SITework, DEMOLITION
AND REMOVAL

Section 02 41 16
Page 3

- .1 Upon completion of work, remove debris, trim surfaces and leave work site in clean condition.
- .2 Reinstall areas and existing works outside areas of demolition to conditions that existed prior to commencement of work.

END OF SECTION