

## 1 - GENERAL

### 1.01 DESCRIPTION

- .1 This section specifies the general requirements for the reinstallation of Floating wharves to the newly placed steel pipe piles. Installation of the floating wharves as indicated on the plan.

### 1.02 RELATED WORK

- .1 Section 05 50 00 - Miscellaneous Metals
- .2 Section 31 63 19 - Bored and Socketed Piles

### 1.03 MEASUREMENT FOR PAYMENT

- .1 Payment for floating wharves installation will be made by the lump sum. This will include the furnishing, all equipment necessary for the complete floating wharves installation, to the locations shown on the plans.

### 1.04 DELIVERY AND HANDLING

- .1 Protect floating wharves from damage due to excessive bending stresses, impact, or other causes during handling.
- .2 Protect public and construction personnel, adjacent structures and work of other sections from hazards attributable to handling and moving of new floating wharves.

## 2 - PRODUCTS

### 2.01 MATERIALS

- .1 Floating wharves are currently anchored to the H pile anchor system, at Stuarttown Wharf, Deer Island, New Brunswick.

## 3 - EXECUTION

### 3.01 INSTALLATION OF FLOATS

- .1 Method of pickup and placing of floating wharves in water is to be submitted as per section 01 33 00, for the Departmental Representative's review.
- .2 Any damage during launching is to be repaired and paid by the Contractor,

---

PWGSC  
FLOATING WHARF ANCHOR  
SYSTEM REPLACEMENT  
STUARTTOWN WHARF  
DEER ISLAND, N.B.  
PROJECT NO. R.104006.001

---

FLOAT INSTALLATION

Section 35 51 24

Page 2

at no additional cost to the Crown.

### 3.02 FLOATING WHARVES ANCHORAGE

.1 Floating wharves are to be installed as indicated on the plan.

**END OF SECTION**