

| Item | Specification Reference | Class of Labour, Plant or Materials | Unit of Measurements | Estimated Quantity | Estimate per Unit | Extended Amount |
|------|-------------------------|---|----------------------|--------------------|-------------------|-----------------|
| 0,1 | | Mobilization and demobilization | L.S. | | | |
| 0,2 | 01 29-00 | Sitework, demolition and removal of existing armourstone, filterstone and timber sheathing, wales and ladders. Reinstatement of timber wales, sheathing and ladders | L.S. | | | |
| 0,3 | 01 29-00 | Load, supply, installation and compaction of approved core material (R 25). | L.S. | | | |
| 0,4 | 01 29-00 | Load, supply and installation of approved clear stone. | CMPM | 25 | | |
| 0,5 | 01 29-00 | Load, supply, installation and compaction of approved Type 1 gravel. | CMPM | 32 | | |
| 0,6 | 01 29-00 | Fabrication, supply and installation of pre-cast reinforced concrete slabs | units | 5 | | |
| 0,7 | 01 29-00 | Installation of cast-in-place reinforced concrete slab. | m3 | 26 | | |
| 0,8 | 01 29-00 | Supply and Installation of filter fabric | L.S. | | | |
| 0,9 | 01 29-00 | Load, supply and placement of rip rap (shore and scour protection). | CMTM | 425 | | |
| | | | | | | |