

PART 1 GENERAL

1.1 ACCESS AND EGRESS

- .1 Design, construct and maintain temporary "access to" and "egress from" work areas, including stairs, runways, ramps or ladders and scaffolding, independent of finished surfaces and in accordance with relevant municipal, provincial and other regulations.

1.2 USE OF SITE AND FACILITIES

- .1 Execute work with least possible interference or disturbance to normal use of premises. Make arrangements with Departmental Representative to facilitate work as stated.
- .2 Maintain existing services to building and provide for personnel and vehicle access.
- .3 Where security is reduced by work provide temporary means to maintain security.
- .4 Closures: protect work temporarily until permanent enclosures are completed.
- .5 For outside work place barricades before the Apron and include signs "No Workers Beyond This Point".
- .6 Transport Canada work hours are 0700-1800. If Contractor forces are required to work outside these hours, Contractor is responsible to hire Commissionaire escort.

1.3 ALTERATIONS, ADDITIONS OR REPAIRS TO EXISTING BUILDING

- .1 Execute work with least possible interference or disturbance to building operations, occupants, public and normal use of premises. Arrange with Departmental Representative to facilitate execution of work with 48 hour notice.

1.4 EXISTING SERVICES

- .1 Notify, Departmental Representative and utility companies of intended interruption of services and obtain required permission.
- .2 Where Work involves breaking into or connecting to existing services, give Departmental Representative 48 hours of notice for necessary interruption of mechanical or electrical service throughout course of work. Keep duration of interruptions to a minimum. Carry out interruptions after normal working hours of occupants, preferably on weekends.
- .3 Construct barriers in accordance with Section 01 56 00 - Temporary Barriers and Enclosures.
- .4 Existing services located on the building that will interfere with the removal and installation of the new cladding shall be removed and reinstalled without any damage to the existing services. Contractor shall remove and reinstall the Service supports to facilitate the work. Contractor is responsible for engaging Newfoundland Power to disconnect and reconnect electrical service. All electrical work to be performed by a certified electrician. Electrical work shall be performed in accordance with the Canadian

Electrical Code. Contractor must coordinate shut-down of services with the Departmental Representative, in form of a written procedure 48 hours prior to scheduled shutdown. No work is to be carried out unless approved by the Departmental Representative.

1.5 SPECIAL REQUIREMENTS

- .1 Submit schedule in accordance with Section 01 32 16.07 - Construction Progress Schedule - Bar (GANTT) Chart.
- .2 Ensure Contractor's personnel employed on site become familiar with and obey regulations including safety, fire, traffic and security regulations.
- .3 Keep within limits of work and avenues of ingress and egress.
- .4 Coordinate the location and use of garbage bins with other Contractors on site.

1.6 SECURITY

- .1 Where security has been reduced by Work of Contract, provide temporary means to maintain security.
- .2 All workers will be issued airport security passes and given mandatory airport safety & security training.

1.7 BUILDING SMOKING ENVIRONMENT

- .1 Comply with smoking restrictions. Smoking is not permitted.

PART 2 PRODUCTS

2.1 NOT USED

- .1 Not Used.

PART 3 EXECUTION

3.1 NOT USED

- .1 Not Used.

END OF SECTION