

PART 1 GENERAL

1.1 RELATED SECTIONS

- .1 Section 02 41 16 – Structure Demolition
- .2 Section 31 05 16 – Aggregates for Earthwork.
- .3 Section 31 23 16.26 – Rock Removal.
- .4 Section 33 11 16 - Site Water Utility Distribution Piping.
- .5 Section 31 25 05 – Excavating, Trenching and Backfilling.
- .6 Section 31 32 00 - Erosion and Sediment Control

1.2 REFERENCES

- .1 American Society for Testing and Materials International (ASTM)
 - .1 ASTM C136-14, Standard Test Method for Sieve Analysis of Fine and Coarse Aggregates.
 - .2 ASTM D422-63(2007) E2, Standard Test Method for Particle-Size Analysis of Soils.
 - .3 ASTM D698-12e2, Standard Test Methods for Laboratory Compaction Characteristics of Soil Using Standard Effort (12,400 ft-lbf/ft ;) (600 kN-m/m ;).
 - .4 ASTM D4318-17e1, Standard Test Methods for Liquid Limit, Plastic Limit, and Plasticity Index of Soils.
- .2 Canadian General Standards Board (CGSB)
 - .1 CAN/CGSB-8.2-M88, Sieves, Testing, Woven Wire, Metric.

1.3 DEFINITIONS

- .1 Excavation classes: two classes of excavation will be recognized; common excavation and rock excavation.
 - .1 Rock: excavation of material from solid masses of igneous, sedimentary or metamorphic rock which, prior to its removal, was integral with its parent mass, and boulders or rock fragments having individual volume in excess of 1.0 m³. Frozen material not classified as rock.
 - .2 Common excavation: excavation of materials of whatever nature, which are not included under definitions of rock excavation.
- .2 Unclassified excavation: excavation of deposits of whatever character encountered in Work.
- .3 Topsoil:
 - .1 Material capable of supporting good vegetative growth and suitable for use in top dressing, landscaping and seeding.
 - .2 Material reasonably free from subsoil, clay lumps, brush, objectionable weeds, and other litter, and free from cobbles, stumps, roots, and other objectionable material larger than 25 millimeters in any dimension.
- .4 Waste material: excavated material unsuitable for use in Work or surplus to requirements.

- .5 Borrow material: material obtained from locations outside area to be graded, and required for construction of fill areas or for other portions of Work.
- .6 Recycled fill material: material, considered inert, obtained from alternate sources and engineered to meet requirements of fill areas.
- .7 Unsuitable materials:
 - .1 Weak, chemically unstable, and compressible materials.
 - .2 Frost susceptible materials under excavated areas.
 - .3 Frost susceptible materials:
 - .1 Fine grained soils with plasticity index less than 10 when tested to ASTM D4318, and gradation within limits specified when tested to ASTM D422 and ASTM C136 : Sieve sizes to CAN/CGSB-8.2.
 - .2 Table:

<u>Sieve Designation</u>	<u>% Passing</u>
2.00 mm	100
0.10 mm	45 – 100
0.02 mm	10 - 80
0.005 mm	0 - 45
 - .3 Coarse grained soils containing more than 20% by mass passing 0.075 mm sieve.

1.4 SUBMITTALS

- .1 Make submittals in accordance with Section 01 33 00 - Submittal Procedures.

1.5 EXISTING CONDITIONS

- .1 Buried services:
 - .1 Before commencing work verify location of buried services on and adjacent to site.
 - .2 Arrange with appropriate authority for relocation of buried services that interfere with execution of work: pay costs of relocating services.
 - .3 Size, depth and location of existing utilities and structures as indicated are for guidance only. Completeness and accuracy are not guaranteed.
 - .4 Prior to beginning excavation Work, notify applicable authorities having jurisdiction, establish location and state of use of buried utilities and structures. Authorities having jurisdiction to clearly mark such locations to prevent disturbance during Work.
 - .5 Confirm locations of buried utilities by careful test excavations.
 - .6 Maintain and protect from damage, water, sewer, gas, electric, telephone and other utilities and structures encountered as indicated.
 - .7 Where utility lines or structures exist in area of excavation, obtain direction of Department Representative before removing or re-routing.
 - .8 Record location of maintained, re-routed and abandoned underground lines.
 - .9 Confirm locations of recent excavations adjacent to area of excavation.
- .2 Existing buildings and surface features:

- .1 Conduct, with Departmental Representative, condition survey of existing buildings, trees and other plants, lawns, fencing, service poles, wires, rail tracks, pavement, survey bench marks and monuments which may be affected by Work.
- .2 Protect existing buildings and surface features from damage while Work is in progress. In event of damage, immediately make repair as directed by Department Representative.

PART 2 PRODUCTS

2.1 MATERIALS

- .1 Type 1 and Type 2 fill: properties to the following requirements:
 - .1 Crushed, pit run or screened stone, gravel or sand.
 - .2 Gradations to be within limits specified when tested to ASTM C136 and ASTM C117. Sieve sizes to CAN/CGSB-8.2.
 - .3 Table:

<u>Sieve Designation</u>	<u>% Passing</u>	
	<u>Type 1</u>	<u>Type 2</u>
75 mm	-	100
50 mm	-	-
37.5 mm	-	-
25 mm	100	-
19 mm	75-100	-
12.5 mm	-	-
9.5 mm	50-100	-
4.75 mm	30-70	22-85
2.00 mm	20-45	-
0.425 mm	10-25	5-30
0.180 mm	-	-
0.075 mm	3-8	0-10
- .2 Type 3 fill: selected material from excavation or other sources, approved by Department Representative for use intended, unfrozen and free from rocks larger than 75 mm, cinders, ashes, sods, refuse or other deleterious materials.
- .3 Engineered fill: as per recommendations of geotechnical report.

PART 3 EXECUTION

3.1 SITE PREPARATION

- .1 Remove obstructions, ice and snow, from surfaces to be excavated within limits indicated.
- .2 Cut pavement or sidewalk neatly along limits of proposed excavation in order that surface may break evenly and cleanly.

3.2 PREPARATION/PROTECTION

- .1 Protect existing features in accordance with Section 01 56 00 - Temporary Barriers and Enclosures and applicable local regulations.

- .2 Keep excavations clean, free of standing water, and loose soil.
- .3 Where soil is subject to significant volume change due to change in moisture content, cover and protect to Department Representative approval.
- .4 Protect natural and man-made features required to remain undisturbed. Unless otherwise indicated or located in an area to be occupied by new construction, protect existing trees from damage.
- .5 Protect buried services that are required to remain undisturbed.

3.3 STRIPPING OF TOPSOIL

- .1 Begin topsoil stripping of areas as directed by Department Representative after area has been cleared of brush, weeds and grasses and removed from site.
- .2 Stockpile in locations as indicated as directed by Department Representative.
 - .1 Stockpile height not to exceed 2 m and should be protected from erosion.
- .3 Dispose of unused topsoil to location as indicated as directed by Departmental Representative off site.

3.4 STOCKPILING

- .1 Stockpile fill materials in areas designated by Departmental Representative.
 - .1 Stockpile granular materials in manner to prevent segregation.
- .2 Protect fill materials from contamination.
- .3 Implement sufficient erosion and sediment control measures to prevent sediment release off construction boundaries and into water bodies.

3.5 SHORING, BRACING AND UNDERPINNING

- .1 Maintain sides and slopes of excavations in safe condition by appropriate methods and in accordance with Section 01 35 29.06 - Health and Safety Requirements and Health and Safety Act for the Province of Newfoundland and Labrador.
- .2 Construct temporary Works to depths, heights and locations as indicated or approved by Department Representative.
- .3 During backfill operation:
 - .1 Unless otherwise indicated or directed by Department Representative, remove shoring from excavations.
 - .2 Do not remove bracing until backfilling has reached respective levels of such bracing.
- .4 Upon completion of substructure construction:
 - .1 Remove shoring and bracing.

3.6 DEWATERING AND HEAVE PREVENTION

- .1 Keep excavations free of water while Work is in progress.
- .2 Provide for Department Representative's review details of proposed dewatering or heave prevention methods, including dikes, well points, and sheet pile cut-offs.
- .3 Avoid excavation below groundwater table if quick condition or heave is likely to occur.

- .1 Prevent piping or bottom heave of excavations by groundwater lowering, sheet pile cut-offs, or other means.
- .4 Protect open excavations against flooding and damage due to surface run-off.
- .5 Dispose of water in accordance with Section 01 35 43 - Environmental Procedures and in a manner not detrimental to public and private property, or portion of Work completed or under construction.
 - .1 Provide and maintain temporary drainage ditches and other diversions outside of excavation limits.
- .6 Provide flocculation tanks, settling basins, or other treatment facilities to remove suspended solids or other materials before discharging to storm sewers, watercourses or drainage areas.

3.7 EXCAVATION

- .1 Excavate to lines, grades, elevations and dimensions as indicated by Department Representative.
- .2 Excavation must not interfere with bearing capacity of adjacent foundations.
- .3 Keep excavated and stockpiled materials safe distance away from edge of trench as directed by Department Representative.
- .4 Restrict vehicle operations directly adjacent to open trenches.
- .5 Dispose of surplus and unsuitable excavated off site.
- .6 Do not obstruct flow of surface drainage or natural watercourses.
- .7 Earth bottoms of excavations to be undisturbed soil, level, free from loose, soft or organic matter.
- .8 Notify Department Representative when bottom of excavation is reached.
- .9 Obtain Department Representative approval of completed excavation.
- .10 Remove unsuitable material from excavation bottom to extent and depth as directed by Department Representative.
- .11 Correct unauthorized over-excavation as follows:
 - .1 Fill under bearing surfaces and footings with concrete specified for footings.
 - .2 Fill under other areas with Type 2 fill compacted to not less than 98% of corrected Standard Proctor maximum dry density.
- .12 Hand trim, make firm and remove loose material and debris from excavations.
 - .1 Where material at bottom of excavation is disturbed, compact foundation soil to density at least equal to undisturbed soil.
 - .2 Clean out rock seams and fill with concrete mortar or grout to approval of Department Representative.

3.8 FILL TYPES AND COMPACTION

- .1 Use types of fill as indicated or specified below. Compaction densities are percentages of maximum densities obtained from ASTM D698.

- .1 Exterior side of perimeter walls: use Type 3 fill to subgrade level. Compact to 95% of corrected maximum dry density.
- .2 Within building area: use Type 3 fill to underside of base course for floor slabs. Compact to 100 % of corrected maximum dry density.
- .3 Under concrete slabs: provide 150mm compacted thickness base course of Type 1 fill to underside of slab. Compact base course to 100%.
- .4 Underside of foundations: use Type 3 fill compacted to 100 %.
- .5 Engineered fill: as per the recommendations of the geotechnical report.

3.9 BACKFILLING

- .1 Vibratory compaction equipment: approved by Department Representative.
- .2 Do not proceed with backfilling operations until completion of following:
 - .1 Department Representative has inspected and approved installations.
 - .2 Department Representative has inspected and approved of construction below finish grade.
 - .3 Removal of concrete formwork.
 - .4 Removal of shoring and bracing; backfilling of voids with satisfactory soil material.
- .3 Areas to be backfilled to be free from debris, snow, ice, water and frozen ground.
- .4 Do not use backfill material which is frozen or contains ice, snow or debris.
- .5 Place backfill material in uniform layers not exceeding 300 mm compacted thickness up to grades indicated. Compact each layer before placing succeeding layer.

3.10 RESTORATION

- .1 Upon completion of Work, remove waste materials and debris, trim slopes, and correct defects as directed by Department Representative
- .2 Reinstate pavements and sidewalks disturbed by excavation to thickness, structure and elevation which existed before excavation.
- .3 Clean and reinstate areas affected by Work as directed by Department Representative.

END OF SECTION