
PART 1 GENERAL

1.1 INSTALLATION AND REMOVAL

- .1 Provide temporary controls in order to execute Work expeditiously.
- .2 Remove from site all such work after use.

1.2 1.2 GUARD RAILS AND BARRICADES

- .1 Provide secure, rigid guard rails and barricades around open edges of floors and roofs.
- .2 Provide as required by governing authorities.

1.3 WEATHER ENCLOSURES

- .1 Provide weather tight closures to unfinished door and window openings, and other openings in roofs.
- .2 Close off floor areas where walls are not finished; seal off other openings; enclose building interior work for temporary heat.
- .3 Design enclosures to withstand wind pressure and snow loading.

1.4 DUST TIGHT SCREENS

- .1 Provide dust tight screens to localize dust generating activities, and for protection of workers, finished areas of Work and public.
- .2 Maintain and relocate protection until such work is complete.

1.5 PROTECTION FOR OFF-SITE AND PUBLIC PROPERTY

- .1 Protect surrounding private and public property from damage during performance of Work.
- .2 Be responsible for damage incurred.

1.6 PROTECTION OF BUILDING FINISHES

- .1 Provide protection for finished and partially finished building finishes and equipment during performance of Work.
- .2 Provide necessary screens, covers, and hoardings.
- .3 Confirm with Departmental Representative locations and installation schedule 3 days prior to installation.
- .4 Be responsible for damage incurred due to lack of or improper protection.

PART 2 PRODUCTS

2.1 NOT USED

PART 3 EXECUTION

3.1 NOT USED

END OF SECTION