

GENERAL NOTES:

1. CEILING SPACES BELOW LEVEL 2 TO RECEIVE SPRAY FIRE PROOFING, WHETHER EXPOSED OR ABOVE FINISHED CEILING(S). (REFER TO SPECIFICATION).
2. CEILING GRID/TELES TO BE CENTERED IN ALL ROOMS UNLESS NOTED OTHERWISE. PARTIAL TILES AT ROOM PERIMETERS SHALL NOT BE LESS THAN 100mm IN EITHER DIMENSION.
3. ALL SINGLE CEILING ELEMENTS (IE. TILES, DIFFUSERS, EXIT SIGNS, SMOKE DETECTORS, MISCELLANEOUS LIGHTS, ETC.) TO BE PLACED IN CENTRAL AREAS OF CEILING OR OFF-CENTRAL BOARD CELLS UNLESS NOTED OTHERWISE. (IN ALL MULTIPLE TILES CENTRE OR CELLS).
4. SEE ELECTRICAL DRAWINGS FOR THE LOCATIONS OF CEILING MOUNTED SMOKE DETECTORS, EXIT SIGNAGE, FIRE ALARM DEVICES, ETC. ALSO SEE ELECTRICAL FOR LOCATIONS FOR LIGHT MOUNTED EXIT LIGHTS.
5. SEE MECHANICAL DRAWINGS FOR EXTENT OF EXPOSED DUCTWORK IN EXPOSED STRUCTURE AREAS. PAINT EXPOSED DUCTWORK, PIPING, HANGERS, ETC.
6. INSTALL ACCESS PANELS IN NON-ACCESSIBLE TIE CELLS WHERE SERVICE OR ADJUSTMENT TO MECHANICAL, PLUMBING, OR ELECTRICAL ITEMS MAY BE REQUIRED. ACCESS PANELS SHALL BE EQUAL TO THE RATING OF THE WALL OR CEILING IN WHICH THEY LOCATED.
7. 450mm MINIMUM CLEARANCE SHALL BE MAINTAINED BETWEEN THE BOTTOM OF THE EXTENDED SPRINKLER HEADS AND THE TOP OF ANY WALLS, HANGING LOCKERS, ETC.
8. SEE ROOM FINISH SCHEDULE FOR CEILING HEIGHTS IN EACH ROOM/AREA. FOR ROOM AREAS DENOTED AS "EX," CEILING TO BE INSTALLED AT SAME HEIGHT AS EXISTING.



C02	ISSUED FOR TENDER	02/14 2019
C01	ISSUED FOR TENDER	03/28 2018
revision		date
project		project
<p>MAINTENANCE GARAGE REHABILITATION ST. ANTHONY AIRPORT</p>		
drawing		details
<p>REFLECTED CEILING PLAN AND FIRE-SEPARATION PLAN LEVEL 2</p>		
designed N.S.		comp
date 2016.11.22		
drawn A.M.		designed
date 2016.11.22		
approved K.S. H.P.		approved
date 2016.11.22		
Project		Seitization
<p>PFSC Project Manager Administrateur de projet PFSC</p>		
project number		no. du projet
<p>R.077269.001</p>		
drawing no.		no. du dessin
<p>A16</p>		