

**The following changes in the bid documents are effective immediately. This addendum will form part of the contract documents.**

Section 02 41 16.01 – Structure Demolition

Part 1

**1.1** Specification Section 1.2.1

**.1** Refer to article

**.1** Delete Section 1.2.1.3 in its entirety.

**.2** Replace with the following:

Removal of top portions of CSP/timber piles and timber fender piles, including connections and concrete encasement, as required.

**.2** Refer to article

**.1** Add Section 1.2.1.7 with the following:

Removal of timber fender piles to harbour bed at northeast end of existing structure (15 total; 8 below water level). Timber fender piles extend below harbour bed, to a minimum of -5.1 m below Chart Datum.