

#### **ADDENDUM No. 4**

Project Number R.077178.001

Page 1 of 1

#### **SPECIFICATIONS**

1. Add Specification Section 26 13 02 Outdoor Pad Mount Sectionalizer 26 13 02 to the Specification.

#### **QUESTION AND RESPONSE**

ID	QUESTION	RESPONSE
32	With Reference to Transformer Drawing E 1.1: Are the 2-600A switches shown in the one line actually 8.3 kv 3 phase disconnects as per 2.1.11 or are they referring to 600a load break elbows? I think if they actually want HV disconnects there would be another switching unit/vault beside the transformer. The same question would be applicable on the sectionalizers as well.	The unfused incoming and outgoing switches noted in each transformer can be "600A load break elbows" to avoid unnecessary switching units/vaults beside each transformer and the costs associated.
33	Do they have a design for terminating all 3 incoming and outgoing 8.3 kv cables at each location? The same question would be applicable on the sectionalizers as well.	The contractor is to follow manufacturer's instructions and the requirements of the Code.