

Solicitation No. - N° de l'invitation
F2930-190028/A

Amd. No. - N° de la modif.
004

Buyer ID - Id de l'acheteur
pwl012

Client Ref. No. - N° de réf. du client
722283

File No. - N° du dossier
PWL-9-42059

CCC No./N° CCC - FMS No./N° VME

QUESTIONS AND ANSWERS

Q1. Turbidity curtain is called for in the specifications but not shown on the drawings.... As this job is in the winter months and ice is inevitable making the installation of the curtain unrealistic and impossible to maintain.

R1. Refer to Section 35 49 25, Clause 1.5.1.

Q2. Pile Cap is called to be epoxy coated before installation, this is unrealistic as the coating will be severely damaged during installation. Can the cap be coated after installation?

R2. Refer to Addendum 4.

Q3. Sect 31 23 33.01 sub 3.4.2 – areas to be backfilled to be free from debris, snow ice, water and frozen ground – is the sheet piled structure expected to be dewatered during backfilling?

R3. No, dewatering is not expected during backfilling.

Q4. Drawing S-02 - P1, can the trees in this picture be removed.

R4. No, these trees cannot be removed. Refer to Section 01 35 43, Clause 1.5.1, and Section 31 11 00, Clause 1.1.1.

Q5. Mobilization/Demobilization has large costs involved, will there be a pay item added in the Price Form?

R5. No a separate pay item will not be added. Refer to Section 01 11 02, Clause 1.8.1.

Q6. Removals of the existing structure has large costs involved, will there be a pay item added in the Price Form?

R6. No a separate pay item will not be added. Refer to Section 02 41 16.01, Clause 1.2.1