



- GENERAL NOTES
1. EXISTING LUMINAIRES AND SMOKE DETECTORS (AND OTHER DEVICES WHERE APPLICABLE) SHOWN WITHIN CELLS TO BE REMOVED AND NEW LUMINAIRES AND SMOKE DETECTORS (AND OTHER DEVICES WHERE APPLICABLE) TO BE INSTALLED AT SAME LOCATION AFTER NEW CEILING INSTALLATION HAS OCCURRED.
 2. EXISTING LUMINAIRES AND SMOKE DETECTORS (AND OTHER DEVICES WHERE SHOWN) TO BE RE-INSTALLED AT SAME LOCATION AFTER NEW CEILING INSTALLATION HAS OCCURRED.
 3. FIRE ALARM SYSTEMS TO BE RE-VERIFIED UPON COMPLETION OF EACH PHASE.

