

**Harbour Improvements****Half Island Cove****Guysborough County Nova Scotia****Project No. R.103901.001**

## Aggregates General

Page 1

PART 1 - GENERAL

- 1.1 Related Work
- .1 Refer to other Specification Sections for related information.
  - .2 Refer to **Section 01 33 00** for Shop Drawing/Submission requirements.
- 1.2 Source Approval
- .1 Source of materials to be incorporated into work or stockpiled requires acceptance.
  - .2 Inform *Departmental Representative* of proposed source of aggregates and provide access for sampling at least 4 weeks prior to commencing production.
  - .3 If, in opinion of *Departmental Representative*, materials from the proposed source do not meet, or cannot reasonably be processed to meet specified requirements, procure an alternative source to demonstrate that materials from source in question can be processed to meet specified requirements.
  - .4 Should a change of material source be proposed during work, advise *Departmental Representative* 4 weeks in advance of proposed change to allow sampling and testing.
  - .5 Acceptance of material at source does not preclude future rejection if it is subsequently found to lack uniformity, or if it fails to conform to requirements specified, or if its field performance is found to be unsatisfactory.
- 1.3 Production Sampling
- .1 Aggregate will be subject to continual sampling during production.
  - .2 Provide *Departmental Representative* with ready access to source and processed material for purpose of sampling and testing.

**Harbour Improvements****Half Island Cove****Guysborough County Nova Scotia****Project No. R.103901.001**

## Aggregates General

Page 2

- 
- 1.4 Measurement for  
Payment .1 This item will not be measured separately.

PART 2 - PRODUCTS

- 2.1 Materials .1 Aggregate quality: sound, hard, durable material free from soft, thin, elongated or laminated particles, organic material or other deleterious substances.
- .2 Flat and elongated particles are those whose greatest dimension exceeds four times their least dimension.
- .3 Fine aggregates satisfying requirements of applicable section shall be one, or a blend of following:
- .1 Natural sand
  - .2 Manufactured sand
  - .3 Screening produced in crushing of quarried rock, boulders, gravel or slag
  - .4 Coarse aggregates satisfying requirements of applicable section shall be one of following:
    - .1 Crushed rock or slag
    - .2 Gravel composed of naturally formed particles of stone.

PART 3 - EXECUTION

- 3.1 Development of Aggregate Source .1 Prior to excavating materials for aggregate production, clear and grub area to be worked, and strip unsuitable surface materials. Dispose of cleared, grubbed and unsuitable materials as directed by the *Departmental Representative*.
- .2 Clear, grub and strip an area ahead of quarrying or excavating operation sufficient to prevent contamination of aggregate by deleterious materials.
-

**Harbour Improvements****Half Island Cove****Guysborough County Nova Scotia****Project No. R.103901.001**

## Aggregates General

Page 3

- 
- |     |                    |  |
|-----|--------------------|--|
|     | .3                 | When operating in stratified deposits use excavation equipment and methods that will produce a uniform, homogeneous aggregate.                                       |
|     | .4                 | When excavation is completed, provide drains or ditches as required to prevent surface standing water.   |
|     | .5                 | Trim off and dress slopes of waste material piles and leave site in a neat condition.  |
| 3.2 | <u>Processing</u>  |  |
|     | .1                 | Process aggregate uniformly using methods that prevent contamination, segregation and degradation.   |
|     | .2                 | Blend aggregate if required to obtain gradation requirements specified. Use approved methods and equipment.  |
|     | .3                 | Blending to increase percentage of crushed particles or decrease percentage of flat and elongated particles is permitted.  |
|     | .4                 | Wash aggregates if required to meet specifications. Use only equipment accepted by <i>Departmental Representative</i> .  |
| 3.3 | <u>Handling</u>    |  |
|     | .1                 | Handle and transport aggregates to avoid segregation, contamination and degradation.   |
| 3.4 | <u>Stockpiling</u> |  |
|     | .1                 | Stockpiling aggregates on stabilized, clean and well drained surfaces.   |
|     | .2                 | To ensure that no material other than stockpiled aggregate is used, do not incorporate bottom 250 mm of stockpile into work, if aggregates are stockpiled on ground. |
|     | .3                 | Stockpile far enough apart to prevent intermixing.   |
|     | .4                 | Reject intermixed or contaminated materials. Remove and dispose of rejected materials as directed within 48 hours of rejection.                                      |
-

**Harbour Improvements****Half Island Cove****Guysborough County Nova Scotia****Project No. R.103901.001**

## Aggregates General

Page 4

- 
- .5 Stockpile materials in uniform layers of thickness as follows:
    - .1 Max 1 m for coarse aggregate and base course materials.
    - .2 Max 2 m for fine aggregate and subbase materials.
    - .3 Max 1.5 m for other materials.
  - .6 Complete each layer over entire stockpile area before beginning next layer.
  - .7 Uniformly spot-dump aggregates delivered to stockpile in trucks and build up stockpile as specified.
  - .8 Coning of piles or spilling of material over edges of pile will not be permitted.
  - .9 During winter operations, prevent ice and snow from becoming mixed into stockpile or in material being removed from stockpile.
-

**Harbour Improvements****Half Island Cove****Guysborough County Nova Scotia****Project No. R.103901.001**

## Sitework, Demolition and Removals

Page 1

---

**PART 1 - GENERAL**

- |                                    |   |
|------------------------------------|---|
| 1.1 <u>Description of Work</u>     | This Section includes but is not limited to the following:<br><br>.1 All normal removals as required to complete the work. All items to be verified by a site visit prior to submission of a tender.  |
| 1.2 <u>Related Work</u>            | .1 Refer to other specification sections for related information.   |
| 1.3 <u>Submissions</u>             | .1 Methodology:<br>.1 When requested provide methodology for carrying out the work  |
| 1.4 <u>Protection</u>              | .1 Prevent movement, settlement or damage of adjacent structures. Provided bracing and shoring as required. In event of damage, immediately replace such items or make repairs to approval of <i>Departmental Representative</i> and at no additional cost to <i>Departmental Representative</i> .<br><br>.2 Prevent debris from going adrift and becoming a menace to navigation.<br><br>.3 All damage to existing structures, roadways, pipelines, electrical systems not specified for removal to be repaired at the Contractor's cost to the satisfaction of the <i>Departmental Representative</i> . |
| 1.5 <u>Measurement for Payment</u> | .1 Sitework, demolition and removals will be measured in accordance with <b>Section 01 29 00</b> .<br>.1 removal of armourstone from exiting breakwater and reinstall in new work where required.   |

---

**PART 3 - EXECUTION**

- |                        |  |
|------------------------|--|
| 3.1 <u>Preparation</u> | .1 Inspect site and verify with <i>Departmental Representative</i> items designated for removal and items to be preserved. |
|------------------------|--|
-

**Harbour Improvements****Half Island Cove****Guysborough County Nova Scotia****Project No. R.103901.001**

## Sitework, Demolition and Removals

Page 2

- .2 Locate and protect utility lines. Preserve in operating condition active utilities traversing site.
- .3 Provide temporary power and lighting as shown on the plan or as required by the *Departmental Representative*.
- .4 All repairs to damages as a result of Contractor's operations to be at Contractor's cost and to the satisfaction of the *Departmental Representative*.

3.2 Removal

- .1 Remove items indicated.
- .2 Do not disturb adjacent structures designated to remain in place.
- .3 At end of each day's work, leave work in safe condition so no part is in danger of toppling or falling.

3.3 Disposal of Material

- .1 Disposal of materials not designated for salvage or re-use in work, will be the contractor's responsibility, and must be disposed of off-site.
- .2 The material to be disposed is to be transported and disposed of in an environmentally acceptable manner to the satisfaction of the *Departmental Representative*, and in accordance with any local, Municipal, Provincial and Federal restrictions and regulations.

3.4 Restoration

- .1 Upon completion of work, remove debris, trim surfaces and leave work site clean.
- .2 Reinstate areas and existing works outside areas of demolition to conditions that existed prior to commencement of work. Match condition of adjacent, undisturbed areas.