

Part 1 General

1.1 ACTION AND INFORMATIONAL SUBMITTALS

- .1 Submit in accordance with Section 01 33 00 - Submittal Procedures.
- .2 Product Data:
 - .1 Submit manufacturer's instructions, printed product literature and data sheets for domestic water heaters and domestic hot water recirculating pump and include product characteristics, performance criteria, physical size, finish and limitations.
- .3 Shop Drawings:
 - .1 Submit drawings stamped and signed by professional engineer registered or licensed in Province of Alberta, Canada.
 - .2 Indicate on drawings:
 - .1 Mounting arrangements.
 - .2 Operating and maintenance clearances.
 - .3 Shop drawings and product data accompanied by:
 - .1 Detailed drawings of bases, supports, and anchor bolts.
 - .2 Acoustical sound power data, where applicable.
 - .3 Points of operation on performance curves.
 - .4 Manufacturer to certify current model production.
 - .5 Certification of compliance to applicable codes.

1.2 CLOSEOUT SUBMITTALS

- .1 Submit in accordance with Section 01 78 00 - Closeout Submittals.
- .2 Operation and Maintenance Data: submit operation and maintenance data for incorporation into manual.
 - .1 Operation and maintenance manual approved by, and final copies deposited with, Departmental Representative before final inspection.
 - .2 Operation data to include:
 - .1 Control schematics for systems including environmental controls.
 - .2 Description of systems and their controls.
 - .3 Description of operation of systems at various loads together with reset schedules and seasonal variances.
 - .4 Operation instruction for systems and component.
 - .5 Description of actions to be taken in event of equipment failure.
 - .6 Valves schedule and flow diagram.
 - .7 Colour coding chart.
 - .3 Maintenance data to include:

- .1 Servicing, maintenance, operation and trouble-shooting instructions for each item of equipment.
- .2 Data to include schedules of tasks, frequency, tools required and task time.
- .4 Performance data to include:
 - .1 Equipment manufacturer's performance datasheets with point of operation as left after commissioning is complete.
 - .2 Equipment performance verification test results.
 - .3 Special performance data as specified.
 - .4 Testing, adjusting and balancing reports as specified in Section 23 05 93 - Testing, Adjusting and Balancing for HVAC.
- .5 Approvals:
 - .1 Submit 2 copies of draft Operation and Maintenance Manual to Departmental Representative for approval. Submission of individual data will not be accepted unless directed by Departmental Representative.
 - .2 Make changes as required and re-submit as directed by Departmental Representative.
- .6 Additional data:
 - .1 Prepare and insert into operation and maintenance manual additional data when need for it becomes apparent during specified demonstrations and instructions.
- .7 Site records:
 - .1 Provide sets of white prints for each phase of work. Mark changes as work progresses and as changes occur.
 - .2 Transfer information weekly to reproducibles, revising reproducibles to show work as actually installed.
 - .3 Use different colour waterproof ink for each service.
 - .4 Make available for reference purposes and inspection.
- .8 As-built drawings:
 - .1 Prior to start of Testing, Adjusting and Balancing for HVAC, finalize production of as-built drawings.
 - .2 Identify each drawing in lower right hand corner in letters at least 12 mm high as follows: - "AS BUILT DRAWINGS: THIS DRAWING HAS BEEN REVISED TO SHOW MECHANICAL SYSTEMS AS INSTALLED" (Signature of Contractor) (Date).
 - .3 Submit to Departmental Representative for approval and make corrections as directed.
 - .4 Perform testing, adjusting and balancing for HVAC using as-built drawings.
 - .5 Submit completed reproducible as-built drawings with Operating and Maintenance Manuals.
- .9 Submit copies of as-built drawings for inclusion in final TAB report.

1.3 MAINTENANCE MATERIAL SUBMITTALS

- .1 Submit in accordance with Section 01 78 00 - Closeout Submittals.
- .2 Furnish spare parts as follows:
 - .1 One set of packing for each pump.
 - .2 One casing joint gasket for each size pump.
 - .3 One glass for each gauge glass.
- .3 Provide one set of special tools required to service equipment as recommended by manufacturers.
- .4 Furnish one commercial quality grease gun, grease and adapters to suit different types of grease and grease fittings.

1.4 DELIVERY, STORAGE AND HANDLING

- .1 Deliver, store and handle materials in accordance with Section 01 61 00 - Common Product Requirements with manufacturer's written instructions.
- .2 Delivery and Acceptance Requirements: deliver materials to site in original factory packaging, labelled with manufacturer's name and address.
- .3 Storage and Handling Requirements:
 - .1 Store materials indoors and in accordance with manufacturer's recommendations in clean, dry, well-ventilated area.
 - .2 Store and protect from nicks, scratches, and blemishes.
 - .3 Replace defective or damaged materials with new.
- .4 Packaging Waste Management: remove for reuse and return by manufacturer of pallets, crates, padding, packaging materials as specified in Construction Waste Management Plan in accordance with Section 01 74 19 - Construction/Demolition Waste Management and Disposal.

Part 2 Products

2.1 NOT USED

- .1 Not used.

Part 3 Execution

3.1 EXAMINATION

- .1 Verification of Conditions: verify that conditions of substrate previously installed under other Sections or Contracts are acceptable for installation in accordance with manufacturer's written instructions.
 - .1 Visually inspect substrate in presence of Departmental Representative.
 - .2 Inform Departmental Representative of unacceptable conditions immediately upon discovery.

- .3 Proceed with installation only after unacceptable conditions have been remedied and after receipt of written approval to proceed from Departmental Representative.

3.2 PAINTING REPAIRS AND RESTORATION

- .1 Do painting in accordance with Section 09 91 00 - Painting.
- .2 Prime and touch up marred finished paintwork to match original.
- .3 Restore to new condition, finishes which have been damaged.

3.3 SYSTEM CLEANING

- .1 Clean interior and exterior of all systems including strainers. Vacuum interior of ductwork and air handling units.

3.4 FIELD QUALITY CONTROL

- .1 Site Tests: conduct following tests in accordance with Section 01 45 00 - Quality Control and submit report as described in PART 1 -ACTION AND INFORMATIONAL SUBMITTALS.
- .2 Manufacturer's Field Services:
 - .1 Obtain written report from manufacturer verifying compliance of Work, in handling, installing, applying, protecting and cleaning of product and submit Manufacturer's Field Reports as described in PART 1 - ACTION AND INFORMATIONAL SUBMITTALS.
 - .2 Provide manufacturer's field services consisting of product use recommendations and periodic site visits for inspection of product installation in accordance with manufacturer's instructions.

3.5 DEMONSTRATION

- .1 Departmental Representative will use equipment and systems for test purposes prior to acceptance. Supply labour, material, and instruments required for testing.
- .2 Supply tools, equipment and personnel to demonstrate and instruct operating and maintenance personnel in operating, controlling, adjusting, trouble-shooting and servicing of all systems and equipment during regular work hours, prior to acceptance.
- .3 Use operation and maintenance manual, as-built drawings, and audio visual aids as part of instruction materials.
- .4 Instruction duration time requirements as specified in appropriate sections.
- .5 Departmental Representative will record these demonstrations on video tape for future reference.

3.6 CLEANING

- .1 Progress Cleaning: clean in accordance with Section 01 74 00 - Cleaning.
 - .1 Leave Work area clean at end of each day.

- .2 Final Cleaning: upon completion remove surplus materials, rubbish, tools and equipment in accordance with Section 01 74 00 - Cleaning.
- .3 Waste Management: separate waste materials for reuse recycling in accordance with Section 01 74 19 - Construction/Demolition Waste Management and Disposal.
 - .1 Remove recycling containers and bins from site and dispose of materials at appropriate facility.

3.7 PROTECTION

- .1 Protect equipment and systems openings from dirt, dust, and other foreign materials with materials appropriate to system.

END OF SECTION

Part 1 General

1.1 SUMMARY

- .1 Section Includes:
 - .1 Materials and installation for plumbing pumps.

1.2 REFERENCES

- .1 Material Safety Data Sheets (MSDS).

1.3 ACTION AND INFORMATIONAL SUBMITTALS

- .1 Submittals in accordance with Section 01 33 00 - Submittal Procedures.
- .2 Product Data:
 - .1 Submit manufacturer's printed product literature, specifications and data sheet for fixtures and equipment.
- .3 Shop Drawings.
 - .1 Submit shop drawings to indicate:
 - .1 Equipment, including connections, fittings, control assemblies and ancillaries. Identify whether factory or field assembled.
 - .2 Wiring and schematic diagrams.
 - .3 Dimensions and recommended installation.
 - .4 Pump performance and efficiency curves.
- .4 Certificates: submit certificates signed by manufacturer certifying that materials comply with specified performance characteristics and physical properties.
- .5 Instructions: submit manufacturer's installation instructions.
- .6 Closeout submittals: submit maintenance and engineering data for incorporation into manual specified in Section 01 78 00 - Closeout Submittals, include:
 - .1 Manufacturers name, type, model year, capacity and serial number.
 - .2 Details of operation, servicing and maintenance.
 - .3 Recommended spare parts list with names and addresses.

1.4 QUALITY ASSURANCE

- .1 Pre-Installation Meeting:
 - .1 Convene pre-installation meeting one week prior to beginning work of this Section in accordance with Section 01 32 16.19 - Construction Progress Schedules-Bar (GANTT) Chart:
 - .1 Verify project requirements.
 - .2 Review installation and substrate conditions.
 - .3 Co-ordination with other building subtrades.

- .4 Review manufacturer's installation instructions and warranty requirements.
- .2 Health and Safety:
 - .1 Do construction occupational health and safety in accordance with Section 01 35 29.06 - Health and Safety Requirements.

1.5 DELIVERY, STORAGE AND HANDLING

- .1 Waste Management and Disposal:
 - .1 Separate waste materials for recycling in accordance with Section 01 74 19 - Construction/Demolition Waste Management and Disposal.
 - .2 Remove from site and dispose of packaging materials at appropriate recycling facilities.
 - .3 Collect and separate for disposal paper plastic polystyrene corrugated cardboard packaging material in appropriate on-site bins for recycling in accordance with Waste Management Plan.
 - .4 Divert unused metal materials from landfill to metal recycling facility as approved by Departmental Representative.
 - .5 Unused sealant materials must not be disposed of into sewer system, into streams, lakes, onto ground or in other location where it will pose health or environmental hazard.
 - .6 Fold up metal plastic banding, flatten and place in designated area for recycling.

Part 2 Products

2.1 DOMESTIC HOT WATER CIRCULATING PUMPS

- .1 Capacity: refer to schedule.
- .2 Construction: closed-coupled, in-line centrifugal, all bronze construction, stainless steel or bronze shaft sleeve, two oil lubricated bronze sleeves or ball bearings.
- .3 Motor: drip-proof, with thermal overload protection.
- .4 Supports: provide as recommended by manufacturer.

2.2 SUMP PUMP SUBMERSIBLE

- .1 Capacity: refer to schedule.
- .2 Construction: simplex CSA approved, housing epoxy coated cast iron, recessed vortex impeller, 2x double lip shaft seal type,
- .3 Motor: PSC Motor
- .4 Supports: provide as recommended by manufacturer.

Part 3 Execution

3.1 MANUFACTURER'S INSTRUCTIONS

- .1 Compliance: comply with manufacturer's written recommendations or specifications, including product technical bulletins, handling, storage and installation instructions, and data sheet.

3.2 INSTALLATION

- .1 Make piping and electrical connections to pump and motor assembly and controls as indicated.
- .2 Ensure pump and motor assembly do not support piping.
- .3 Align vertical pit mounted pump assembly after mounting and securing cover plate.
- .4 Place 150 mm sand under sump pit tank.

3.3 FIELD QUALITY CONTROL

- .1 Site Tests/Inspection:
 - .1 Check power supply.
 - .2 Check starter protective devices.
- .2 Start-up, check for proper and safe operation.
- .3 Check settings and operation of hand-off-auto selector switch, operating, safety and limit controls, audible and visual alarms, over-temperature and other protective devices.
- .4 Adjust flow from water-cooled bearings.
- .5 Adjust impeller shaft stuffing boxes, packing glands.

3.4 START-UP

- .1 General:
 - .1 In accordance with Section 23 05 93 – Testing, Adjusting and Balancing for HVAC.
 - .2 Procedures:
 - .1 Check power supply.
 - .2 Check starter O/L heater sizes.
 - .3 Start pumps, check impeller rotation.
 - .4 Check for safe and proper operation.
 - .5 Check settings, operation of operating, limit, safety controls, over-temperature, audible/visual alarms, other protective devices.
 - .6 Test operation of hands-on-auto switch.
 - .7 Test operation of alternator.
 - .8 Adjust leakage through water-cooled bearings.

- .9 Adjust shaft stuffing boxes.
- .10 Adjust leakage flow rate from pump shaft stuffing boxes to manufacturer's recommendations.
- .11 Check base for free-floating, no obstructions under base.
- .12 Run-in pumps for 12 continuous hours.
- .13 Check installation, operation of mechanical seals, packing gland type seals. Adjust as necessary.
- .14 Adjust alignment of piping and conduit to ensure full flexibility.
- .15 Eliminate causes of cavitation, flashing, air entrainment.
- .16 Measure pressure drop across strainer when clean and with flow rates as finally set.
- .17 Replace seals if pump used to degrease system or if pump used for temporary heat.
- .18 Verify lubricating oil levels.

3.5 REPORTS

- .1 In accordance with Section 23 05 93 – Testing, Adjusting and Balancing for HVAC.
- .2 Include:
 - .1 Product Information report forms.
 - .2 Pump performance curves (family of curves) with final point of actual performance.

3.6 TRAINING

- .1 In accordance with Section 23 05 93 – Testing, Adjusting and Balancing for HVAC and 01 91 13 - General Commissioning (Cx) Requirements: Training of Operation and Maintenance Personnel, supplemented as specified.

END OF SECTION

Part 1 General

1.1 RELATED REQUIREMENTS

- .1 Section 21 05 01 - Common Work Results for Mechanical.
- .2 Section 23 05 93 - Testing, Adjusting and Balancing for HVAC.
- .3 Section 23 05 05 - Installation of Pipework.

1.2 REFERENCES

- .1 American National Standards Institute (ANSI)/American Society of Mechanical Engineers International (ASME)
 - .1 ANSI/ASME B16.15, Cast Bronze Threaded Fittings, Classes 125 and 250.
 - .2 ANSI/ASME B16.18, Cast Copper Alloy Solder Joint Pressure Fittings.
 - .3 ANSI/ASME B16.22, Wrought Copper and Copper Alloy Solder Joint Pressure Fittings.
 - .4 ANSI/ASME B16.24, Cast Copper Alloy Pipe Flanges and Flanged Fittings, Class 150, 300, 400, 600, 900, 1500 and 2500.
- .2 ASTM International Inc.
 - .1 ASTM A307, Standard Specification for Carbon Steel Bolts and Studs, 60,000 PSI Tensile Strength.
 - .2 ASTM A536, Standard Specification for Ductile Iron Castings.
 - .3 ASTM B88M, Standard Specification for Seamless Copper Water Tube (Metric).
- .3 American National Standards Institute/American Water Works Association (ANSI)/(AWWA)
 - .1 ANSI/AWWA C111/A21.11-07, Rubber-Gasket Joints for Ductile-Iron Pressure Pipe and Fittings.
- .4 Canadian Standards Association (CSA International)
 - .1 CSA B242, Groove and Shoulder Type Mechanical Pipe Couplings.
- .5 Department of Justice Canada (Jus)
 - .1 Canadian Environmental Protection Act, 1999, c. 33 (CEPA).
- .6 Health Canada/Workplace Hazardous Materials Information System (WHMIS)
 - .1 Material Safety Data Sheets (MSDS).
- .7 Manufacturer's Standardization Society of the Valve and Fittings Industry (MSS).
 - .1 MSS-SP-67, Butterfly Valves.
 - .2 MSS-SP-70, Gray Iron Gate Valves, Flanged and Threaded Ends.

- .3 MSS-SP-71, Gray Iron Swing Check Valves, Flanged and Threaded Ends.
- .4 MSS-SP-80, Bronze Gate, Globe, Angle and Check Valves.
- .8 National Research Council (NRC)/Institute for Research in Construction
 - .1 NRCC 56190, National Plumbing Code of Canada 2015.
- .9 Transport Canada (TC)
 - .1 Transportation of Dangerous Goods Act, 1992, c. 34 (TDGA).

1.3 ACTION AND INFORMATIONAL SUBMITTALS

- .1 Provide submittals in accordance with Section 01 33 00 - Submittal Procedures.
- .2 Product Data:
 - .1 Provide manufacturer's printed product literature and datasheets for insulation and adhesives, and include product characteristics, performance criteria, physical size, finish and limitations.
- .3 Closeout Submittals:
 - .1 Provide maintenance data for incorporation into manual specified in Section 01 78 00 - Closeout Submittals.

1.4 DELIVERY, STORAGE AND HANDLING

- .1 Packaging Waste Management: remove for reuse by manufacturer of pallets crates padding packaging materials in accordance with Section 01 74 19 - Construction/Demolition Waste Management and Disposal.
- .2 Place materials defined as hazardous or toxic in designated containers.
- .3 Handle and dispose of hazardous materials in accordance with Regional and Municipal regulations.

Part 2 Products

2.1 PIPING

- .1 Domestic hot, cold and recirculation systems, within building.
 - .1 Above ground: copper tube, hard drawn, type K,L,M: to ASTM B88M.
 - .2 Buried or embedded: copper tube, soft annealed, type K, L: to ASTM B88M, in long lengths and with no buried joints.

2.2 FITTINGS

- .1 Bronze pipe flanges and flanged fittings, Class 150: to ANSI/ASME B16.24.
- .2 Cast bronze threaded fittings, Class 125: to ANSI/ASME B16.15.
- .3 Cast copper, solder type: to ANSI/ASME B16.18.
- .4 Wrought copper and copper alloy, solder type: to ANSI/ASME B16.22.

- .5 NPS 2 and larger: ANSI/ASME B16.18 or ANSI/ASME B16.22 roll grooved to CSA B242.
- .6 NPS 1 and smaller: wrought copper to ANSI/ASME B16.22 cast copper to ANSI/ASME B16.18; with 301 stainless steel internal components and EPDM seals. Suitable for operating pressure to 1380 kPa.

2.3 JOINTS

- .1 Rubber gaskets, latex-free 1.6 mm thick: to AWWA C111.
- .2 Bolts, nuts, hex head and washers: to ASTM A307, heavy series.
- .3 Solder: 95/5 tin copper alloy.
- .4 Teflon tape: for threaded joints.
- .5 Grooved couplings: designed with angle bolt pads to provide rigid joint, complete with EPDM gasket.
- .6 Dielectric connections between dissimilar metals: dielectric fitting, complete with thermoplastic liner.

2.4 GATE VALVES

- .1 NPS 2 and under, soldered:
 - .1 Rising stem: to MSS-SP-80, Class 125, 860 kPa, bronze body, screw-in bonnet, solid wedge disc as specified Section 23 05 23.01 - Valves - Bronze.
- .2 NPS 2 and under, screwed:
 - .1 Rising stem: to MSS-SP-80, Class 125, 860 kPa, bronze body, screw-in bonnet, solid wedge disc as specified Section 23 05 23.01 - Valves - Bronze.

2.5 BALL VALVES

- .1 NPS 2 and under, screwed:
 - .1 Class 150.
 - .2 Bronze body, stainless steel ball, PTFE adjustable packing, brass gland and PTFE seat, steel lever.
- .2 NPS 2 and under, soldered:
 - .1 To ANSI/ASME B16.18, Class 150.
 - .2 Bronze body, stainless steel ball, PTFE adjustable packing, brass gland and PTFE seat, steel lever handle.

Part 3 Execution

3.1 APPLICATION

- .1 Manufacturer's Instructions: comply with manufacturer's written recommendations, including product technical bulletins, handling, storage and installation instructions, and datasheets.

3.2 INSTALLATION

- .1 Install in accordance with NPC local authority having jurisdiction.
- .2 Install pipe work in accordance with Section 23 05 05 - Installation of Pipework, supplemented as specified herein.
- .3 Assemble piping using fittings manufactured to ANSI standards.
- .4 Install CWS piping below and away from HWS and HWC and other hot piping so as to maintain temperature of cold water as low as possible.
- .5 Connect to fixtures and equipment in accordance with manufacturer's written instructions unless otherwise indicated.
- .6 Buried tubing:
 - .1 Lay in well compacted washed sand in accordance with AWWA Class B bedding.
 - .2 Bend tubing without crimping or constriction. Minimize use of fittings.

3.3 VALVES

- .1 Isolate equipment, fixtures and branches with gate ball valves.
- .2 Balance recirculation system using lockshield globe valves. Mark settings and record on as-built drawings on completion.

3.4 PRESSURE TESTS

- .1 Conform to requirements of Section 21 05 01 - Common Work Results for Mechanical.
- .2 Test pressure: greater of 1 time maximum system operating pressure or 860 kPa.

3.5 FLUSHING AND CLEANING

- .1 Flush entire system for 8 hours. Ensure outlets flushed for 2 hours. Let stand for 24 hours, then draw one sample off longest run. Submit to testing laboratory to verify that system is clean copper to Provincial potable water guidelines. Let system flush for additional 2 hours, then draw off another sample for testing.

3.6 PRE-START-UP INSPECTIONS

- .1 Systems to be complete, prior to flushing, testing and start-up.
- .2 Verify that system can be completely drained.

- .3 Ensure that pressure booster systems are operating properly.
- .4 Ensure that air chambers, expansion compensators are installed properly.

3.7 DISINFECTION

- .1 Flush out, disinfect and rinse system to requirements of authority having jurisdiction.
- .2 Coordinate with Section 33 11 16- Water Distribution Piping.
- .3 Upon completion, provide laboratory test reports on water quality for Departmental Representative approval.

3.8 START-UP

- .1 Timing: start up after:
 - .1 Pressure tests have been completed.
 - .2 Disinfection procedures have been completed.
 - .3 Certificate of static completion has been issued.
 - .4 Water treatment systems operational.
- .2 Provide continuous supervision during start-up.
- .3 Start-up procedures:
 - .1 Establish circulation and ensure that air is eliminated.
 - .2 Check pressurization to ensure proper operation and to prevent water hammer, flashing and/or cavitation.
 - .3 Commission water conditioning specified Section 22 31 13 - Residential Domestic Water Softeners.
 - .4 Bring HWS storage tank up to design temperature slowly.
 - .5 Monitor piping HWS and HWC piping systems for freedom of movement, pipe expansion as designed.
 - .6 Check control, limit, safety devices for normal and safe operation.
- .4 Rectify start-up deficiencies.

3.9 PERFORMANCE VERIFICATION

- .1 Scheduling:
 - .1 Verify system performance after pressure and leakage tests and disinfection are completed, and Certificate of Completion has been issued by authority having jurisdiction.
- .2 Procedures:
 - .1 Verify that flow rate and pressure meet Design Criteria.
 - .2 TAB HWC in accordance with Section 23 05 93 - Testing, Adjusting and Balancing for HVAC.
 - .3 Adjust pressure regulating valves while withdrawal is maximum and inlet pressure is minimum.

- .4 Sterilize HWS and HWC systems for Legionella control.
- .5 Verify performance of temperature controls.
- .6 Verify compliance with safety and health requirements.
- .7 Check for proper operation of water hammer arrestors. Run one outlet for 10 seconds, then shut of water immediately. If water hammer occurs, replace water hammer arrestor or re-charge air chambers. Repeat for outlets and flush valves.
- .8 Confirm water quality consistent with supply standards, and ensure no residuals remain as result of flushing or cleaning.
- .3 Reports:
 - .1 Include certificate of water flow and pressure tests conducted on incoming water service, demonstrating adequacy of flow and pressure.

3.10 OPERATION REQUIREMENTS

- .1 Co-ordinate operation and maintenance requirements including, cleaning and maintenance of specified materials and products with Section 23 05 05 - Installation of Pipework.

3.11 CLEANING

- .1 Clean in accordance with Section 01 74 00 - Cleaning.
- .2 Waste Management: separate waste materials for recycling in accordance with Section 01 74 19 - Construction/Demolition Waste Management and Disposal.

END OF SECTION

Part 1 General

1.1 REFERENCES

- .1 ASTM International Inc.
 - .1 ASTM B32, Standard Specification for Solder Metal.
 - .2 ASTM B306, Standard Specification for Copper Drainage Tube (DWV).
 - .3 ASTM C564, Standard Specification for Rubber Gaskets for Cast Iron Soil Pipe and Fittings.
- .2 Canadian Standards Association (CSA International).
 - .1 CSA B67, Lead Service Pipe, Waste Pipe, Traps, Bends and Accessories.
 - .2 CAN/CSA-B70, Cast Iron Soil Pipe, Fittings and Means of Joining.
 - .3 CAN/CSA-B125.3, Plumbing Fittings.
- .3 Green Seal Environmental Standards (GSES)
 - .1 Standard GS-36, Commercial Adhesives.
- .4 South Coast Air Quality Management District (SCAQMD), California State
 - .1 SCAQMD Rule 1168, Adhesive and Sealant Applications.

1.2 ACTION AND INFORMATIONAL SUBMITTALS

- .1 Provide submittals in accordance with Section 01 33 00 - Submittal Procedures.
- .2 Product Data:
 - .1 Provide manufacturer's printed product literature and datasheets for adhesives, and include product characteristics, performance criteria, physical size, finish and limitations.

1.3 DELIVERY, STORAGE AND HANDLING

- .1 Deliver, store and handle in accordance with Section 01 61 00 - Common Product Requirements.
- .2 Deliver materials to site in original factory packaging, labelled with manufacturer's name, address.
- .3 Packaging Waste Management: remove for reuse by manufacturer of pallets crates padding packaging materials in accordance with Section 01 74 19 - Construction/Demolition Waste Management and Disposal.

Part 2 Products

2.1 COPPER TUBE AND FITTINGS

- .1 Above ground sanitary storm and vent Type DWV to: ASTM B306.

- .1 Fittings.
 - .1 Cast brass: to CAN/CSA-B125.3.
 - .2 Wrought copper: to CAN/CSA-B125.3.
- .2 Solder: tin-lead, 50:50, type 50A to ASTM B32.

2.2 CAST IRON PIPING AND FITTINGS

- .1 Buried sanitary storm and vent minimum NPS 3, to: CAN/CSA-B70, with one layer of protective coating.
 - .1 Joints:
 - .1 Mechanical joints:
 - .1 Neoprene or butyl rubber compression gaskets: to CAN/CSA-B70.
 - .2 Hub and spigot:
 - .1 Caulking lead: to CSA B67.
 - .2 Cold caulking compounds.
 - .2 Above ground sanitary storm and vent: to CAN/CSA-B70.
 - .1 Joints:
 - .1 Hub and spigot:
 - .1 Caulking lead: to CSA B67.
 - .2 Mechanical joints:
 - .1 Neoprene or butyl rubber compression gaskets with stainless steel clamps.

Part 3 Execution

3.1 APPLICATION

- .1 Manufacturer's Instructions: comply with manufacturer's written recommendations, including product technical bulletins, handling, storage and installation instructions, and datasheets.

3.2 INSTALLATION

- .1 In accordance with Section 23 05 05 - Installation of Pipework.
- .2 Install in accordance with National Plumbing Code local authority having jurisdiction.

3.3 TESTING

- .1 Pressure test buried systems before backfilling.
- .2 Hydraulically test to verify grades and freedom from obstructions.

3.4 PERFORMANCE VERIFICATION

- .1 Cleanouts:

- .1 Ensure accessible and that access doors are correctly located.
- .2 Open, cover with linseed oil and re-seal.
- .3 Verify that cleanout rods can probe as far as the next cleanout, at least.
- .2 Test to ensure traps are fully and permanently primed.
- .3 Storm water drainage:
 - .1 Verify domes are secure.
 - .2 Ensure weirs are correctly sized and installed correctly.
 - .3 Verify provisions for movement of roof system.
- .4 Ensure that fixtures are properly anchored, connected to system and effectively vented.
- .5 Affix applicable label (storm, sanitary, vent, pump discharge etc.) c/w directional arrows every floor or 4.5 m (whichever is less).

3.5

CLEANING

- .1 Clean in accordance with Section 01 74 00 - Cleaning.
- .2 Waste Management: separate waste materials for reuse recycling in accordance with Section 01 74 19 - Construction/Demolition Waste Management and Disposal.

END OF SECTION

1.1 RELATED REQUIREMENTS

- .1 Section 23 05 05 - Installation of Pipework.

1.2 REFERENCES

- .1 ASTM International Inc.
 - .1 ASTM D2235, Standard Specification for Solvent Cement for Acrylonitrile-Butadiene-Styrene (ABS) Plastic Pipe and Fittings.
 - .2 ASTM D2564, Standard Specification for Solvent Cements for Poly(Vinyl-Chloride) (PVC) Plastic Piping Systems.
- .2 Canadian Standards Association (CSA International)
 - .1 CAN/CSA-Series B1800, Thermoplastic Nonpressure Pipe Compendium - B1800 Series.
- .3 Green Seal Environmental Standards (GSES)
 - .1 Standard GS-36, Commercial Adhesives.
- .4 Health Canada/Workplace Hazardous Materials Information System (WHMIS)
 - .1 Material Safety Data Sheets (MSDS).
- .5 South Coast Air Quality Management District (SCAQMD), California State
 - .1 SCAQMD Rule 1168, Adhesive and Sealant Applications.

1.3 ACTION AND INFORMATIONAL SUBMITTALS

- .1 Provide submittals in accordance with Section 01 33 00 - Submittal Procedures.
- .2 Product Data:
 - .1 Provide manufacturer's printed product literature and datasheets for piping and adhesives, and include product characteristics, performance criteria, physical size, finish and limitations.
 - .2 Provide two copies WHMIS MSDS - Material Safety Data Sheets in accordance with Section 01 35 29.06 - Health and Safety Requirements.

1.4 DELIVERY, STORAGE AND HANDLING

- .1 Deliver, store and handle in accordance with Section 01 61 00 - Common Product Requirements.
- .2 Deliver materials to site in original factory packaging, labelled with manufacturer's name, address.
- .3 Store at temperatures and conditions recommended by manufacturer.
- .4 Packaging Waste Management: remove for reuse by manufacturer of pallets crates padding packaging materials in accordance with Section 01 74 19 - Construction/Demolition Waste Management and Disposal.

Part 2 Products

2.1 PIPING AND FITTINGS

- .1 For buried above ground DWV piping to:
 - .1 CAN/CSA B1800.

2.2 JOINTS

- .1 Solvent weld for PVC: to ASTM D2564.
- .2 Solvent weld for ABS: to ASTM D2235.

Part 3 Execution

3.1 APPLICATION

- .1 Manufacturer's Instructions: comply with manufacturer's written recommendations, including product technical bulletins, handling, storage and installation instructions, and datasheets.

3.2 INSTALLATION

- .1 In accordance with Section 23 05 05 - Installation of Pipework.
- .2 Install in accordance with National Plumbing Code local authority having jurisdiction.

3.3 TESTING

- .1 Pressure test buried systems before backfilling.
- .2 Hydraulically test to verify grades and freedom from obstructions.

3.4 PERFORMANCE VERIFICATION

- .1 Cleanouts:
 - .1 Ensure accessible and that access doors are correctly located.
 - .2 Open, cover with linseed oil and re-seal.
 - .3 Verify cleanout rods can probe as far as the next cleanout, at least.
- .2 Test to ensure traps are fully and permanently primed.
- .3 Storm water drainage:
 - .1 Verify domes are secure.
 - .2 Ensure weirs are correctly sized and installed correctly.
 - .3 Verify provisions for movement of roof system.
- .4 Ensure fixtures are properly anchored, connected to system and effectively vented.

- .5 Affix applicable label (storm, sanitary, vent, pump discharge) c/w directional arrows every floor or 4.5 m (whichever is less).

3.5 CLEANING

- .1 Clean in accordance with Section 01 74 00 - Cleaning.
 - .1 Remove surplus materials, excess materials, rubbish, tools and equipment.
- .2 Waste Management: separate waste materials for recycling in accordance with Section 01 74 19 - Construction/Demolition Waste Management and Disposal.

END OF SECTION

Part 1 General

1.1 REFERENCES

- .1 American National Standards Institute/Canadian Standards Association (ANSI/CSA)
 - .1 ANSI Z21.10.3A/CSA 4.3, Gas Water Heaters - Volume III - Storage Water Heaters, with Input Ratings Above 75,000 Btu Per Hour, Circulating and Instantaneous.
- .2 Canadian Standards Association (CSA International)
 - .1 CSA B51, Boiler, Pressure Vessel, and Pressure Piping Code.
 - .2 CAN/CSA-B149.1, Natural Gas and Propane Installation Code.

1.2 ACTION AND INFORMATIONAL SUBMITTALS

- .1 Provide submittals in accordance with Section 01 33 00 - Submittal Procedures.
- .2 Product Data:
 - .1 Provide manufacturer's printed product literature and datasheets for domestic water heater, and include product characteristics, performance criteria, physical size, finish and limitations.
- .3 Shop Drawings:
 - .1 Provide drawings stamped and signed by professional engineer registered or licensed in Alberta, Canada.
 - .2 Indicate:
 - .1 Equipment, including connections, fittings, control assemblies and ancillaries, identifying factory and field assembled.

1.3 CLOSEOUT SUBMITTALS

- .1 Provide maintenance and engineering data for incorporation into manual specified in Section 01 78 00 - Closeout Submittals.

1.4 DELIVERY, STORAGE AND HANDLING

- .1 Deliver, store and handle in accordance with Section 01 61 00 - Common Product Requirements.
- .2 Deliver materials to site in original factory packaging, labelled with manufacturer's name, address.
- .3 Packaging Waste Management: remove for reuse by manufacturer of pallets crates padding packaging materials in accordance with Section 01 74 19 - Construction/Demolition Waste Management and Disposal.

1.5 WARRANTY

- .1 For the Work of this Section [22 30 05 – Domestic Water Heaters], 12 months' warranty period prescribed in subsection GC 32.1 of General Conditions "C" is extended to number of years specified for each product.
- .2 Contractor hereby warrants domestic water heaters in accordance with CCDC2, but for number of years specified for each product.

Part 2 Products

2.1 DHW HEATER AND STORAGE TANK

- .1 DHW heater:
 - .1 General: packaged unit to ASME standards, stamped for 1100 kPa WP. Provide CGA certification.
 - .2 Capacity: refer to schedule.
 - .3 Heat exchanger: multi-tube, 2 pass, copper and bronze, with NPS 1 extruded and finned tubes rolled into heavy tube sheets. Inlet and outlet headers to include drain valves and thermowells.
 - .4 Combustion chamber: line with 50 mm insulating refractory.
 - .5 Burners: high chromium stainless steel, die stamped, raised port, fixed primary air.
 - .6 Cabinet: baked enamel, welded steel, insulated with foil-faced fibreglass.
 - .7 Trim:
 - .1 Self-actuated modulating valves with 2 ply thermostatic bellows, copper capillary tubing, separate built-in well, tight disc shut-off removable composition disc stem with lubricator temperature adjustment setting reference scale, maximum, pressure differential of 28 kPa, temperature range 25-60 degrees C.
 - .8 Controls:
 - .1 Main gas shut-off valve.
 - .2 Approved gas train including pressure regulator, motorized electric shut-off valve, downstream block/test valve, test connection, pressure gauge.
 - .3 Thermopilot safety with 100% shut-off, adjustable electric high limit control.
 - .4 Gas modulating valve adjusted for 100% to 20% input.
 - .5 Minimum input valve, on-off.
 - .6 Flow switch, interlocked with ignition system to prevent operation in event of low flow.
- .2 Storage tank:
 - .1 Sizes, capacity: refer to schedule.

- .2 Shell: vertical, steel to CSA B51, ANSI/ASME Unfired Pressure Vessel Code and Province of Alberta standards, WWP/WSP 700 kPa. Provide certificates.
- .3 Lining: glass.
- .4 Service Hole: 280 x 380 mm ASME, with gasketted cover.
- .5 Cathodic protection: magnesium anodes, number and size to provide for 20 years protection of tank material.
- .6 Cradles: steel, minimum of 2.
- .7 Thermal insulation: see Section 23 07 14 - Thermal Insulation for Equipment.
- .8 A warranty of 10 years is required on domestic water heater. Purchase 10 year extended warranty if manufacturer does not provide. Provide certificate.

2.2 TRIM AND INSTRUMENTATION

- .1 Drain valve: NPS 1 with hose end.
- .2 Thermometer: 100 mm dial type with red pointer and thermowell filled with conductive paste.
- .3 Pressure gauge: 75 mm dial type with red pointer, syphon, and shut-off cock.
- .4 Thermowell filled with conductive paste for control valve temperature sensor.
- .5 ASME rated temperature and pressure relief valve sized for full capacity of heater control valve, having discharge terminating over floor drain and visible to operators.
- .6 Magnesium anodes adequate for 20 years of operation and located for easy replacement.

2.3 ANCHOR BOLTS AND TEMPLATES

- .1 Supply anchor bolts and templates for installation in concrete support pad in accordance with Section 03 30 00 - Cast-in-Place Concrete.
- .2 Size anchor bolts to withstand seismic zone 4 acceleration and velocity forces.

Part 3 Execution

3.1 APPLICATION

- .1 Manufacturer's Instructions: comply with manufacturer's written recommendations, including product technical bulletins, handling, storage and installation instructions, and datasheets.

3.2 INSTALLATION

- .1 Install in accordance with manufacturer's recommendations and authority having jurisdiction.

- .2 Provide insulation between tank and supports.
- .3 Install oil burning domestic water heaters in accordance with CAN/CSA-B139.
- .4 Install natural gas fired domestic water heaters in accordance with CAN/CSA-B149.1.
- .5 Install propane gas fired domestic water heaters in accordance with CAN/CSA-B149.2.

3.3 FIELD QUALITY CONTROL

- .1 Manufacturer's factory trained, certified Engineer to start up and commission DHW heaters.

3.4 CLEANING

- .1 Clean in accordance with Section 01 74 00 - Cleaning.
 - .1 Remove surplus materials, excess materials, rubbish, tools and equipment.
- .2 Waste Management: separate waste materials for recycling in accordance with Section 01 74 19 - Construction/Demolition Waste Management and Disposal.

END OF SECTION

Part 1 General

1.1 REFERENCES

- .1 ASTM International
 - .1 ASTM A126-, Standard Specification for Gray Iron Castings for Valves, Flanges and Pipe Fittings.
 - .2 ASTM B62, Standard Specification for Composition Bronze or Ounce Metal Castings.
- .2 American Water Works Association (AWWA)
 - .1 ANSI/AWWA C700, Standard for Cold Water Meters-Displacement Type, Bronze Main Case.
- .3 CSA International
 - .1 CSA-B64 Series, Backflow Preventers and Vacuum Breakers.
 - .2 CSA B79, Commercial and Residential Drains and Cleanouts.
 - .3 CAN/CSA-B356, Water Pressure Reducing Valves for Domestic Water Supply Systems.
- .4 Plumbing and Drainage Institute (PDI)
 - .1 PDI-WH201, Water Hammer Arresters Standard.

1.2 ADMINISTRATIVE REQUIREMENTS

- .1 Pre-installation Meetings:
 - .1 Convene pre-installation meeting 1 week prior to beginning work of this Section on-site installation, with Departmental Representative in accordance with Section 01 31 19 - Project Meetings to:
 - .1 Verify project requirements.
 - .2 Review installation and substrate conditions.
 - .3 Co-ordination with other building construction subtrades.
 - .4 Review manufacturer's written installation instructions and warranty requirements.

1.3 ACTION AND INFORMATIONAL SUBMITTALS

- .1 Submit in accordance with Section 01 33 00 - Submittal Procedures.
- .2 Product Data:
 - .1 Submit manufacturer's instructions, printed product literature and data sheets for plumbing products and include product characteristics, performance criteria, physical size, finish and limitations.

- .2 Submit [2] copies of WHMIS MSDS in accordance with Section 01 35 29.06 - Health and Safety Requirements 01 35 43 - Environmental Procedures. Indicate VOC's.
- .3 Shop Drawings:
 - .1 Submit drawings stamped and signed by professional engineer registered or licensed in Province of Alberta, Canada.
 - .2 Indicate on drawings to indicate materials, finishes, method of anchorage, and number of anchors, dimensions construction.
- .4 Certificates: submit certificates signed by manufacturer certifying that materials comply with specified performance characteristics and physical properties.
- .5 Instructions: submit manufacturer's installation instructions.

1.4 CLOSEOUT SUBMITTALS

- .1 Submit in accordance with Section 01 78 00 - Closeout Submittals.
- .2 Operation and Maintenance Data: submit operation and maintenance data for plumbing specialties and accessories for incorporation into manual.
 - .1 Description of plumbing specialties and accessories, giving manufacturers name, type, model, year and capacity.
 - .2 Details of operation, servicing and maintenance.
 - .3 Recommended spare parts list.

1.5 DELIVERY, STORAGE AND HANDLING

- .1 Deliver, store and handle materials in accordance with Section 01 61 00 - Common Product Requirements with manufacturer's written instructions.
- .2 Delivery and Acceptance Requirements: deliver materials to site in original factory packaging, labelled with manufacturer's name and address.
- .3 Storage and Handling Requirements:
 - .1 Store materials in dry location and in accordance with manufacturer's recommendations in clean, dry, well-ventilated area.
 - .2 Store and protect materials from nicks, scratches, and blemishes.
 - .3 Replace defective or damaged materials with new.
- .4 Packaging Waste Management: remove for reuse by manufacturer of pallets, crates, padding, packaging materials as specified in Construction Waste Management Plan Waste Reduction Workplan in accordance with Section 01 74 19 - Construction/Demolition Waste Management and Disposal.

Part 2 Products

2.1 FLOOR DRAINS

- .1 Floor Drains and Trench Drains: to CSA B79.
- .2 Refer to schedule.

2.2 CLEANOUTS

- .1 Cleanout Plugs: heavy cast iron male ferrule with brass screws and threaded brass or bronze plug. Sealing-caulked lead seat or neoprene gasket.
- .2 Access Covers:
 - .1 Wall Access: face or wall type, polished nickel bronze round cover with flush head securing screws, bevelled edge frame complete with anchoring lugs.
 - .2 Floor Access: rectangular cast iron body and frame with adjustable secured nickel bronze top and:
 - .1 Plugs: bolted bronze with neoprene gasket.
 - .2 Cover for Unfinished Concrete Floors: cast iron round, gasket, vandal-proof screws.
 - .3 Cover for Tile and Linoleum Floors: polished nickel bronze with recessed cover for linoleum or tile infill, complete with vandal-proof locking screws.

2.3 NON-FREEZE WALL HYDRANTS

- .1 Surface mount with integral vacuum breaker, NPS 3/4 hose outlet, Chrome plated finish.

2.4 WATER HAMMER ARRESTORS

- .1 Copper construction, piston type: to PDI-WH201.

2.5 BACK FLOW PREVENTERS

- .1 Preventers: to CSA-B64, double check valve type assembly, consisting of two (2) positive sealing replaceable check valves with stainless steel or bronze seats. Provide strainer on units 50 mm and smaller. All interior surfaces of iron double check valve assemblies to be epoxy coated.

2.6 VACUUM BREAKERS

- .1 Breakers: to CSA-B64 Series, vacuum breaker atmospheric.

2.7 BACKWATER VALVES

- .1 Galvanized body with bronze seat, revolving bronze flapper and threaded cover.
- .2 Access:

- .1 Surface access.
- .2 Access pipe with cover: maximum 300 mm depth.
- .3 Steel housing with gasketted steel cover.
- .4 Concrete access pit with cover, as indicated.

2.8 HOSE BIBBS AND SEDIMENT FAUCETS

- .1 Bronze construction complete with integral back flow preventer, hose thread spout, replaceable composition disc, and chrome plated in finished areas.

2.9 WATER MAKE-UP ASSEMBLY

- .1 Complete with backflow preventer pressure gauge on inlet and outlet, pressure reducing valve to CAN/CSA-B356, pressure relief valve on low pressure side and gate valves on inlet and outlet.

2.10 WATER METERS

- .1 Displacement type to ANSI/AWWA C700.
- .2 Capacity: as indicated.
- .3 Accessories: remote readout device.

2.11 TRAP SEAL PRIMERS

- .1 Brass, with integral vacuum breaker, NPS 1/2 solder ends, NPS 1/2 drip line connection.

2.12 STRAINERS

- .1 860 kPa, Y type with 20 mesh, monel, bronze or stainless steel removable screen.
- .2 NPS 2 and under, bronze body, screwed ends, with brass cap.
- .3 NPS 2 1/2 and over, cast iron body, flanged ends, with bolted cap.

Part 3 Execution

3.1 EXAMINATION

- .1 Verification of Conditions:
 - .1 Visually inspect substrate in presence of Departmental Representative.
 - .2 Inform Departmental Representative of unacceptable conditions immediately upon discovery.
 - .3 Proceed with installation only after unacceptable conditions have been remedied and after receipt of written approval to proceed from Departmental Representative.

3.2 MANUFACTURER'S INSTRUCTIONS

- .1 Compliance: comply with manufacturer's written recommendations or specifications, including product technical bulletins, handling, storage and installation instructions, and data sheet.

3.3 INSTALLATION

- .1 Install in accordance with National Plumbing Code of Canada, local authority having jurisdiction.
- .2 Install in accordance with manufacturer's instructions and as specified.

3.4 CLEANOUTS

- .1 Install cleanouts at base of soil and waste stacks at locations required code, and as indicated.
- .2 Bring cleanouts to wall or finished floor unless serviceable from below floor.
- .3 Building drain cleanout and stack base cleanouts: line size to maximum NPS 4.

3.5 NON-FREEZE WALL HYDRANTS

- .1 Install 600 mm above finished grade and as indicated.

3.6 WATER HAMMER ARRESTORS

- .1 Install on branch supplies to fixtures or group of fixtures.

3.7 BACK FLOW PREVENTERS

- .1 Install in accordance with CSA-B64 Series, where indicated and elsewhere as required by code.
 - .1 Drains.
 - .2 Backwater Valves.
 - .3 Water Make-up Assembly.
- .2 Pipe discharge to terminate over nearest drain.

3.8 BACKWATER VALVES

- .1 Install in main sewer lines where indicated and at weeping tile connection in pit provided at building cleanout.

3.9 HOSE BIBBS AND SEDIMENT FAUCETS

- .1 Install at bottom of risers, at low points to drain systems, and as indicated.

3.10 TRAP SEAL PRIMERS

- .1 Install for floor drains and elsewhere, as indicated.

- .2 Install on cold water supply to nearest frequently used plumbing fixture, in concealed space, to approval of Departmental Representative.
- .3 Install soft copper tubing to floor drain.

3.11 STRAINERS

- .1 Install with sufficient room to remove basket for maintenance.

3.12 WATER METERS

- .1 Install water meter provided by local water authority.
- .2 Install water meter as indicated.

3.13 WATER MAKE-UP ASSEMBLY

- .1 Install on valved bypass.
- .2 Pipe discharge from relief valve to nearest floor drain.

3.14 START-UP

- .1 General:
 - .1 In accordance with Section 01 91 13 - General Commissioning (Cx) Requirements: General Requirements, supplemented as specified herein.
- .2 Timing: start-up only after:
 - .1 Pressure tests have been completed.
 - .2 Disinfection procedures have been completed.
 - .3 Certificate of static completion has been issued.
 - .4 Water treatment systems operational.
- .3 Provide continuous supervision during start-up.

3.15 TESTING AND ADJUSTING

- .1 General:
 - .1 Test and adjust plumbing specialties and accessories in accordance with Section 23 05 93 – Testing, Adjusting and Balancing for HVAC as specified.
- .2 Timing:
 - .1 After start-up deficiencies rectified.
 - .2 After certificate of completion has been issued by authority having jurisdiction.
- .3 Application tolerances:
 - .1 Pressure at fixtures: +/- 70 kPa.
 - .2 Flow rate at fixtures: +/- 20%.

- .4 Adjustments:
 - .1 Verify that flow rate and pressure meet design criteria.
 - .2 Make adjustments while flow rate or withdrawal is (1) maximum and (2) 25% of maximum and while pressure is (1) maximum and (2) minimum.
- .5 Floor drains:
 - .1 Verify operation of trap seal primer.
 - .2 Prime, using trap primer. Adjust flow rate to suit site conditions.
 - .3 Check operations of flushing features.
 - .4 Check security, accessibility, removability of strainer.
 - .5 Clean out baskets.
- .6 Vacuum breakers, backflow preventers, backwater valves:
 - .1 Test tightness, accessibility for Operation and Maintenance of cover and of valve.
 - .2 Simulate reverse flow and back-pressure conditions to test operation of vacuum breakers, backflow preventers.
 - .3 Verify visibility of discharge from open ports.
- .7 Access doors:
 - .1 Verify size and location relative to items to be accessed.
- .8 Cleanouts:
 - .1 Verify covers are gas-tight, secure, yet readily removable.
- .9 Water hammer arrestors:
 - .1 Verify proper installation of correct type of water hammer arrester.
- .10 Wall hydrants:
 - .1 Verify complete drainage, freeze protection.
 - .2 Verify operation of vacuum breakers.
- .11 Pressure regulators, PRV assemblies:
 - .1 Adjust settings to suit locations, flow rates, pressure conditions.
- .12 Strainers:
 - .1 Clean out repeatedly until clear.
 - .2 Verify accessibility of cleanout plug and basket.
 - .3 Verify that cleanout plug does not leak.
- .13 Hose bibbs, sediment faucets:
 - .1 Verify that flow and pressure meet design criteria.
 - .2 Check for leaks, replace compression washer if required.
- .14 Hydronic system water Make-up Assembly:

- .1 Verify flow, pressure, and connection.
- .15 Water meters:
 - .1 Verify location and accessibility.
 - .2 Test meter reading accuracy.

3.16 CLEANING

- .1 Progress Cleaning: clean in accordance with Section 01 74 00 - Cleaning.
 - .1 Leave Work area clean at end of each day.
- .2 Final Cleaning: upon completion remove surplus materials, rubbish, tools and equipment in accordance with Section 01 74 00 - Cleaning.
- .3 Waste Management: separate waste materials for reuse recycling in accordance with Section 01 74 19 - Construction/Demolition Waste Management and Disposal.
 - .1 Remove recycling containers and bins from site and dispose of materials at appropriate facility.

3.17 PROTECTION

- .1 Protect installed products and components from damage during construction.
- .2 Repair damage to adjacent materials caused by plumbing specialties and accessories installation.

END OF SECTION

Part 1 General

1.1 REFERENCES

- .1 CSA Group
 - .1 CAN/CSA-B45 Series, Plumbing Fixtures, (Consists of B45.0, B45.1, B45.2, B45.3, B45.4, B45.5, B45.6, B45.7, B45.8 and B45.9).
 - .2 CSA B125.3, Plumbing Fittings.
 - .3 CSA B651, Accessible Design for the Built Environment.
- .2 Green Seal (GS)
 - .1 GS-36, Adhesives for Commercial Use.

1.2 ACTION AND INFORMATIONAL SUBMITTALS

- .1 Submit in accordance with Section 01 33 00 - Submittal Procedures.
- .2 Product Data:
 - .1 Submit manufacturer's instructions, printed product literature and data sheets for washroom fixtures and include product characteristics, performance criteria, physical size, finish and limitations.
 - .2 Indicate fixtures and trim:
 - .1 Dimensions, construction details, roughing-in dimensions.
 - .2 Factory-set water consumption per flush at recommended pressure.
 - .3 For water closets: minimum pressure required for flushing.

1.3 CLOSEOUT SUBMITTALS

- .1 Include:
 - .1 Description of fixtures and trim, giving manufacturer's name, type, model, year, capacity.
 - .2 Details of operation, servicing, maintenance.
 - .3 List of recommended spare parts.

1.4 DELIVERY, STORAGE AND HANDLING

- .1 Deliver, store and handle materials in accordance with Section with manufacturer's written instructions 01 61 00 - Common Product Requirements.
- .2 Delivery and Acceptance Requirements: deliver materials to site in original factory packaging, labelled with manufacturer's name and address.
- .3 Storage and Handling Requirements:
 - .1 Store materials in dry location and in accordance with manufacturer's recommendations in clean, dry, well-ventilated area.
 - .2 Store and protect materials from nicks, scratches, and blemishes.

- .3 Replace defective or damaged materials with new.
- .4 Packaging Waste Management: remove for reuse by manufacturer of packaging materials padding, crates, pallets, as specified in Construction Waste Management Plan in accordance with Section 01 74 19 - Construction/Demolition Waste Management and Disposal.

Part 2 Products

2.1 MANUFACTURED UNITS

- .1 Fixtures: manufacture in accordance with CAN/CSA-B45 series.
- .2 Trim, fittings: manufacture in accordance with CSA B125.3.
- .3 Exposed plumbing brass to be chrome plated.
- .4 Number, locations: as shown on drawings.
- .5 Fixtures in any one location to be product of one manufacturer and of same type.
- .6 Trim in any one location to be product of one manufacturer and of same type.
- .7 Water closets: refer to schedule.
- .8 Washroom Lavatories: refer to schedule.
- .9 Chair carriers:
 - .1 Factory manufactured floor-mounted carrier systems for wall-mounted fixtures.

Part 3 Execution

3.1 EXAMINATION

- .1 Verification of Conditions:
 - .1 Visually inspect substrate in presence of Departmental Representative.
 - .2 Inform Departmental Representative of unacceptable conditions immediately upon discovery.
 - .3 Proceed with installation only after unacceptable conditions have been remedied and after receipt of written approval to proceed from Departmental Representative.

3.2 INSTALLATION

- .1 Mounting heights: refer to schedule.
 - .1 Barrier-free: to most stringent CSA B651, NBC.

3.3 ADJUSTING

- .1 Conform to water conservation requirements specified this section.

- .2 Adjustments:
 - .1 Adjust water flow rate to design flow rates.
 - .2 Adjust pressure to fixtures to ensure no splashing at maximum pressures.
 - .3 Adjust flush valves to suit actual site conditions.
- .3 Checks:
 - .1 Water closets: flushing action.
 - .2 Aerators: operation, cleanliness.
 - .3 Vacuum breakers, backflow preventers: operation under all conditions.
- .4 Thermostatic controls:
 - .1 Verify temperature settings, operation of control, limit and safety controls.

3.4 CLEANING

- .1 Progress Cleaning: clean in accordance with Section 01 74 00 - Cleaning.
 - .1 Leave Work area clean at end of each day.
- .2 Final Cleaning: upon completion remove surplus materials, rubbish, tools and equipment in accordance with Section 01 74 00 - Cleaning.
- .3 Waste Management: separate waste materials for recycling in accordance with Section 01 74 19 - Construction/Demolition Waste Management and Disposal.
 - .1 Remove recycling containers and bins from site and dispose of materials at appropriate facility.

END OF SECTION

Part 1 General

1.1 REFERENCES

- .1 Canadian Standards Association (CSA International)
 - .1 CAN/CSA-B45 Series, Plumbing Fixtures.
 - .2 CAN/CSA-B125.3, Plumbing Fittings.
 - .3 CAN/CSA-B651, Accessible Design for the Built Environment.

1.2 ACTION AND INFORMATIONAL SUBMITTALS

- .1 Provide submittals in accordance with Section 01 33 00 - Submittal Procedures.
- .2 Product Data:
 - .1 Provide manufacturer's printed product literature and datasheets for fixtures, and include product characteristics, performance criteria, physical size, finish and limitations.

1.3 CLOSEOUT SUBMITTALS

- .1 Provide maintenance data in accordance with Section 01 78 00 - Closeout Submittals.
- .2 Include:
 - .1 Description of fixtures and trim, giving manufacturer's name, type, model, year, capacity.
 - .2 Details of operation, servicing, maintenance.
 - .3 List of recommended spare parts.

1.4 DELIVERY, STORAGE AND HANDLING

- .1 Deliver, store and handle in accordance with Section 01 61 00 - Common Product Requirements.
- .2 Deliver materials to site in original factory packaging, labelled with manufacturer's name, address.
- .3 Packaging Waste Management: remove for reuse by manufacturer of pallets crates padding packaging materials in accordance with Section 01 74 19 - Construction/Demolition Waste Management and Disposal.

Part 2 Products

2.1 MANUFACTURED UNITS

- .1 Fixtures: manufacture in accordance with CAN/CSA-B45 series.
- .2 Trim, fittings: manufacture in accordance with CAN/CSA-B125.

- .3 Exposed plumbing brass to be chrome plated.
- .4 Number, locations: architectural drawings to govern.
- .5 Fixtures to be product of one manufacturer.
- .6 Trim to be product of one manufacturer.
- .7 Mop sinks:
 - .1 Refer to schedule.
- .8 Chair carriers:
 - .1 Factory manufactured floor-mounted carrier systems for all wall-mounted fixtures.

Part 3 Execution

3.1 APPLICATION

- .1 Manufacturer's Instructions: comply with manufacturer's written recommendations, including product technical bulletins, handling, storage and installation instructions, and datasheets.

3.2 INSTALLATION

- .1 Mounting heights:
 - .1 Standard: to comply with manufacturer's recommendations unless otherwise indicated or specified.
 - .2 Physically handicapped: to comply with most stringent of either NBC or CAN/CSA-B651.

3.3 ADJUSTING

- .1 Conform to water conservation requirements specified this section.
- .2 Adjustments:
 - .1 Adjust water flow rate to design flow rates.
 - .2 Adjust pressure to fixtures to ensure no splashing at maximum pressures.
- .3 Checks:
 - .1 Aerators: operation, cleanliness.
 - .2 Vacuum breakers, backflow preventers: operation under all conditions.
 - .3 Wash fountains: operation of flow-actuating devices.
- .4 Thermostatic controls:
 - .1 Verify temperature settings, operation of control, limit and safety controls.

3.4 CLEANING

- .1 Clean in accordance with Section 01 74 00 - Cleaning.

- .1 Remove surplus materials, excess materials, rubbish, tools and equipment.
- .2 Waste Management: separate waste materials for recycling in accordance with Section 01 74 19 - Construction/Demolition Waste Management and Disposal.

END OF SECTION

Part 1 General

1.1 REFERENCES

- .1 Canadian Standards Association (CSA International)
 - .1 CAN/CSA-B45 Series, Plumbing Fixtures.
 - .2 CAN/CSA-B125.3, Plumbing Fittings.
 - .3 CAN/CSA-B651, Accessible Design for the Built Environment.

1.2 ACTION AND INFORMATIONAL SUBMITTALS

- .1 Provide submittals in accordance with Section 01 33 00 - Submittal Procedures.
- .2 Product Data:
 - .1 Provide manufacturer's printed product literature and datasheets for fixtures, and include product characteristics, performance criteria, physical size, finish and limitations.

1.3 CLOSEOUT SUBMITTALS

- .1 Provide maintenance data including monitoring requirements for incorporation into manuals specified in Section 01 78 00 - Closeout Submittals.
- .2 Include:
 - .1 Description of fixtures and trim, giving manufacturer's name, type, model, year, capacity.
 - .2 Details of operation, servicing, maintenance.
 - .3 List of recommended spare parts.

1.4 DELIVERY, STORAGE AND HANDLING

- .1 Deliver, store and handle in accordance with Section 01 61 00 - Common Product Requirements.
- .2 Deliver materials to site in original factory packaging, labelled with manufacturer's name, address.
- .3 Packaging Waste Management: remove for reuse by manufacturer of pallets crates padding packaging materials in accordance with Section 01 74 19 - Construction/Demolition Waste Management and Disposal.

Part 2 Products

2.1 MANUFACTURED UNITS

- .1 Fixtures: manufacture in accordance with CAN/CSA-B45 series.
- .2 Trim, fittings: manufacture in accordance with CAN/CSA-B125.3.

- .3 Exposed plumbing brass to be chrome plated.
- .4 Number, locations: architectural drawings to govern.
- .5 Fixtures in any one location to be product of one manufacturer and of same type.
- .6 Trim in any one location to be product of one manufacturer and of same type.
- .7 Baths: refer to schedule.

Part 3 Execution

3.1 APPLICATION

- .1 Manufacturer's Instructions: comply with manufacturer's written recommendations, including product technical bulletins, handling, storage and installation instructions, and datasheets.

3.2 INSTALLATION

- .1 Mounting heights:
 - .1 Standard: to comply with manufacturer's recommendations unless otherwise indicated or specified.
 - .2 Physically handicapped: to comply with most stringent of either NBCC or CAN/CSA B651.

3.3 ADJUSTING

- .1 Conform to water conservation requirements specified this section.
- .2 Adjustments:
 - .1 Adjust water flow rate to design flow rates.
 - .2 Adjust pressure to fixtures to ensure no splashing at maximum pressures.
- .3 Checks:
 - .1 Aerators: operation, cleanliness.
 - .2 Vacuum breakers, backflow preventers: operation under all conditions.
- .4 Thermostatic controls:
 - .1 Verify temperature settings, operation of control, limit and safety controls.

3.4 CLEANING

- .1 Clean in accordance with Section 01 74 00 - Cleaning.
 - .1 Remove surplus materials, excess materials, rubbish, tools and equipment.
- .2 Waste Management: separate waste materials for recycling in accordance with Section 01 74 19 - Construction/Demolition Waste Management and Disposal.

PWGSC/TPSGC Project R.100429.001
Jasper Staff Housing
902 Patricia St. 5-Plex
Jasper, AB

Section 22 42 20
COMMERCIAL SHOWERS AND BATHTUBS

Page 3 of 3

END OF SECTION