

PART 1 GENERAL

1.1 ACCESS AND EGRESS

- .1 Design, construct and maintain temporary "access to" and "egress from" work areas, including stairs, runways, ramps or ladder and scaffolding, independent of finished surfaces and in accordance with relevant municipal, provincial and other regulations.

1.2 USE OF SITE AND FACILITIES

- .1 Execute work with least possible interference or disturbance to normal use of premises. Make arrangements with Departmental Representative to facilitate work as stated.
- .2 Maintain existing services to building and provide for personnel and vehicle access. Provide temporary dust screens, barriers, warning signs in locations where renovation and alteration work is adjacent to areas which will be operative during such work.
- .3 Where security is reduced by work provide temporary means to maintain security.
- .4 Departmental Representative will assign sanitary facilities for use by Contractor's personnel. Keep facilities clean and provide paper products as necessary.
- .5 Use only elevators existing in building for moving workers and material.
 - .1 Protect walls of passenger elevators, to approval of Departmental Representative prior to use.
 - .2 Accept liability for damage, safety of equipment and overloading of existing equipment.
- .7 Note that there are existing only two elevators on campus, one in Telecom and one in Cabot near the Galley. There are several barrier free lifts throughout the campus. Obtain permission from Departmental Representative to access these lifts.
- .8 Closures: protect work temporarily until permanent enclosures are completed.

1.3 SPECIAL REQUIREMENTS

- .1 Carry out noise generating Work in Monday to Friday from 18:00 to 07:00 hours and on Saturdays, Sundays, and statutory holidays.
- .2 Submit schedule in accordance with Section 01 32 15
- .3 Ensure Contractor's personnel employed on site become familiar with and obey regulations including safety, fire, traffic and security regulations.
- .4 Keep within limits of work and avenues of ingress and egress.
- .5 Minimize Contractor use of vehicles on site, keeping fire access roads free.
- .6 Coordinate delivery of materials with Departmental Representative.

1.4 BUILDING SMOKING ENVIRONMENT

- .1 Comply with smoking restrictions. Smoking is not permitted.

PART 2 PRODUCTS

2.1 NOT USED

PART 3 EXECUTION

3.1 NOT USED

END