

The following changes to the tender documents are effective immediately. This amendment will form part of the contract documents.

Amendment 02 is issued for the following:

- (1) Provide Addendum 01 Revised Specifications and Drawings**
- (2) Post Questions and Answers**

(1) Provide Addendum Revised Specifications and Drawings

Added: ADDENDUM 01 Revised DSR

(2) Post Questions and Answers

Q1

On E3 power note #5, it asks for a couple volume controls, is there a spec for these controls?

A1

GWAL: volume control to be compatible with Bogen system, contractor to bid as per the contract document.

Q2

On E3 power note #5, is conduit to run to second floor tuner and third floor Bogen System? If so where is the Bogen system located on drawings?

A2

GWAL: system is located on the third floor at the end of the conduit as indicated on E3, contractor to bid as per the contract document.

Q3

The miscellaneous glazing in the hollow metal doors specify a 10mm one way mirrored glazing. We would use a product call Mirropane. Mirropane's max. thickness is 6mm opposed to the requested 10mm. If you require 10mm thickness that you would have to use an after-market film. Please clarify if 6mm tempered mirropane is acceptable for the miscellaneous glazing in the hollow metal doors.

A3

The 6mm Mirropane that is tempered for *safety glazing is acceptable. Coordinate the light levels to ensure that ratio meets the requirements.*

Q4

As per note #27 on A202 "Slab to slab.... highest 2747 mm" and GB ceiling shown on A302 highest 2737 mm AFF which leaves no plenum space above. So what the actual measurement from slab to slab?

A4

Delete note #27 on drawing A202. Slab height varies +/- 3567mm.

Q5

Will the work be completed in phases?

A5

The schedule must show a phased approach to the Work. Phase 1 to encompass all work on the second floor. Phase 2 to encompass all work on the third floor. Allow for two weeks between the completion of phase 1 and the start of phase 2 so the areas subject to Work on the third floor can be vacated by the Departmental Representative.

Q6

Dirty Corridor 215 is new drywall partition required? No Wall Legend shown

A6

Please see Addendum 1, Item number 1.28

Q7

Clean Corridor 200 is new drywall partition required? No Wall Legend shown

A7

Please see Addendum 1, Item number 1.28

Q8

Dirty Cage Area 214 is new drywall partition required on east wall -No Wall Legend shown

A8

Please see Addendum 1, Item number 1.28

ALL OTHER TERMS AND CONDITIONS REMAIN THE SAME