

**Part 1 General**

**1.1 RELATED SECTIONS**

- .1 Division 1

**1.2 REFERENCES**

- .1 CSA International
  - .1 CSA S350-M, Code of Practice for Safety in Demolition of Structures.
- .2 U.S. Environmental Protection Agency (EPA)/Office of Water
  - .1 EPA 832/R-92-005, Storm Water Management for Construction Activities: Developing Pollution Prevention Plans and Best Management Practices.

**1.3 ACTION AND INFORMATIONAL SUBMITTALS**

- .1 Submit in accordance with Division 1.

**1.4 SITE CONDITIONS**

- .1 Review "Designated Substance Report" and take precautions to protect environment.
- .2 If material resembling spray or trowel-applied asbestos or other designated substance listed as hazardous be encountered, stop work, take preventative measures, and notify Departmental Representative immediately.
- .3 Proceed only after receipt of written instructions has been received from Departmental Representative.
- .4 Notify Departmental Representative before disrupting building access or services.

**Part 2 PRODUCTS**

**2.1 NOT USED**

- .1 Not used.

**Part 3 EXECUTION**

**3.1 EXAMINATION**

- .1 Inspect building site with Departmental Representative and verify extent and location of items designated for removal, disposal, alternative disposal, recycling, salvage and items to remain.
  - .2 Locate and protect utilities. Preserve active utilities traversing site in operating condition.
  - .3 Notify and obtain approval of utility companies before starting demolition.
-

- .4 Disconnect, cap, plug or divert, as required, existing public utilities within the property where they interfere with the execution of the work, in conformity with the requirements of the authorities having jurisdiction. Mark the location of these and previously capped or plugged services on the site and indicate location (horizontal and vertical) on the record drawings. Support, shore up and maintain pipes and conduits encountered.
- .5 Immediately notify Departmental Representative and utility company concerned in case of damage to any utility or service, designated to remain in place.
- .6 Immediately notify the Departmental Representative should uncharted utility or service be encountered, and await instruction in writing regarding remedial action.

### 3.2 PREPARATION

- .1 Protection of In-Place Conditions:
  - .1 Prevent movement, settlement, or damage to adjacent structures, utilities, and landscaping features and parts of building to remain in place. Provide bracing and shoring required.
  - .2 Keep noise, dust, and inconvenience to occupants to minimum.
  - .3 Protect building systems, services and equipment.
  - .4 Provide temporary dust screens, covers, railings, supports and other protection as required.
  - .5 Do Work in accordance with Section 01 35 29.06 - Health and Safety Requirements.
- .2 Demolition/Removal:
  - .1 Remove items as indicated.
  - .2 Remove parts of existing building to permit new construction.
  - .3 Trim edges of partially demolished building elements to tolerances as defined by Departmental Representative to suit future use.

### 3.3 CLEANING

- .1 Progress Cleaning: clean in accordance with Section 01 74 11 - Cleaning.
  - .1 Leave Work area clean at end of each day.
- .2 Final Cleaning: upon completion remove surplus materials, rubbish, tools and equipment in accordance with Division 1.
- .3 Refer to demolition drawings and specifications for items to be salvaged for reuse.
- .4 Waste Management: separate waste materials for reuse and recycling in accordance with Division 1.
- .5 Remove recycling containers and bins from site and dispose of materials at appropriate facility.

END OF SECTION

---