


1 ID-161 FLOOR & WALL FINISHES PLAN

SCALE : 1:100

0m 1m 2m 3m 4m 5m 6m 7m 8m 9m 10m




2 ID-161 ENLARGED FINISH PLAN – RM 301A & CORRIDOR 302

SCALE : 1:50

0mm 10 20 30 40 50 60 70 80 90 100mm




3 ID-161 ENLARGED FINISH PLAN MEZZANINE

SCALE : 1:50

0mm 10 20 30 40 50 60 70 80 90 100mm




4 ID-161 ENLARGED FINISH PLAN LOBBY

SCALE : 1:50

0mm 10 20 30 40 50 60 70 80 90 100mm

## WALL FINISHES LEGEND

AREA NOT IN CONTRACT

## WALL FINISHES SCHEDULE

PT–1 PAINT FINISH 1 – PAINT TO MATCH EXISTING. PAINT GYPSUM REPAIR WORK AT WALLS AND BULKHEADS PT–1 UNLESS OTHERWISE NOTED

PT–2 PAINT FINISH 2 – WALL FIELD COLOUR

PT–3 PAINT FINISH 3 – BASE B1 PAINT COLOUR

WC–1 VINYL WALL COVERING TYPE 1

## ACOUSTIC ACCESSORIES

REFERENCE ELEVATIONS FOR LOCATION AND DETAIL INFORMATION.

FLT1 ACOUSTIC FELT TYPE 1
SUSPENDED FELT ACOUSTIC PANEL.
SUPPORT AT FLOOR & CEILING.
REFERENCE ELEVATION & SPEC.

FLT2 ACOUSTIC FELT TYPE 2
SURFACE–APPLIED FELT ACOUSTIC PANEL.
REFERENCE ELEVATION & SPEC.

FLT3 ACOUSTIC FELT TYPE 3
CEILING–SUSPENDED ACOUSTIC BAFFLE
REFERENCE ROP & SPEC.
QTY 7 @ 3050 LENGTH,
QTY 4 @ 2440 LENGTH

FLT4 ACOUSTIC FELT TYPE 4
SLIDING PANEL COMPLETE W/ HARDWARE. REFERENCE ELEVATION & SPEC.

## FLOOR FINISHES LEGEND

AREA NOT IN CONTRACT

EXHIBIT FLOOR MURAL AREA TO BE PROTECTED AND MAINTAINED. EXISTING FLOOR, WALL, AND CEILING FINISHES TO REMAIN IN GOOD CONDITION.

T1 TRANSITION TYPE 1: CARPET TO EXISTING TILE REFERENCE SPEC

T2 TRANSITION TYPE 2: EXISTING THRESHOLD TO RE–INSTATE

EX CT EXISTING PORCELAIN TILE TO REMAIN

CPT1 CARPET TILE TYPE 1 NO BASE UNLESS OTHERWISE SPECIFIED

CPT2 CARPET TILE TYPE 2 NO BASE UNLESS OTHERWISE SPECIFIED

PATTERN DIRECTION

## WALL BASE LEGEND

B1: 4" (100MM) HIGH X ¾" 19MM) THICK MDF BASE. SQUARE PROFILE. PAINT PT–3.

## WALL & FLOOR FINISHES PLAN NOTES

01 LINE OF BULKHEAD ABOVE

02 ALIGN END OF CARPET WITH FURNITURE DESK. REFERENCE FURNITURE PLAN.

03 WALL COVERING AND WALL BASE TO WRAP CORNER OF WALL END.

04 CPT–2 'STRIP' DETAIL TO BE OF EQUAL WIDTH AT ALL LOCATIONS.

Public Works and Government Services Canada / Travaux Publics et Services gouvernementaux Canada

FBM ARCHITECTURE • INTERIOR DESIGN

ASSOCIATION OF INTERIOR DESIGNERS REGISTERED Emma L. Woodhull Date: 060 NOVA SCOTIA

| | | |
|---|---|---|
| 1 | ISSUE FOR TENDER | 12/12 |
| B | ISSUE FOR 99% | 11/15 |
| A | ISSUE FOR 50% | 09/06 |
| revisions | | date |

project / projet

GC CO–WORKING SITE PILOT PROGRAM AT BIO FACILITY
1 CHALLENGER DRIVE
DARTMOUTH, NS

drawing / dessin

NEW FLOOR FINISHES & WALL FINISHES PLAN

LEVEL 3
HOLLAND BUILDING

designed NLS/ELW conçu
date
drawn RWTW/ELW dessiné
date
approved approuvé
date
Tender / Soumission
CL LeBlanc, Connor
PWGSC Project Manager / Administrateur de projets TPSGC
project number / no. du projet
R.101402.002
drawing no. / no. du dessin
ID–161

PWGSC A1 (2004)

E–DRM/GDD–E: 553075