



RETURN BIDS TO:

RETOURNER LES SOUMISSIONS À:

Bid Receiving Public Works and Government
Services Canada/Réception des soumissions Travaux
publics et Services gouvernementaux Canada
800 Burrard Street, Room 219
800, rue Burrard, pièce 219
Vancouver
British Columbia
V6Z 0B9
Bid Fax: (604) 775-9381

SOLICITATION AMENDMENT MODIFICATION DE L'INVITATION

The referenced document is hereby revised; unless otherwise
indicated, all other terms and conditions of the Solicitation
remain the same.

Ce document est par la présente révisé; sauf indication contraire,
les modalités de l'invitation demeurent les mêmes.

Comments - Commentaires

THIS DOCUMENT CONTAINS A SECURITY
REQUIREMENT

Vendor/Firm Name and Address

Raison sociale et adresse du
fournisseur/de l'entrepreneur

Issuing Office - Bureau de distribution

Public Works and Government Services Canada - Pacific
Region
800 Burrard Street, Room 219
800, rue Burrard, pièce 219
Vancouver
British C
V6Z 0B9

Title - Sujet High Voltage Maintenance	
Solicitation No. - N° de l'invitation EZ108-201858/A	Amendment No. - N° modif. 001
Client Reference No. - N° de référence du client	Date 2020-01-23
GETS Reference No. - N° de référence de SEAG PW-\$PWY-028-8728	
File No. - N° de dossier PWY-9-42208 (028)	CCC No./N° CCC - FMS No./N° VME
Solicitation Closes - L'invitation prend fin at - à 02:00 PM on - le 2020-02-10	Time Zone Fuseau horaire Pacific Standard Time PST
F.O.B. - F.A.B. Plant-Usine: <input type="checkbox"/> Destination: <input checked="" type="checkbox"/> Other-Autre: <input type="checkbox"/>	
Address Enquiries to: - Adresser toutes questions à: Lam (PWY), Tian	Buyer Id - Id de l'acheteur pwy028
Telephone No. - N° de téléphone (604) 363-7968 ()	FAX No. - N° de FAX (604) 775-6633
Destination - of Goods, Services, and Construction: Destination - des biens, services et construction: PWGSC - Esquimalt Graving Dock - Victoria, BC	

Instructions: See Herein

Instructions: Voir aux présentes

Delivery Required - Livraison exigée	Delivery Offered - Livraison proposée
Vendor/Firm Name and Address Raison sociale et adresse du fournisseur/de l'entrepreneur	
Telephone No. - N° de téléphone Facsimile No. - N° de télécopieur	
Name and title of person authorized to sign on behalf of Vendor/Firm (type or print) Nom et titre de la personne autorisée à signer au nom du fournisseur/ de l'entrepreneur (taper ou écrire en caractères d'imprimerie)	
Signature	Date

The Solicitation Amendment 001 is raised to update the mandatory site visit instructions, issue the Addendum 001 and attach new drawings.

1) In the solicitation documents at page 3 of 18:

a. Under SI03 Mandatory Site Visit, Paragraph 3:

DELETE: PWGSC Operations Centre, Building 2025

INSERT: PWGSC Security Trailer Boardroom, Building 2026

2) Please see Addendum 001 herein.

3) Please view and download the new drawings file (as referenced in Addendum 001) under "Attachments" entitled: TENDER-EGD-ESQUIMALT-R.106345.001-HIGH VOLTAGE MAINTENANCE-ADDENDUM 01 DRAWINGS-22_01_2020.

All other terms and conditions remain unchanged.

APPENDIX 1 - COMBINED PRICE FORM – REVISION 1

- 1) The prices per unit will govern in establishing the Total Extended Amount. Any arithmetical errors in this Appendix will be corrected by Canada.
- 2) Canada may reject the bid if any of the prices submitted do not reasonably reflect the cost of performing the part of the work to which that price applies.

UNIT PRICE TABLE

The Unit Price Table designates Work to which a Unit Price Arrangement applies.

- (a) Work included in each item is as described in the referenced specification section.
- (b) The Price per Unit shall not include any amounts for Work that is not included in that unit price Item.

The following are the Tender Items for work, including all labour, material, tools, equipment, overhead, and profit, required to complete the works as described in the attached Specifications and Drawings. The Unit Prices for these Tender Items may be used to adjust the Contract price as the scope of work increases or decreases as required by the Departmental Representative.

	Class of Labour, Plant or Material	Specification Section	Unit of Measure	Estimated Quantity (EQ)	Price per Unit (PU) applicable taxes extra	Extended amount (EQ x PU) applicable taxes extra
1	Pre-Mobilization Submittals	012520 -1.1.1	Lump Sum	1		
2	Mobilization	012520 -1.1.2	Lump Sum	1		
3	Site Preparation	012520 -1.1.3	Lump Sum	1		
4	Relocation of Residential Trailers	012520-1.1.4	Lump Sum	1		
5	Construction of Mezzanine	012520-1.1.5	Lump Sum	1		
6	Weigh Scale placed at Site	012520-1.1.6	Lump Sum	1		
7	Standby Time	012520 -1.1.7	Days	2		
8	Site Restoration	012520 -1.1.8	Lump Sum	1		
9	Demobilization	012520 -1.1.9	Lump Sum	1		
10	Closeout Submittals	012520 -1.1.10	Lump Sum	1		
11	Non-Contaminated Quality Material Transport and Disposal	013543 – 1.1.1	Tonnes	10		
12	Site Facilities – Provision	015200 – 1.1.1	Lump Sum	1		
13	Site Facilities - Operation	015200 – 1.1.2	Lump Sum	1		

	Class of Labour, Plant or Material	Specification Section	Unit of Measure	Estimated Quantity (EQ)	Price per Unit (PU) applicable taxes extra	Extended amount (EQ x PU) applicable taxes extra
14	Contaminated Water Treatment and Disposal - Provision	026100.01 – 1.1.1	Lump Sum	1		
15	Contaminated Water Treatment - Operation	026100.01 – 1.1.2	Liters	2,000		
16	Oversize Debris Removal	026100.02 – 1.1.1	Hours	24		
17	Excavation	026100.02 – 1.1.2	Tonnes	7,465		
18	Temporary Sloping and Shoring	026100.02 1.1.3	Lump Sum	1		
19	Backfill-Imported – Surfacing and Subbase Aggregate	026100.02 – 1.1.4	Tonnes	1,845		
20	Backfill-Owner Supplied – Stringer Creek Pit	026100.02 – 1.1.5	Tonnes	1,124		
21	Backfill-Owner Supplied - Wood Creek Pit	026100.02 – 1.1.5	Tonnes	4,496		
22	Backfill – Import – Control Density Fill	026100.02 - 1.1.6	m ³	200		
23	Fertilizer Supply and Application	026100.07 – 1.1.2	Tonnes	4		
24	Water Application	026100.07 – 1.1.3	Litres	3,000		
25	Aerator Operation	026100.07 – 1.1.4	Hours	120		
26	Bioremediated Soil Relocation	026100.07 – 1.1.5	m ³	2,376		
27	Soil Sampling Assistance	026100.07 – 1.1.6	Hours	12		
28	Compliant Soil Relocation	026100.07 – 1.1.7	m ³	2,376		
TOTAL BID AMOUNT (Sum of Total Extended Amounts, plus applicable taxes extra)						

All other terms and conditions remain unchanged.

THE FOLLOWING ADDENDUM SUPERCEDES INFORMATION CONTAINED IN DRAWINGS AND SPECIFICATIONS ISSUED FOR THE PROJECT TO THE EXTENT REFERENCED. THE FOLLOWING CHANGES IN THE TENDER DOCUMENTS ARE EFFECTIVE IMMEDIATELY. THIS ADDENDUM WILL FORM PART OF THE CONTRACT DOCUMENTS.

SPECIFICATIONS

1. Section 01 35 33 – Health and Safety Requirements

- .1 Delete Clause (1.36.1.11) entirely
- .2 Add new Clause (1.36.1.11) as follows:
“Electrical installation permit for project work, including a BC Safety Authority Permit. A Township of Esquimalt Permit is not required for this project.”

2. Section 01 11 55 General Instructions

- .3 Change Clause (1.10.3) as follows:
Replace the acronym “SSSR” with “SSS”
- .4 Change Clause (1.10.3.2) as follows:
Replace the acronym “SSSR” with “SSS”

3. Section 26 08 01 – HV System Maintenance, Inspection, and Calibration

- .1 Add new Clause (2.1.13) as follows:
 - SES-ATS-1
 - 400A Generator Supplied Disconnect
 - 400A Utility Supply Disconnect
- .2 Add new Clause (2.1.14) as follows:
 - 6SES-SP-1 Manual Transfer Pair
 - 250AF/250AT K46 keyed interlock of Manual Transfer pair with
 - 400AF/300AT K46 keyed interlock Manual Transfer pair
- .3 Add new Clause (2.1.15) as follows:
 - Manual Transfer Switch
 - 400A, 3 Pole
 - Includes generator connector box
- .4 Add new Clause (2.2.17) as follows:
 - PHS-ATS-1

- 400A Generator Supplied Disconnect
 - 400A Utility Supply Disconnect
- .5 Add new Clause (2.2.18) as follows:
- 6PHS-SP-1-2 Manual Transfer Pair
 - 400AF/400AT K3 keyed interlock of Manual Transfer pair with
 - 400AF/400AT K3 keyed interlock Manual Transfer pair
- .6 Add new Clause (2.3.22) as follows:
- Manual Transfer Switch
 - 400A, 3 Pole
 - Includes generator connector box
- .7 Delete Clause (3.2.10.1) entirely
- .8 Add new Clause (3.2.10.1) as follows:
"3.2.10.1: Test, calibrate, and verify the control wiring for ground fault relays as listed."

4. All Sections:

- .1 "SSS" and "SSSR" are used throughout the tender documents, standing for "South Side Substation" and "South Side Substation Replacement", respectively. The SSSR was the original name for the substation, which became the permanent SSS on completion of construction. "SSS" and "SSSR" are used interchangeably throughout the project scope documents and should be considered the same Substation. SSS shall be used going forward and shall be used for any labels or when recording information.

DRAWINGS

1. EGD-SSS STANDBY POWER GENERATION SYSTEM

- .1 Add new drawing as follows:
Sheet 8411, Service Entrance Substation Low Voltage Single Line Diagram, Revision 5, Issued for As-Built May 25, 2017. Attached Separately
- .2 Add new drawing as follows:
Sheet 8455, South Side Substation Replacement Low Voltage Single Line Diagram (For Information Only), Revision 5, Issued for As-Built May 25, 2017. Attached Separately

END OF ADDENDUM NO. 001