

Containment Berm Construction**Newellton Harbour SCH****Shelburne County Nova Scotia****Project No: R.106630.001**

Sitework, Demolition and Removals

Page 1

PART 1 - GENERAL

- | | | |
|-----|--------------------------------|--|
| 1.1 | <u>Description of Work</u> | This Section includes but is not limited to the following:

.1 All normal removals as required to complete the work. All items to be verified by a site visit prior to submission of a tender. |
| 1.2 | <u>Related Work</u> | .1 Refer to other specification sections for related information. |
| 1.3 | <u>Submissions</u> | .1 Methodology:
.1 When requested provide methodology for carrying out the work. |
| 1.4 | <u>Protection</u> | .1 Prevent movement, settlement or damage of adjacent structures. Provide bracing and shoring as required. In event of damage, immediately replace such items or make repairs to approval of <i>Departmental Representative</i> and at no additional cost to <i>Departmental Representative</i> .

.2 Prevent debris from going adrift and becoming a menace to navigation.

.3 All damage to existing structures, roadways, pipelines, electrical systems not specified for removal to be repaired at the Contractor's cost to the satisfaction of the <i>Departmental Representative</i> . |
| 1.5 | <u>Measurement for Payment</u> | .1 Sitework, demolition and removals will be measured in accordance with Section 01 29 00 . |

PART 2 - PRODUCTS

Not applicable.

Containment Berm Construction**Newellton Harbour SCH****Shelburne County Nova Scotia****Project No: R.106630.001**

Sitework, Demolition and Removals

Page 2

PART 3 - EXECUTION3.1 Preparation

- .1 Inspect site and verify with *Departmental Representative* items designated for removal and items to be preserved.
- .2 Locate and protect utility lines. Preserve in operating condition active utilities traversing site.
- .3 Provide temporary power and lighting as shown on the plan or as required by the *Departmental Representative*.
- .4 All repairs to damages as a result of Contractor's operations to be at Contractor's cost and to the satisfaction of the *Departmental Representative*.

3.2 Removal

- .1 Remove items indicated.
- .2 Do not disturb adjacent structures designated to remain in place.
- .3 At end of each day's work, leave work in safe condition so no part is in danger of toppling or falling.

3.3 Disposal of Material

- .1 Disposal of materials not designated for salvage or re-use in work, will be the contractor's responsibility, and must be disposed of off-site.
- .2 The material to be disposed is to be transported and disposed of in an environmentally acceptable manner to the satisfaction of the *Departmental Representative*, and in accordance with any local, Municipal, Provincial and Federal restrictions and regulations.

3.4 Restoration

- .1 Upon completion of work, remove debris, trim surfaces and leave work site clean.

Containment Berm Construction

Newellton Harbour SCH

Shelburne County Nova Scotia

Project No: R.106630.001

Sitework, Demolition and Removals

Page 3

- .2 Reinstall areas and existing works outside areas of demolition to conditions that existed prior to commencement of work. Match condition of adjacent, undisturbed areas.