

POWER & LIGHTING PLAN - SECOND FLOOR
SCALE: 1 : 50

GENREAL NOTES:

- A. REFER TO DRAWING E4.0 FOR PANEL SCHEDULES
- B. REFER TO DRAWING E4.0 FOR LUMINAIRE SCHEDULES.
- C. REFER TO MECHANICAL DRAWINGS FOR MECHANICAL EQUIPMENT SCHEDULE.
- D. ALL ELECTRICAL RISER CONDUIT, AND OPENINGS TO BE COORDINATED WITH ARCHITECTURAL AND STRUCTURAL PRIOR TO ROUGH IN.
- E. ELECTRICAL CONTRACTOR SHALL SUBMIT SLEEVING DRAWINGS INDICATING THE LAYOUT AND SIZING OF ALL INTENDED PENETRATIONS. THOUGH STRUCTURAL ELEMENTS, INCLUDING EMBEDDED ITEMS, FOR REVIEW BY CONSULTANT WELL IN ADVANCE OF COMPLETING THE WORK.
- F. MECHANICAL/ELECTRICAL SYSTEMS, THEIR SUPPORTS AND THE LIKE, MUST BE DESIGNED AND DETAILED TO ACCOMMODATE THE ANTICIPATED MOVMENTS NOTED UNDER 'SERVICEABILITY CRITERIA' ON STRUCTURAL DRAWINGS.
- G. DESIGN AND DETAIL ALL NECESSARY SEISMIC RESTRAINTS FOR MECHANICAL / ELECTRICAL SYSTEMS SHOWN ON THE CONTRACT DOCUMENTS. SUBMIT SHOP DRAWINGS PREPARED BY A PROFESSIONAL ENGINEER, LICENSED TO PRACTICE IN THE PROVINCE OF ALBERTA, FOR REVIEW BY CONSULTANTS.
- H. ELECTRICAL EQUIPMENT SHOWN REPRESENTS GENERAL EQUIPMENT CONFIGURATION AND SIZING. IT IS THE RESPONSIBILITY OF THE CONTRACTOR TO ENSURE THAT FINAL SELECTED WILL FIT IN LOCATIONS INDICATED.
- I. PROVIDE FIRE STOPPING ON ALL CABLE PENETRATIONS THROUGH RATED WALL AND FLOOR ASSEMBLIES.
- J. ALL RECEPTACLES TO BE CONNECTED TO ARC FAULT BREAKERS AS PER CEC 2018.
- K. ALL RECEPTACLES NOT INSTALLED BEHIND KITCHEN EQUIPMENT SHALL BE TAMPER RESISTANT AS PER CEC 2015.
- L. KITCHEN COUNTER RECEPTACLES SHALL BE 20A T-SLOT AS PER CEC 2015.
- M. COORDINATE LOCATIONS AND MOUNTING HEIGHTS OF RECEPTACLES, INCLUDING MICROWAVE, WITH ARCHITECTRUAL.
- N. DO NOT INSTALL OULET BOXES BACK TO BACK IN WALLS. OFFSET OUTLETS HORIZONTALLY A MINIMUM OF 406mm AS PER CODE. OUTLET BOXES TO BE SEALED.
- O. INSTALL EXTERIOR RECEPTACLES HORIZONTALLY COMPLETE WITH WEATHER PROOF COVERS AS PER CEC 2018.
- P. ALL GFCI AND AFCI BREAKERS TO MATCH THE RECEPTACLES.
- Q. SUPPLY AND INSTALL GFCI BREAKERS AND RECEPTACLES TO MEET REQUIREMENTS OF CEC 2018.
- R. COORDINATE LOCATIONS AND HEIGHT OF LUMINAIRES WITH ALL MECHANICAL DUCTWORK, PIPING AND STRUCTURAL MEMBERS.
- S. IN SUITE CIRCUITING REPRESENTS GENERAL COORDINATION AND GROUPING OF CIRCUITS. REFER TO PANEL SHEDULE THAT CORRESPONDS TO SPECIFIC SUITE TYPE.

REFFERAL NOTES:

- 1 30 MIN WALL TIMER TO BE INTERCONNECTED WITH EXHAUST FAN. TIMER SUPPLIED BY MECHANICAL AND WIRED BY ELECTRICAL.
- 2 FIXTURE TO BE MOUNTED ON INSIDE VERTICAL FACE OF CLOSET WALL ABOVE CLOSET DOOR.
- 3 JUNCTION BOX TO BE CAPABLE OF SUPPORTING A CEILING FAN, ADDITIONAL REINFORCEMENT TO BE INSTALLED AS REQUIRED. CEILING FAN TO BE LOW PROFILE 5 BLADE FAN WITH MAX. DIAMETER OF 42" IN FOUR(4) SMALLER BEDROOMS AND MAX DIAMETER OF 48" IN TWO(2) LARGER BEDROOMS. FAN TO BE CHAIN OPERATED, WITH 3 SPEED, ON/OFF OPERABILITY. FAN LIGHT TO SUPPORT MIN 2 13W LED BULBS.


REPUBLIC
ARCHITECTURE
INC

385 St. Mary Avenue
Winnipeg, MB R3C 0N1

T 204 989 0102

F 204 989 0094

www.republicarchitecture.ca



ALBERTA PERMIT TO PRACTICE

NUMBER-11944

MARCH 6, 2020

NORR

2300, 411 1st Street SE,
Calgary, Alberta, Canada T2G 4Y5
norr.com

NORR ARCHITECTS ENGINEERS PLANNERS

A Partnership of Limited Companies

From McKenzie Architects (Alberta) Inc. From McKenzie Holdings Inc.

NORR is a trademark owned by Norrman Group Inc. and is used under license.

Victor Smith, Architect, AAA, B.Arch, MABC
Bruce McKenzie, Architect, AAA, B.Arch, MABC
A. Shro Siddhewara, Architect, AAA, B.Arch, MABC
Anirban Tootlia, P.Eng., APEGA
Chris Piel, P.Eng., APEGA

Revised	Description	Date
5	ISSUED FOR CONSTRUCTION	2020-03-06
3	95% CLIENT REVIEW	2019-08-29
2	66% CLIENT REVIEW	2019-05-09
1	33% CLIENT REVIEW	2019-03-14

Client	Client
--------	--------

PSPC

10025 JASPER AVE
EDMONTON, AB, T5J 1S6
PH. 780-919-9445

Project title
JASPER STAFF HOUSING CONSTRUCTION

DUPLEX
720 PATRICIA STREET
JASPER, AB, T0E 1E0

Designed by
R.ALLEN

Drawn by
F.HAK

Approved by
D.HIDER

Project Manager / Administrateur de Projets / PM/AC
ROB HAFER

Drawing Title
POWER & LIGHTING PLAN - SECOND FLOOR

Project Number
R.100429.001

Project Name
JASPER STAFF HOUSING CONSTRUCTION

Project Location
720 PATRICIA STREET, JASPER, AB, T0E 1E0

Project Description
POWER & LIGHTING PLAN - SECOND FLOOR

Project Status
In Progress

Project Manager
Rob Hafner

Project Engineer
D. Hider

Project Architect
R. Allen

Project Designer
F. Hak

Project Draftsman
F. Hak

Project Checker
F. Hak

Project Approver
D. Hider

Project Reviewer
R. Allen