



RETURN BIDS TO:

RETOURNER LES SOUMISSIONS À:

Bid Receiving Box/Boîte de Réception des
Soumissions

1st Floor/1^{ère} étage, Suite 1212

100-1045 Main Street

Moncton

New Brunswick

E1C 1H1

Bid Fax: (506) 851-6759

SOLICITATION AMENDMENT MODIFICATION DE L'INVITATION

The referenced document is hereby revised; unless otherwise indicated, all other terms and conditions of the Solicitation remain the same.

Ce document est par la présente révisé; sauf indication contraire, les modalités de l'invitation demeurent les mêmes.

Comments - Commentaires

Vendor/Firm Name and Address

Raison sociale et adresse du
fournisseur/de l'entrepreneur

Issuing Office - Bureau de distribution

Acquisitions NB/PEI (Moncton Office) – Bureau
d'acquisitions N.-B./Î.-P.-É. (Moncton)
1045 Main Street / 1045, rue Main
Moncton
New Bruns
E1C 1H1

Title - Sujet Marshalling Yard Improvements-SJohn	
Solicitation No. - N° de l'invitation EB144-203131/A	Amendment No. - N° modif. 002
Client Reference No. - N° de référence du client EB144-203131	Date 2020-04-23
GETS Reference No. - N° de référence de SEAG PW-\$PWJ-005-5724	
File No. - N° de dossier PWJ-0-43001 (005)	CCC No./N° CCC - FMS No./N° VME
Solicitation Closes - L'invitation prend fin at - à 02:00 PM on - le 2020-04-29	
Time Zone Fuseau horaire Atlantic Daylight Saving Time ADT	
F.O.B. - F.A.B. Plant-Usine: <input type="checkbox"/> Destination: <input checked="" type="checkbox"/> Other-Autre: <input type="checkbox"/>	
Address Enquiries to: - Adresser toutes questions à: Lomax (PWJ), Sandra	Buyer Id - Id de l'acheteur pwj005
Telephone No. - N° de téléphone (506) 639-8503 ()	FAX No. - N° de FAX (506) 851-6759
Destination - of Goods, Services, and Construction: Destination - des biens, services et construction:	

Instructions: See Herein

Instructions: Voir aux présentes

Delivery Required - Livraison exigée	Delivery Offered - Livraison proposée
Vendor/Firm Name and Address Raison sociale et adresse du fournisseur/de l'entrepreneur	
Telephone No. - N° de téléphone Facsimile No. - N° de télécopieur	
Name and title of person authorized to sign on behalf of Vendor/Firm (type or print) Nom et titre de la personne autorisée à signer au nom du fournisseur/ de l'entrepreneur (taper ou écrire en caractères d'imprimerie)	
Signature	Date

This Solicitation Amendment No. two (2) is raised to include the following Addendum No. two (2).

The following Addendum to the tender is effective immediately. This addendum shall form part of the contract documents.

All other terms and conditions remain the same.

SOLICITATION

REMOVE “APPENDIX 1 – COMBINED PRICE FORM” and **REPLACE WITH** the “APPENDIX 1 – COMBINED PRICE FORM revised April 22, 2020”.

Note: “APPENDIX 1 – COMBINED PRICE FORM revised April 22, 2020” attached in this amendment is the Offer/Pricing Schedule that **MUST** be submitted with your offer. Failure to comply with this requirement will result in your offer being deemed non-responsive

QUESTIONS AND ANSWERS

1. **Question:** There is some ditching to be done that is also to be lined with R -5 Rip Rap. I didn't see a quantity for ditching or a quantity for R -5 .

Answer: The ditching is to be included in the contractors lump sum. The quantity of rip rap can be estimated from the plans.

2. **Questions:** I see the typical detail for the pipe trenches show Class " A " borrow between the pipe zone material and the subbase material. Are we allowed to reuse the material in that particular section of the trench if suitable? If not suitable, will there be additional payment for imported Class " A " borrow?

Answer: Contractor can propose the reuse of existing material if suitable. The unit price for pipe culvert is to include bedding material and no additional payment will be made if bedding material is imported from off site.

3. **Questions:** In the plans and specs for the Marshaling Yard Improvements and I don't see any information with regards to hi and low water elevations. This information is required as some of the underground services are installed near the water and the tide levels with likely impact this work. Does such information exist and if so can it be provided on the corresponding drawings.

Answer: Tide levels are publicly available and can be accessed from the following site:

<https://www.waterlevels.gc.ca/eng/station?sid=65>

4. **Questions:** The tender for calls for 310 meters of reinforced concrete curb but the detail does not show reinforcing and typically curb would not be reinforced, can you clarify the requirement for this item?

Answer: No reinforcement is required for the curb as shown in the detail.

5. **Questions:** How is the excavation and subsequent supply and placement of Granular base for the new curb and sidewalk going to be paid? Are these items incidental to the curb and sidewalk or are they measured for payment?

Answer: This work is considered incidentally to the construction of the curb and sidewalk and should be included in the unit price for this item.

6. **Questions:** In the spec under the section for measure for payment, division 31, what work is included under the item for excavation and backfilling that is to be included in the lump sum?

Answer: All excavation and backfill required to complete the work set out in this Contract that is not explicitly compensated as part of a unit price item should be included in the contractor's lump sum. See 01 29 00, Project Measurement 1.1

7. **Questions:** How will the ditch excavation/shaping and subsequent geotextile and R5 riprap be paid for the ditch along the northwest side of the marshaling yard?

Answer: These components are to be included in the contractor's lump sum.

8. **Questions:** Is there a pay item for landscape reinstatement (ie topsoil and sod/seed) or is it incidental to some other item?

Answer: This is to be included in the contractor's lump sum.

9. **Questions:** Is there an electrical drawing showing where the conduits are to go? Panel Requirements? What will be supplied in the chamber?

Answer: The general layout of the conduit is provided in the drawings C04. The panel schedule for the existing panel located in the Terminal Bldg (Panel TB-600V) has been included as an attachment to this solicitation.

APPENDIX 1 - COMBINED PRICE FORM – REVISED APRIL 22, 2020

- 1) The prices per unit will govern in establishing the Total Extended Amount. Any arithmetical errors in this Appendix will be corrected by Canada.
- 2) Canada may reject the bid if any of the prices submitted do not reasonably reflect the cost of performing the part of the work to which that price applies.

LUMP SUM

The Lump Sum Amount designates Work to which a Lump Sum Arrangement applies.

- (a) Work included in the Lump Sum Amount represents all work not included in the unit price table.

LUMP SUM AMOUNT (LSA) Excluding applicable tax(es)	
--	--

UNIT PRICE TABLE

The Unit Price Table designates Work to which a Unit Price Arrangement applies.

- (a) Work included in each item is as described in the referenced specification section.
 (b) The Price per Unit shall not include any amounts for Work that is not included in that unit price Item.

Item	Specification Reference	Class of Labour, Plant or Material	Unit of Measurement	Estimated Quantity (EQ)	Price per Unit applicable tax(es) extra (PU)	Extended amount (EQ x PU) applicable tax(es) extra
1	03 30 00	Reinforced Cast-in-Place Concrete Curb	Lineal Meter (m)	310		
2	03 30 00	Reinforced Cast-in-Place Concrete Sidewalk	Lineal Meter (m)	260		
3	32 01 16	Asphalt Milling & Removal (Treatment 1)	Square Meter (m ²)	19000		
4	33 01 16	Asphalt Milling & Removal (Treatment 2)	Square Meter (m ²)	4600		
5	32 11 02	Granular Base	Tonne	4100		
6	32 11 16.01	Granular Sub-Base	Tonne	4600		
7	32 12 16	Hot-Mix Asphalt (Type B)	Square Meter (m ²)	23600		
8	32 12 16	Hot-Mix Asphalt (Type D)	Square Meter (m ²)	23600		
9	32 32 13.13	Packaged Lift Station, Wet Well Type	Each	1		
10	33 34 00	Lift Station Force Mains, 75mm Ø PVC	Lineal Meter (m)	116		
11	33 42 13	Pipe Culvert, 100mm Ø Sanitary PVC	Lineal Meter (m)	33		
12	33 42 13	Pipe Culvert, 150mm Ø Sanitary	Lineal Meter (m)	130		

Item	Specification Reference	Class of Labour, Plant or Material	Unit of Measurement	Estimated Quantity (EQ)	Price per Unit applicable tax(s) extra (PU)	Extended amount (EQ x PU) applicable tax(s) extra
13	33 42 13	Pipe Culvert, 300mm Ø Storm	Lineal Meter (m)	20		
14	33 42 13	Pipe Culvert, 450mm Ø Storm	Lineal Meter (m)	18		
15	33 42 13	Pipe Culvert, 600mm Ø Storm	Lineal Meter (m)	49		
16	33 42 13	Pipe Culvert, 1200mm Ø Storm - 100D RCP	Lineal Meter (m)	51		
17	33 05 14	Pre-Cast Concrete Catch Basins, 750mm Ø	Each	1		
18	33 05 14	Pre-Cast Concrete Catch Basins, 1200mm Ø	Each	3		
19	33 05 14	Pre-Cast Concrete Lift Station Structure, 1500mm Ø	Each	1		
20	33 05 14	Pre-Cast Concrete Catch Basins, 2100mm Ø	Each	1		
21	35 31 23	Storm Outlet Bedding Material	Tonne	135		
22	35 31 23	Storm Outlet Core Material	Tonne	665		
23	35 31 23	Storm Outlet Armour Material	Tonne	1260		
TOTAL EXTENDED AMOUNT (TEA)						
						Excluding applicable tax(s)
LUMP SUM AMOUNT (TEA)						
						Excluding applicable tax(s)
TOTAL BID AMOUNT (LSA +TEA)						
						Excluding applicable tax(s)