



RETURN BIDS TO:
RETOURNER LES SOUMISSIONS À:
Specified herein - précisé dans les présentes.

SOLICITATION AMENDMENT
MODIFICATION DE L'INVITATION

The referenced document is hereby revised; unless otherwise indicated, all other terms and conditions of the Solicitation remain the same.

Ce document est par la présente révisé; sauf indication contraire, les modalités de l'invitation demeurent les mêmes.

Comments - Commentaires

Vendor/Firm Name and Address
Raison sociale et adresse du
fournisseur/de l'entrepreneur

Issuing Office - Bureau de distribution
TPSGC/PWGSC
1550 Avenue d'Estimauville
Québec
Québec
G1J 0C7

Title - Sujet Cale Sèche Martha L. Black 2020	
Solicitation No. - N° de l'invitation F3065-201043/A	Amendment No. - N° modif. 006
Client Reference No. - N° de référence du client F3065-201043	Date 2020-05-01
GETS Reference No. - N° de référence de SEAG PW-\$QCV-018-17905	
File No. - N° de dossier QCV-9-42262 (018)	CCC No./N° CCC - FMS No./N° VME
Solicitation Closes - L'invitation prend fin at - à 02:00 PM on - le 2020-05-14	Time Zone Fuseau horaire Heure Avancée de l'Est HAE
F.O.B. - F.A.B. Specified Herein - Précisé dans les présentes Plant-Usine: <input type="checkbox"/> Destination: <input type="checkbox"/> Other-Autre: <input checked="" type="checkbox"/>	
Address Enquiries to: - Adresser toutes questions à: Piras, Gabriel	Buyer Id - Id de l'acheteur qcv018
Telephone No. - N° de téléphone (418) 956-2350 ()	FAX No. - N° de FAX () -
Destination - of Goods, Services, and Construction: Destination - des biens, services et construction:	

Instructions: See Herein

Instructions: Voir aux présentes

Delivery Required - Livraison exigée	Delivery Offered - Livraison proposée
Vendor/Firm Name and Address Raison sociale et adresse du fournisseur/de l'entrepreneur	
Telephone No. - N° de téléphone Facsimile No. - N° de télécopieur	
Name and title of person authorized to sign on behalf of Vendor/Firm (type or print) Nom et titre de la personne autorisée à signer au nom du fournisseur/ de l'entrepreneur (taper ou écrire en caractères d'imprimerie)	
Signature	Date

**TITLE : CCGS Martha L. Black - Drydock Refit - 2020
Amendment 006**

Included in the present amendment:

1. Questions and answers 19 to 29
2. Modifications to the Specifications
3. Addition of technical documents

QUESTIONS AND ANSWERS

Question 19

In Spec 18.3.11 : Require the type of contents (additive etc.) in the cooling system for environmental disposal.

Answer : The additive is Drew Marine's Maxigard product. CORROSIVE INORGANIC LIQUID, BASIC, NSA (contains disodium metasilicate and sodium hydroxide).

Question 20

18.3.22 - The central cooling article requires to change the copper-nickel piping. However, plan 70-10-01 is the one of the actual installation on board. It does not show the sections to be changed, nor the lengths of pipes, nor the elbows or reducers. Can you give more information to allow us to properly assess the amount of material required for the bid?

Answer : The Cupro / Ni 90/10 piping sections are those of seawater, inlet and outlet, so two connections of 150 mm / 6 " on each of the coolers to be adapted and connected to the Cupro / Ni piping of the central cooling. It is difficult to predict the exact material requirement until the equipment is in place. On the photo of the document Pictures and videos / 19 - Central cooler replacement / 20200217_182812.jpg we can see that the connection is almost immediately made with a 90° elbow of 150 mm/6 " then a reducer 150 mm/6 " - 250 mm/10 ". Some additional photos of the Cupro/Ni sections are included.

Approximate existing dimensions for information, final dimensions to be taken on the ship by the contractor:

Front cooler: Top pipe 120 " between the outlet flange and the flange leading to the manifold, with reducer



Bottom pipe 30" between the cooler outlet flange to the flange leading to the manifold



Rear cooler: Top pipe 60 " between the cooler outlet flange to the flange that leads to the manifold, with reducer and 2 " bypass



Bottom pipe 22 " between the outlet flange of the cooler up to the flange that leads to the manifold, with reducer



Question 21

15.3.26 & 16.3.1 - The requested M24 anodes are no longer common in the industry, according to our suppliers. Z22 anodes are common and available. Can you address the question?

Answer : Anodes Z22 can replace the M24 anodes, at sections 15.3.26 and 16.3.1

Question 22

10.3.18 – Amercoat 238 for stern tubes no longer exists according to a representative of Amercoat PPG. Can you recommend another paint?

Answer : The PPG Quebec representative mentioned that they still have the product in inventory available, Amercoat 238 black.

Question 23

17.5.7 - The contractor must supply and install new 20 gauge 316 stainless steel sheets. Can you confirm that you want 316? Knowing that the kitchen equipment is made of 304 stainless steel and that 316 stainless steel is more expensive (35% more) than 304; (information from the SML supplier).

Answer : See MODIFICATIONS TO THE SPECIFICATIONS, below.

Question 24

17.5.8 - The Contractor must supply and install new stainless steel window boxes for the three kitchen windows by certified sheet metal professionals. Can we have the dimensions of the windows or a drawing?

Answer : L = 26" ; H = 28" ; D 14.5" (inside dimensions of the window boxe)

Question 25

27.2.1 - In order to price accurately, we will need to know what ends are on these hoses (i.e. camlocks, NPT, flanges etc.).

We know from past experience that some of the Coast Guard vessels sometimes have non-standard fittings (like BSP-British Standard Pipe).

Can you provide this information?

Answer : The answer will be provided soon.

Question 26


What is the type & quantity of oil required for job 29.0 – Hiab Cranes?

Answer : 100 liters of PC Hydrex MV Arctic 15

Question 27

What is the type of flooring, surface area & thickness of underlayment required for the flooring replacement in job 17.0 – Galley Refit?

Answer : Currently, the A-60 floor is multi-layer, on the deck as described above extracted from dwg H-3510, the new floor sections (total surface to replace is 350 sqft) must be of the same arrangement in order to tie with the existing sections et still meet A-60 Ref.17.3.13



Question 28

Will you be issuing new/revised Pricing data sheets based on the changes that have been made in the recent amendments?

Answer : Yes, the intention is to post a final version of Annex J – PRICING DATA SHEETS approximately one week before the Solicitation closing date. The goal is to avoid confusion that could be created by posting multiple versions. The same goes for Appendix 1 of Annex I – Price per Item Sheet.

Question 29

Our sub is requesting the serial number of the compressor in job 23.0. Can you advise on this?

Answer : Sérial number 96/2445/03
Manufacturer: JORDAIR, model K100-3EH
Manufactured: 1996
Pressure: 5000 PSI

MODIFICATIONS TO THE SPECIFICATIONS

The Technical Specifications are amended as follows :

17.2 : Add the following line to table "Drawings and documentation" :

H-3510	Deck covering plan
--------	--------------------

17.5.7, 17.5.8, 17.5.9 and 17.5.10 :

Delete : "316 stainless steelsteel with a finish no. 4", when applicable.
Instead, insert : "304 stainless steel with a finish no. 4",

45.1.B References :

Delete subsection "Drawings/ Documents" in its entirety.
Replace with :

- "Drawings/ Documents
a) 06-050-002 R1
b) M017-11-001
c) LM601-010-AL_V1
d) Sea Tel 120 TV Product Sheet
e) H-29-10
f) DSCF0501
g) DSCF0505"

ADDITION OF TECHNICAL DOCUMENTS

The following technical documents are included in this modification.

See electronic attachment « F3065-201043-A__References Modif 006 - References Amend 006.zip ».

ALL OTHER TERMS AND CONDITIONS REMAIN UNCHANGED.