

The following changes to the tender documents are effective immediately and will form part of the contract documents:

Enquiries received during the Solicitation Period:

Question 1: Please confirm that the PVC liner shall not be visible in cross section C/C04. (see attached drawing with mark-ups). This cross section appears to intersect the PVC liner on drawing C04 however cross section B/C03 shows the liner terminating on the North side of the sheet pile structure. Please confirm that there is no PVC liner on the South side of the sheet pile structure.

Response: Correct, the PVC liner should not be visible in C/C04 and there is no liner on the south-side of the sheet pile wall.

Question 2: Please confirm where the East end of the liner shall terminate on the downstream coffer dam. (see attached drawing with mark-ups). Cross Section D/C04 shows the liner anchored to a concrete wall within this vicinity however this cross section does not appear to intersect any concrete walls. Is it the designers intent to terminate the liner at the East end of the sheet pile structure, or wrap the liner around the outside of the concrete divider wall?

Response: The intent is that the liner wraps around the outside of the divider wall.

Question 3: Please describe how measurement and payment for supply and placement of pit run will be handled. (Items 7 & 8).

Response: These two items will be paid per cubic metre of pitrun installed and will be the same quantity for both. The quantity to be paid will be based on the neat line volume between the cofferdam foundation, as surveyed by the Contractor after sediment removal, and the cofferdam design lines and elevations provided in the Drawings. Monthly progress payment requests by the Contractor will need to include verification of the requested quantities (e.g. survey data, cross sections, calculations), and are subject to approval by the Departmental Representative.

Question 4: Please describe how measurement and payment for the excavation of sediment will be handled. (Item 11).

Response: As per Section 31 00 00.01, clause 3.01.1, the Contractor is to survey the cofferdam foundation locations to establish how much sediment to remove. "Bathymetric survey techniques" will be required to complete the downstream cofferdam footprint survey. Sediment removal will be paid per cubic metre of sediment removed as established by Contractor survey at the receiving off-site disposal location, and as approved by the Departmental Representative.

Question 5: Please describe how measurement and payment for supply and install non-woven geotextile will be handled. (Item 16).

Response: Item will be paid per square metre of geotextile installed. The quantity to be paid will be computed based on neat line area as illustrated in the Drawings (i.e., overlap and wastage will not be paid).

Question 6: Do you know when the contract will be awarded?

Response: Approximately 3 weeks from the date of tender close.

END OF ADDENDUM NO. 4