

SPECIFICATION

Emergency Generator Systems for
Search and Rescue Station Located
In Port Au Choix, NL

Project Number F6879-201000

PREPARED FOR

Fisheries and Oceans Canada

DATE

March 30, 2020

Revision 3

Emergency Generator System for
Search and Rescue Station Located
In Port Au Choix, NL

Page 1
2020-03-30

<u>Section</u>	<u>Title</u>	<u>Pages</u>
01 10 10	SUMMARY OF WORK	11
01 29 83	PAYMENT PROCEDUREES FOR TESTING LABORATORY SERVICES	2
01 33 00	SUBMITTAL PROCEDURES	5
01 35 24	SPECIAL PROCEDURES ON FIRE SAFETY REQUIREMENTS	6
01 35 25	SPECIAL PROCEDURES ON LOCKOUT REQUIREMENTS	7
01 35 29.06	HEALTH AND SAFETY REQUIREMENTS	12
01 35 43	ENVIRONMENTAL PROCEDURES	2
01 45 00	TESTING AND QUALITY CONTROL	3
01 51 00	TEMPORARY UTILITIES	1
01 56 00	TEMPORARY BARRIERS AND ENCLOSURES	1
01 61 00	COMMON PRODUCT REQUIREMENTS	5
01 74 11	CLEANING	1
01 74 21	CONSTRUCTION/DEMOLITION WASTE MANAGEMENT AND DISPOSAL	6
01 78 00	CLOSEOUT SUBMITTALS	1
01 91 1	GENERAL COMMISSIONING (Cx) REQUIREMENTS	1
02 41 13	SELECTIVE SITE DEMOLITION	4
26 05 00	COMMON WORK RESULTS FOR ELECTRICAL	11
26 05 20	WIRE AND BOX CONNECTORS (0 - 1000V)	2
26 05 21	WIRES AND CABLES (0 - 1000V)	4
26 05 22	CONNECTORS AND TERMINATIONS	1
26 05 28	GROUNDING - SECONDARY	5
26 05 31	SPLITTERS, JUNCTION, PULL BOXES AND CABINETS	3
26 05 32	OUTLET BOXES, CONDUIT BOXES AND FITTINGS	3
26 05 34	CONDUITS, CONDUIT FASTENINGS AND CONDUIT FITTINGS	6
26 05 43.01	INSTALLATION OF CABLES IN TRENCHES AND IN DUCTS	5
26 24 01	SERVICE EQUIPMENT	2
26 24 16.01	PANELBOARDS BREAKER TYPE	3
26 27 26	WIRING DEVICES	2
26 28 13.01	FUSES - LOW VOLTAGE	3
26 28 16.02	MOULDED CASE CURCUIT BREAKERS	2
26 28 23	DISCONNECT SWITCHES - FUSED AND NON-FUSED	2
26 80 00	COMMISSIONING OF ELECTRICAL SYSTEMS	4
26 90 00	WIRING OF EQUIPMENT SUPPLIED BY OTHERS	2
31 23 33.01	EXCAVATING TRENCHING AND BACKFILLING	8
31 53 13	TIMBER CRIBWORK	7

Emergency Generator System for
Search and Rescue Station Located
In Port Au Choix, NL

Page 2
2020-03-30

Appendix A: Shop Drawings of Owner Supplied Equipment
Appendix B: Covid-19 Standardized Protocols

List of Drawings

Emergency Generator Systems for
Search and Rescue Station Located
In Port Au Choix, NL

Page 1
2020-03-30

<u>DRAWING NO</u>	<u>TITLE</u>
E1	Electrical Site Plan & Details
E2	Electrical Single Line Diagram and Details Administration Bldg.
E3	Electrical Single Line Diagram and Details Support Garage
E4	Electrical Plans and Schedules
S1	Generator System Concrete Pad & Access Platform Plans (Admin Building)
S2	Generator System Concrete Pad & Access Platform Sections (Admin Building)
S3	Generator System Concrete Pad & Access Platform Details (Admin Building)
S4	Generator System Concrete Pad & Access Platform Plans (Garage)
S5	Generator System Concrete Pad & Access Platform Sections (Garage)
S6	Generator System Concrete Pad & Access Platform Details (Garage)
C1	Support Crib (Garage Generator System)
C2	Support Crib (Garage Generator System)

Emergency Generator Systems for
Search and Rescue Station Located
In Port Au Choix, NL

Page 1
2020-03-30

1.1 SCOPE

- .1 The work consists of the furnishing of all plant, labour, equipment and material for emergency generator installation at the Search and Rescue facility in Port Au Choix, NL, in strict accordance with specifications and accompanying drawings and subject to all terms and conditions of the Contract. The generators and associated fuel tanks and transfer switches will be supplied by the Owner and is to be picked-up at DFO's warehouse in Donovan's Industrial Park, Mount Pearl, by the successful Contractor and delivered to the site. The successful contractor assumes all responsibility for the loading, delivery and installation of Owner supplied equipment. Any damages to Owner supplied equipment will be replaced at the Contractor's cost. The approved shop drawings for Owner supplied equipment is attached as Appendix A.
- .2 Note that the Contractor must incorporate COVID-19 standardized protocols in their site specific Health and Safety Plan. The protocols are to include:
- .1 Prevention (signage, practices to reduce risk of transmission, encouragement of social distancing, use of PPE, use of individual modes of transportation, monitoring status of workers, construction jobsite and trailer cleaning protocols, etc.).
 - .2 Detection (screening at entry of construction site, unauthorized entry points, etc.).
 - .3 Response measures (shut down procedures, individual case handling, etc.)

See Appendix B for reference.

Emergency Generator Systems for
Search and Rescue Station Located
In Port Au Choix, NL

Page 2
2020-03-30

- .3 Contractor to submit detailed work plan prior to initiating any work activities. Detailed plan to include a Sequence of Work (S.W.) outlining the procedure proposed for the reconfiguration of the existing electrical service. Where applicable, the S.W. to cover the installation of the new standby generator set, automatic transfer switch and panels along with the installation and terminations of the standby service feeder, new utility service feeder, supply feeder for new panel "DPB", transfer of branch circuits from existing panel "DPA" to new panel "DPB", and a schedule of the downtime required. In all instances, shut down of the existing systems is to be minimal and to the approval of the Departmental Representative.

1.2 DESCRIPTION OF
WORK

- .1 In general, work under this contract consists of The work consists of:
- installing a new owner supplied emergency generators and associated 72 hour capacity fuel tanks (1 at the garage and 1 at the administration building). The one for the garage will require concrete filled support cribbing, as shown on the drawings.
 - Construction of a new emergency power electrical service trench. Service trench to be completed to match surrounding terrain including provisions for new asphalt where applicable.
 - Construction of a new fenced compound for the emergency generator systems, including concrete pads, chain link fencing and access steps/grating.
 - Modifications to the existing electrical room to accommodate the new work and new automatic transfer switches. This

Emergency Generator Systems for
Search and Rescue Station Located
In Port Au Choix, NL

Page 3
2020-03-30

includes new interior walls, new fire rated door with heavy duty stainless steel hardware (style and keying to match existing in building - confirm on site), new concrete paint, new wall paint, etc.

Do not proceed with any portion of the work until the Departmental Representative has approved the Contractor's written work plan. Note that the Contractor will be responsible for engaging a Cummins manufacturer's representative to assist with commissioning and training of both systems, at the installation site (all costs associated with engaging the Cummins representative will be the responsibility of the successful contractor).

Note that all excavated soil during trenching and cribseat excavation activities is to be disposed of at the Provincially approved lined waste disposal facility in Norris Arm, NL. Note also that the Contractor is to provide enough fuel for the Genset for commissioning purposes only. Filling the tank once the commissioning process is finished is the Owner's responsibility.

1.3 SITE OF WORK

- .1 Work will be carried out at Port Au Choix, NL.

1.4 DATUM

- .1 If requested by the Contractor, the Departmental Representative will establish a benchmark prior to the start of work activities.

1.5 FAMILIARIZATION WITH SITE

- .1 Before submitting a bid, it is recommended that bidders visit the site and its surroundings to review and verify the form, nature and extent of the work, materials needed for the completion of the work, the means of access to the site, any accommodations they may require, and in

Emergency Generator Systems for
Search and Rescue Station Located
In Port Au Choix, NL

Page 4
2020-03-30

general shall obtain all necessary information as to risks, contingencies and other circumstances which may influence or affect their bid or costs to do the work. No allowance shall be made subsequently in this connection on account of error or negligence to properly observe and determine the conditions that will apply.

- .2 Contractors, bidders or those they invite to site are to review specification Section 01 35 29.06 - Health and Safety Requirements before visiting site. Take all appropriate safety measures for any visit to site, either before or after acceptance of bid.
- .3 Obtain prior permission from the Departmental Representative before carrying out such site inspection.

1.6 CODES AND STANDARDS

- .1 Perform work in accordance with the latest edition of the National Building Code of Canada, and any other code of provincial or local application including all amendments up to project bid closing date provided that in any case of conflict or discrepancy, the more stringent requirements shall apply.
- .2 Materials and workmanship must meet or exceed requirements of specified standards, codes and referenced documents.

1.7 TERM ENGINEER

- .1 Unless specifically stated otherwise, the term Engineer where used in the Specifications and on the Drawings shall mean the Departmental Representative.

1.8 SETTING OUT WORK

- .1 Set grades and layout work in detail from control points and grades established by Departmental Representative.

Emergency Generator Systems for
Search and Rescue Station Located
In Port Au Choix, NL

Page 5
2020-03-30

- .2 Assume full responsibility for and execute complete layout of work to locations, lines and elevations indicated or as directed by Departmental Representative.
- .3 Provide devices needed to layout and construct work.
- .4 Supply such devices required to facilitate Departmental Representative's inspection of work.

1.9 COST BREAKDOWN

- .1 Before submitting first progress claim submit breakdown of Contract price in detail as directed by Departmental Representative and aggregating contract price.
- .2 Provide cost breakdown in same format as the numerical and subject title system used in this specification project manual and thereafter sub-divided into major work components as directed by Departmental Representative.
- .3 Upon approval by Departmental Representative, cost breakdown will be used as basis for progress payment.
- .4 This will be a lump sum project. Individual work items will not be measured separately for payment.

1.10 WORK SCHEDULE

- .1 Submit within 7 work days of notification of acceptance of bid, a construction schedule showing commencement and completion of all work within the time stated on the Bid and Acceptance Form and the date stated in the bid acceptance letter.
- .2 Provide sufficient details in schedule to clearly illustrate entire implementation

Emergency Generator Systems for
Search and Rescue Station Located
In Port Au Choix, NL

Page 6
2020-03-30

plan, depicting efficient coordination of tasks and resources, to achieve completion of work on time and permit effective monitoring of work progress in relation to established milestones.

- .3 As a minimum, work schedule to be prepared and submitted in the form of Bar (GANTT) Charts, indicating work activities, tasks and other project elements, their anticipated durations and planned dates for achieving key activities and major project milestones provided in sufficient details and supported by narratives to demonstrate a reasonable plan for completion of project within designated time. Generally Bar Charts derived from commercially available computerized project management system are preferred but not mandatory.
- .4 Submit schedule updates on a minimum bi-weekly basis and more often, when requested by Departmental Representative, due to frequent changing project conditions. Provide a narrative explanation of necessary changes and schedule revisions at each update.
- .5 The schedule, including all updates, shall be to Departmental Representative's approval. Take necessary measures to complete work within approved time. Do not change schedule without Departmental Representative's approval.
- .6 All work on the project will be completed within the time indicated on the Bid and Acceptance Form.

1.11 ABBREVIATIONS

- .1 Following abbreviations of standard specifications have been used in this

Emergency Generator Systems for
Search and Rescue Station Located
In Port Au Choix, NL

Page 7
2020-03-30

specification and on the drawings:

CGSB - Canadian Government
Specifications Board
CSA - Canadian Standards Association
NLGA - National Lumber Grades
Authority
ASTM - American Society for Testing
and Materials

.2 Where these abbreviations and standards are used in this project, latest edition in effect on date of bid call will be considered applicable.

1.12 SITE
OPERATIONS

.1 Arrange for sufficient space adjacent to project site for conduct of operations, storage of materials and so on. Exercise care so as not to obstruct or damage public or private property in area. All arrangements for space and access will be made by Contractor.

1.13 PROJECT
MEETINGS

.1 Departmental Representative will arrange project meetings and assume responsibility for setting times and recording minutes.

.2 Project meetings will take place on site of work unless so directed by the Departmental Representative.

.3 Departmental Representative will assume responsibility for recording minutes of meetings and forwarding copies to all parties present at the meetings.

.4 Have a responsible member of firm present at all project meetings.

1.14 PROTECTION

.1 Store all materials and equipment to be incorporated into work to prevent damage

Emergency Generator Systems for
Search and Rescue Station Located
In Port Au Choix, NL

Page 8
2020-03-30

by any means. Note that there will be no temporary storage space available in the existing building for the Contractor.

- .2 Repair or replace all materials damaged in transit or storage to the satisfaction of Departmental Representative and at no cost to Canada.

1.15 EXISTING SERVICES

- .1 Where work involves breaking into or connecting to existing services, carry out work at times directed by governing authorities, with minimum of disturbance to site operations, and tenant operations.
- .2 Before commencing work, establish location and extent of service lines in area of work and notify Departmental Representative of findings.
- .3 Submit schedule to and obtain approval from Departmental Representative for any shut-down or closure of services. Provide temporary services when directed by Departmental Representative to maintain critical facility systems.

1.16 DOCUMENTS REQUIRED

- .1 Maintain at job site, one copy each of the following:
 - .1 Contract Drawings
 - .2 Specifications
 - .3 Addenda
 - .4 Contract and any resulting amendments signed by contracting authority.
 - .5 Test Reports
 - .6 Copy of Approved Work Schedule
 - .7 Site specific Health and Safety Plan and other safety related documents.

1.17 PERMITS

- .1 Obtain and pay for all permits, certificates and licenses as required by Municipal, Provincial, Federal and other

Emergency Generator Systems for
Search and Rescue Station Located
In Port Au Choix, NL

Page 9
2020-03-30

Authorities.

- .2 Provide appropriate notifications of project to municipal and provincial inspection authorities.
 - .3 Obtain compliance certificates as prescribed by legislative and regulatory provisions of municipal, provincial and federal authorities as applicable to the performance of work.
 - .4 Submit to Departmental Representative, copy of application submissions and approval documents received for above referenced authorities.
 - .5 Comply with all requirements, recommendations and advice by all regulatory authorities unless otherwise agreed in writing by Departmental Representative. Make requests for such deviations to these requirements sufficiently in advance of related work.
- 1.18 CUTTING,
FITTING AND
PATCHING
- .1 Execute cutting, including excavation, fitting and patching required to make work fit properly.
- 1.19 ACCEPTANCE
- .1 Prior to the issuance of the Certificate of Substantial Performance, in company with Departmental Representative, make a check of all work. Correct all discrepancies before final inspection and acceptance.
- 1.20 WORKS
COORDINATION
- .1 Responsible for coordinating the work of the various trades, where the work of such trades interfaces with each other.
 - .2 Convene meetings between trades whose work

Emergency Generator Systems for
Search and Rescue Station Located
In Port Au Choix, NL

Page 10
2020-03-30

interfaces and ensure that they are fully aware of the areas and the extent of where interfacing is required. Provide each trade with the plans and specifications of the interfacing trade, as required, to assist them in planning and carrying out their respective work.

- .3 Canada will not be responsible for or held accountable for any extra costs incurred as a result of the failure to carry out coordination work. Disputes between the various trades as a result of their not being informed of the areas and extent of interface work shall be the sole responsibility of the General Contractor and shall be resolved at no extra cost to Canada.

1.21 CONTRACTOR'S
USE OF SITE

- .1 Responsible for arranging the storage of materials on or off site, and any materials stored at the site which interfere with any of the day to day activities at or near the site will be moved promptly at the Contractor's expense, upon request by Departmental Representative.
- .2 Exercise care so as not to obstruct or damage public or private property in the area. At completion of work, restore area to its original condition. Damage to ground and property will be repaired by Contractor. Remove all construction materials, residue, excess, etc., and leave site in a condition acceptable to Departmental Representative.

1.22 WORK
COMMENCEMENT

- .1 Mobilization to project site is to commence immediately after acceptance of bid and submission of Site Specific Safety

Emergency Generator Systems for
Search and Rescue Station Located
In Port Au Choix, NL

Page 11
2020-03-30

Plan and insurance and bonding documentation, unless otherwise agreed by Departmental Representative. Project work on site is to commence as soon as possible, with a continuous reasonable work force, unless otherwise agreed by Departmental Representative.

- .2 Delivery challenges, coordination with site users, and the location of the work site may require the use of longer working days and additional work force to complete the project within the specified completion time. Make every effort to ensure that sufficient material and equipment is delivered to site at the earliest possible date after acceptance of bid and replenished as required.

PART 1 - GENERAL

1.1 SECTION
INCLUDES

- .1 Inspecting and testing by inspecting firms or testing laboratories designated by Departmental Representative.

1.2 RELATED
REQUIREMENTS
SPECIFIED ELSEWHERE

- .1 Particular requirements for inspection and testing to be carried out by testing laboratory designated by Departmental Representative are specified under various sections.

1.3 APPOINTMENT
AND PAYMENT

- .1 Departmental Representative will appoint and pay for services of testing laboratory except for the following:
 - .1 Inspection and testing required by laws, ordinances, rules, regulations or orders of public authorities.
 - .2 Inspection and testing performed exclusively for Contractor's convenience.
 - .3 Tests specified to be carried out by Contractor under the supervision of Departmental Representative.
 - .4 Tests requested by Departmental Representative to confirm material specifications when the applicable manufacturer's documentation or test results are unavailable.
 - .5 Additional tests specified in the following paragraph.
- .2 Where tests or inspections by designated testing laboratory reveal Work not in accordance with contract requirements, pay costs for additional tests or inspections as required by Departmental Representative to verify acceptability of corrected work.

1.4 CONTRACTOR'S
RESPONSIBILITIES

- .1 Provide labour, equipment and facilities to:
 - .1 Provide access to Work to be inspected and tested.
 - .2 Facilitate inspections and tests.
 - .3 Make good Work disturbed by inspection and test.
 - .4 Provide storage on site for laboratory's exclusive use to store equipment, where required.
- .2 Notify Departmental Representative sufficiently in advance of operations to allow for assignment of laboratory personnel and scheduling of test.
- .3 Where materials are specified to be tested, deliver representative samples in required quantity to testing laboratory.
- .4 Pay costs for uncovering and making good Work that is covered before required inspection or testing is completed and approved by Departmental Representative.

PART 2 - PRODUCTS

- 2.1 NOT USED .1 Not Used.

PART 3 - EXECUTION

- 3.1 NOT USED .1 Not Used.

Emergency Generator Systems for
Search and Rescue Station Located
In Port Au Choix, NL

Page 1
2020-03-30

PART 1 - GENERAL

1.1 SECTION
INCLUDES

- .1 Product data.
- .2 Samples.
- .3 Certificates.

1.2 SUBMITTAL
GENERAL REQUIREMENTS

- .1 Submit to Departmental Representative for review submittals listed, including samples, certificates and other data, as specified in other sections of the Specifications. Note that any and all changes to the contract will have to be approved in writing by the Contracting Authority. Departmental Representative will provide a list of required samples/product data sheets to be provided, after contract award.
- .2 Submit with reasonable promptness and in orderly sequence so as to allow for Departmental Representative's review and not cause delay in Work. Failure to submit in ample time will not be considered sufficient reason for an extension of Contract time and no claim for extension by reason of such default will be allowed.
- .3 Do not proceed with work until relevant submissions are reviewed by Departmental Representative.
- .4 Present product data, samples and mock-ups in SI Metric units.
- .5 Where items or information is not produced in SI Metric units, provide soft converted values.
- .6 Review submittals prior to submission to

Emergency Generator Systems for
Search and Rescue Station Located
In Port Au Choix, NL

Page 2
2020-03-30

Departmental Representative. Ensure during review that necessary requirements have been determined and verified, required field measurements or data have been taken, and that each submittal has been checked and co-ordinated with requirements of Work and Contract Documents.

- .1 Submittals not stamped, signed, dated and identified as to specific project will be returned unexamined by Departmental Representative and considered rejected.
- .7 Notify Departmental Representative, in writing at time of submission, identifying deviations from requirements of Contract Documents stating reasons for deviations.
- .8 Verify field measurements and affected adjacent work and coordinate.
- .9 Contractor's responsibility for errors and omissions in submission is not relieved by Departmental Representative's review of submittals.
- .10 Contractor's responsibility for deviations in submission from requirements of Contract Documents is not relieved by Departmental Representative's review.
- .11 Submittal format: paper originals, or alternatively clear and fully legible photocopies of originals. Facsimiles are not acceptable, except in special circumstances pre-approved by Departmental Representative. Poorly printed non-legible photocopies or facsimiles will not be accepted and be returned for resubmission.
- .12 Make changes or revision to submissions which Departmental Representative may require,

Emergency Generator Systems for
Search and Rescue Station Located
In Port Au Choix, NL

Page 3
2020-03-30

consistent with Contract Documents and resubmit as directed by Departmental Representative. When resubmitting, notify Departmental Representative in writing of any revisions other than those requested.

- .13 Keep one reviewed copy of each submittal document on site for duration of Work.

1.3 PRODUCT DATA

- .1 Product data includes drawings, diagrams, illustrations, schedules, performance charts, brochures and other data which are to be provided by Contractor to illustrate details of a portion of Work.
- .2 Submit sufficient copies of product data which are required by the General Contractor and sub-contractors plus 2 copies which will be retained by Departmental Representative. Ensure sufficient numbers are submitted to enable one complete set to be included in each of the maintenance manuals specified, if applicable.
- .3 Allow 10 calendar days for Departmental Representative's review of each submission.
- .4 Adjustments or corrections made on product data by Departmental Representative are not intended to change Contract Price. If adjustments affect value of Work, advise Departmental Representative in writing prior to proceeding with Work.
- .5 If upon review by Departmental Representative, no errors or omissions are discovered or if only minor corrections and comments are made, fabrication and installation may proceed upon receipt of shop drawings. If product data are rejected and noted to be Resubmitted, do not proceed with

Emergency Generator Systems for
Search and Rescue Station Located
In Port Au Choix, NL

Page 4
2020-03-30

that portion of work until resubmission and review of corrected product data, through same submission procedures indicated above.

- .6 Accompany each submission with transmittal letter, containing:
 - .1 Date.
 - .2 Project title and project number.
 - .3 Contractor's name and address.
 - .4 Identification and quantity of each product data and sample.
 - .5 Other pertinent data.
- .7 Submissions shall include:
 - .1 Date and revision dates.
 - .2 Project title and project number.
 - .3 Name and address of:
 - .1 Subcontractor.
 - .2 Supplier.
 - .3 Manufacturer.
 - .4 Contractor's stamp, signed by Contractor's authorized representative certifying approval of submissions, verification of field measurements and compliance with Contract Documents.
 - .5 Cross references to particular details of contract drawings and specifications section number for which product data submission addresses.
 - .6 Details of appropriate portions of Work.
- .8 After Departmental Representative's review, distribute copies.
- .9 The review of samples and product data by the Departmental Representative or their delegated representative is for sole purpose of ascertaining conformance with general concept. This review shall not mean that the Departmental Representative approves the detail design inherent in the product data, responsibility for which shall remain with

Emergency Generator Systems for
Search and Rescue Station Located
In Port Au Choix, NL

Page 5
2020-03-30

Contractor submitting same, and such review shall not relieve Contractor of responsibility for errors or omissions in product data or of responsibility for meeting all requirements of the construction and Contract Documents. Without restricting generality of foregoing, Contractor is responsible for dimensions to be confirmed and correlated at job site, for information that pertains solely to fabrication processes or to techniques of construction and installation and for co-ordination of Work of all sub-trades.

1.4 SCHEDULES,
PERMITS AND
CERTIFICATES

- .1 Upon acceptance of bid, submit to Departmental Representative copy of Work Schedule and various other schedules, permits, certification documents and project management plans as specified in other sections of the Specifications.
- .2 Submit copy of permits, notices, compliance Certificates received by Regulatory Agencies having jurisdiction and as applicable to the Work.
- .3 Submission of above documents to be in accordance with Submittal General Requirements procedures specified in this section.

1.1 SECTION
INCLUDES

- .1 Fire Safety Requirements.
- .2 Hot Work Permit.

1.2 RELATED WORK

- .1 Section 01 35 29.06 - Health and Safety Requirements.

1.3 REFERENCES

- .1 Fire Protection Standards issued by Fire Protection Services of Human Resources Development Canada as follows:
 - .1 National Fire Code - Standard for Construction Operations - latest edition (http://www.hrsdc.gc.ca/eng/labour/fire_protection/policies_standards/commissioner/301/page00.shtml).
 - .2 National Fire Code - Standard for Welding and Cutting - latest edition (http://www.hrsdc.gc.ca/eng/labour/fire_protection/policies_standards/commissioner/302/page00.shtml).
 - .3 FCC standards, may also be viewed at the Regional Labour Canada Office located at Baine Johnson Centre, 10 Fort William Place, St. John's, NL, A1C 1K4; Telephone 1-800-641-4049; fax 1-709-772-5985.

1.4 DEFINITIONS

- .1 Hot Work defined as:
 - .1 Welding work.
 - .2 Cutting of materials by use of torch or other open flame devices.
 - .3 Grinding with equipment which produces sparks.

1.5 SUBMITTALS

- .1 Submit copy of Hot Work Procedures and sample of Hot Work permit to Departmental Representative for review, within five (5) calendar days after notification of acceptance of bid.

1.6 FIRE SAFETY
REQUIREMENTS

- .2 Submit in accordance with the Submittal General Requirements specified in Section 01 33 00.
- .1 Implement and follow fire safety measures during Work. Comply with following:
 - .1 National Fire Code, latest edition.
 - .2 Fire Protection Standards FCC 301 and FCC 302 - latest edition.
 - .3 Federal and Provincial Occupational Health and Safety Acts and Regulations as specified in Section 01 35 29.06.
- .2 In event of conflict between any provisions of above authorities the most stringent provision will apply. Should a dispute arise in determining the most stringent requirement, Departmental Representative will advise on the course of action to be followed.

1.7 HOT WORK
AUTHORIZATION

- .1 Obtain Departmental Representative's written "Authorization to Proceed" before conducting any form of Hot work on site.
- .2 To obtain authorization submit to Departmental Representative:
 - .1 Contractor's typewritten Hot Work Procedures to be followed on site as specified below.
 - .2 Description of the type and frequency of Hot Work required.
 - .3 Sample Hot Work Permit to be used.
- .3 Upon review and confirmation that effective fire safety measures will be implemented during performance of hot work, Departmental Representative will provide authorization to proceed as follows:
 - .1 Issue one written "Authorization to Proceed" covering the entire project for

duration of work or;

.2 Separate work, or segregate certain parts of work, into individual entities. Each entity requiring a separately written "Authorization to Proceed" from Departmental Representative. Follow Departmental Representative's directives in this regard.

.4 Requirement for individual authorization based on:

.1 Nature or phasing of work;

.2 Risk to Facility operations;

.3 Quantity of various trades needing to perform hot work on project or;

.4 Other situation deemed necessary by Departmental Representative to ensure fire safety on premises.

.5 Do not perform any Hot Work until receipt of Departmental Representative's written "Authorization to Proceed" for that portion of work.

1.8 HOT WORK PROCEDURES

.1 Develop and implement safety procedures and work practices to be followed during the performance of Hot Work.

.2 Procedures to include:

.1 Requirement to perform hazard assessment of site and immediate hot work area for each hot work event in accordance with Hazard Assessment and Safety Plan requirements of Section 01 35 29.06.

.2 Use of a Hot Work Permit system for each hot work event.

.3 The step by step process of how to prepare and issue permit.

.4 Permit shall be issued by Contractor's site Superintendent, or other authorized person designated by Contractor, granting permission to worker or subcontractor to

proceed with hot work.

.5 Provision of a designated person to carryout a Fire Safety Watch for a minimum of 60 minutes immediately upon completion of the hot work.

.6 Compliance with fire safety codes and standards specified herein and occupational health and safety regulations specified in Section 01 35 29.

.3 Generic procedures, if used, must be edited and supplemented with pertinent information tailored to reflect specific project conditions. Clearly label as being the Hot Work Procedures applicable to this contract.

.4 Hot Work Procedures shall clearly establish worker instructions and allocate responsibilities of:

.1 Worker(s),

.2 Authorized person issuing the Hot Work Permit,

.3 Fire Safety Watcher,

.4 Subcontractors and Contractor.

.5 Brief all workers and subcontractors on Hot Work Procedures and Permit system established for project. Stringently enforce compliance.

.1 Failure to comply with the established procedures may result in the issuance of a Non-Compliance Notification at Departmental Representative's discretion with possible disciplinary measures imposed as specified in Section 01 35 29.06

1.9 HOT WORK
PERMIT

.1 Hot Work Permit to include, as a minimum, the following data:

.1 Project name and project number.

.2 Building name, address and specific room or area where hot work will be performed.

.3 Date when permit issued.

- .4 Description of hot work type to be performed.
 - .5 Special precautions required, including type of fire extinguisher needed.
 - .6 Name and signature of person authorized to issue the permit.
 - .7 Name of worker (clearly printed) to which the permit is being issued.
 - .8 Time Duration that permit is valid (not to exceed 8 hours). Indicate start time and date, and completion time and date.
 - .9 Worker signature with date and time upon hot work termination.
 - .10 Specified time period requiring safety watch.
 - .11 Name and signature of designated Fire Safety Watcher, complete with time and date when safety watch terminated, certifying that surrounding area was under continual surveillance and inspection during the full watch time period specified in Permit and commenced immediately upon completion of Hot Work.
-
- .2 Permit to be typewritten form. Industry Standard forms shall only be used if all data specified above is included on form.
 - .3 Each Hot Work Permit to be completed in full and signed as follows:
 - .1 Authorized person issuing Permit before hot work commences.
 - .2 Worker upon completion of Hot Work.
 - .3 Fire Safety Watcher upon termination of safety watch.
 - .4 Returned to Contractor's Site Superintendent for safe keeping.
-
- | | |
|----------------------------------|--|
| 1.10 DOCUMENTS
<u>ON SITE</u> | <ul style="list-style-type: none">.1 Keep Hot Work Permits and Hazard assessment documentation on site for duration of Work. |
|----------------------------------|--|

- .2 Upon request, make available to Departmental Representative or to authorized safety representative for inspection.

-
- | | | |
|-----------------------------|----|---|
| <u>1.1 SECTION INCLUDES</u> | .1 | Procedures to isolate and lockout electrical facility or other equipment from energy source. |
|
 | | |
| <u>1.2 RELATED WORK</u> | .1 | Section 01 35 24 - Fire Safety Requirements. |
| | .2 | Section 01 35 29.06 - Health and Safety Requirements. |
|
 | | |
| <u>1.3 REFERENCES</u> | .1 | C22.1-06 - Canadian Electrical Code, Part 1, Safety Standard for Electrical Installations. |
| | .2 | CAN/CSA C22.3 No. 1-10 - Overhead Systems. |
| | .3 | COSH, Canada Occupational Health and Safety Regulations made under Part II of the Canada Labour Code. |
|
 | | |
| <u>1.4 DEFINITIONS</u> | .1 | Electrical Facility: means any system, equipment, device, apparatus, wiring, conductor, assembly or part thereof that is used for the generation, transformation, transmission, distribution, storage, control, measurement or utilization of electrical energy, and that has an amperage and voltage that is dangerous to persons. |
| | .2 | Guarantee of Isolation: means a guarantee by a competent person in control or in charge that a particular facility or equipment is isolated. |
| | .3 | De-energize: in the electrical sense, that a piece of equipment is isolated and grounded, e.g. if the equipment is not grounded, it cannot be considered de-energized (DEAD). |
| | .4 | Guarded: means that an equipment or facility |

Emergency Generator Systems for
Search and Rescue Station Located
In Port Au Choix, NL

is covered, shielded, fenced, enclosed, inaccessible by location, or otherwise protected in a manner that, to the extent that is reasonably practicable, will prevent or reduce danger to any person who might touch or go near such item.

- .5 Isolate: means that an electrical facility, mechanical equipment or machinery is separated or disconnected from every source of electrical, mechanical, hydraulic, pneumatic or other kind of energy that is capable of making it dangerous.
- .6 Live/alive: means that an electrical facility produces, contains, stores or is electrically connected to a source of alternating or direct current of an amperage and voltage that is dangerous or contains any hydraulic, pneumatic or other kind of energy that is capable of making the facility dangerous to persons.

1.5 COMPLIANCE
REQUIREMENTS

- .1 Perform lockouts in compliance with:
 - .1 Canadian Electrical Code.
 - .2 Federal and Provincial Occupational Health and Safety Acts and Regulations as specified in Section 01 35 29.06.
 - .3 Regulations and code of practice as applicable to mechanical equipment or other machinery being de-energized.
 - .4 Procedures specified herein.
- .2 In event of conflict between any provisions of above authorities the most stringent provision will apply. Should a dispute arise in determining the most stringent requirement, Departmental Representative will advise on the course of action to be followed.

1.6 SUBMITTALS

- .1 Submit copy of proposed Lockout Procedures and sample form of lockout permit or lockout tags for review.
- .2 Submit documentation within 7 calendar days of acceptance of bid. Do not proceed with work until submittal has been reviewed by Departmental Representative.
- .3 Submit above documents in accordance with the submittal requirements specified in Section 01 33 00.
- .4 Resubmit Lockout Procedures with noted revisions as may result from Departmental Representative's review.

1.7 ISOLATION OF
EXISTING SERVICES

- .1 Obtain Departmental Representative's written authorization prior to conducting work on an existing active, energized service or facility required as part of the work and before proceeding with lockout of such services or facility.
- .2 To obtain authorization, submit to Departmental Representative the following documentation:
 - .1 Written Request for Isolation of the service or facility and;
 - .2 Copy of Contractor's Lockout Procedures.
- .3 Make a Request for Isolation for each event, unless directed otherwise by Departmental Representative, and as follows:
 - .1 Fill-out standard forms in current use at the Facility when so directed by Departmental Representative or;
 - .2 Where no form exist at Facility, make request in writing identifying:

- .1 Identification of system or equipment to be isolated, including it's location;
- .2 Time duration, indicating Start time and date, and Completion time and date when isolation will be in effect;
- .3 Voltage of service feed to system or equipment being isolated;
- .4 Name of person making the request.
- .3 Document to be in typewritten format.
- .4 Do not proceed until receipt of written notification from Departmental Representative granting the Isolation Request and authorization to proceed with the isolation of designated equipment or facility. Departmental Representative may designate other individual at the Facility as the person authorized to grant the Isolation Request.
- .5 Conduct safe, orderly shut down of equipment or facilities, de-energize and isolate power and other sources of energy and lockout items in accordance with requirement of clause 1.8 below.
- .6 Plan and schedule shut down of existing services in consultation with the Departmental Representative and the Facility Manager. Minimize impact and downtime of facility operations.
- .7 Determine in advance, as much as possible, in cooperation with the Departmental Representative, the type and frequency of situations which will require a Request for Isolation. Follow Departmental Representative's directives in this regard.
- .8 Conduct hazard assessment as part of the

planning process of isolating existing equipment and facilities. Hazard Assessments to conform with requirements of Health and Safety Section 01 35 29.06.

1.8 LOCKOUTS

- .1 Isolate and lockout electrical facilities, mechanical equipment and machinery from all potential energy sources prior to starting work on such items.
- .2 Develop and implement lockout procedures to be followed on site as an integral part of the Work.
- .3 Use energy isolation lockout devices specifically designed and appropriate for type of facility or equipment being locked out.
- .4 Use industry standard lockout tags.
- .5 Provide appropriate safety grounding and guards as required.
- .6 Prepare Lockout Procedures in writing. Describe safe work practices, work functions and sequence of activities to be followed on site to safely isolate all potential energy sources and lockout/tagout facilities and equipment.
- .7 Include within procedures a system of worker request and issuance of individual lockout permit by a person, employed by Contractor, designated to be "in-charge" and being responsible for:
 - .1 Controlling issuance of permits or tags to workers.
 - .2 Determining permit duration.
 - .3 Maintaining record of permits and tags issued.

Emergency Generator Systems for
Search and Rescue Station Located
In Port Au Choix, NL

- .4 Submitting a Request for Isolation to Departmental Representative when required in accordance with Clause 1.7 above.
- .5 Designating a Safety Watcher, when one is required based on type of work.
- .6 Ensuring equipment or facility has been properly isolated, providing a Guarantee of Isolation to worker(s) prior to proceeding with work.
- .7 Collecting and safekeeping lockout tags, returned by workers, as a record of the event.
- .8 Clearly establish, describe and allocate, within procedures, the responsibilities of:
 - .1 Workers.
 - .2 Designated person controlling issuance of lockout tags/permits.
 - .3 Safety Watcher.
 - .4 Subcontractors and General Contractor.
- .9 Procedures shall meet the requirements of Codes and Regulations specified in clause 1.5 above.
- .10 Generic procedures, if used, must be edited, supplemented with pertinent information and tailored to reflect specific project conditions. Clearly label as being the procedures applicable to this contract.
 - .1 Incorporate site specific rules and procedures established by Facility Manager and in force at site. Obtain such procedures through Departmental Representative.
- .11 Procedures to be in typewritten format.
- .12 Submit copy of Lockout Procedures to Departmental Representative, in accordance with submittal requirements of clause 1.6 herein, prior to commencement of work.

1.9 CONFORMANCE

- .1 Ensure that lockout procedures, as established for project on site, are stringently followed. Enforce use and compliance by all workers.
- .2 Brief all persons working on electrical facilities, mechanical and other equipment fed by an energy source on requirements of this section.
- .3 Failure to perform lockouts in accordance with regulatory requirements or follow procedures specified herein may result in the issuance of a Non-Compliance Notification at Departmental Representative's discretion with possible disciplinary measures imposed as specified in Section 01 35 29.06.

1.10 DOCUMENTS
ON SITE

- .1 Post Lockout Procedures on site in common location for viewing by workers.
- .2 Keep copies of Request for Isolation submitted to Departmental Representative and lockout permits or tags issued to workers during the course of work for full project duration.
- .3 Upon request, make such data available to Departmental Representative or to authorized safety representative for inspection.

Emergency Generator Systems for
Search and Rescue Station Located
In Port Au Choix, NL

1.1 RELATED WORK

- .1 Section 01 35 24 - Special Procedures on Fire Safety Requirements.

1.2 DEFINITIONS

- .1 COSH: Canada Occupational Health and Safety Regulations made under Part II of the Canada Labour Code.
- .2 Competent Person: means a person who is:
 - .1 Qualified by virtue of personal knowledge, training and experience to perform assigned work in a manner that will ensure the health and safety of persons in the workplace, and;
 - .2 Knowledgeable about the provisions of occupational health and safety statutes and regulations that apply to the Work and;
 - .3 Knowledgeable about potential or actual danger to health or safety associated with the Work.
- .3 Medical Aid Injury: any minor injury for which medical treatment was provided and the cost of which is covered by Workers' Compensation Board of the province in which the injury was incurred.
- .4 PPE: personal protective equipment.
- .5 Work Site: where used in this section shall mean areas, located at the premises where Work is undertaken, used by Contractor to perform all of the activities associated with the performance of the Work.

1.3 SUBMITTALS

- .1 Make submittals in accordance with Section 01 33 00.
- .2 Submit to Departmental Representative, copies of the following documents

Emergency Generator Systems for
Search and Rescue Station Located
In Port Au Choix, NL

including updates.

- .1 Site specific Health and Safety Plan.
 - .2 Building permit, compliance certification and other permits obtained.
 - .3 Reports or directives issued by Federal and Provincial Inspectors and other Authorities having jurisdiction.
 - .4 Accident or incident reports.
 - .5 WHMIS - MSDS data sheets.
 - .6 Name of Contractor's Representative designated to perform health and safety supervision in site.
 - .7 Certificate of clearance from Workplace Health Safety and Compensation Commission (Assessment Services Department) of Newfoundland and Labrador.
-
- .3 Submit within five (5) work days of notification of Bid Acceptance. Provide one (1) copy.
 - .4 Departmental Representative will review Health and Safety Plan and provide comments.
 - .5 The Contractor will revise the Plan as appropriate and resubmit within five (5) work days after receipt of comments.
 - .6 Departmental Representative's review and comments made of the Plan shall not be construed as an endorsement, approval or implied warranty of any kind by Canada and does not reduce Contractor's overall responsibility for Occupational Health and Safety of the Work.
 - .7 Submit revisions and updates made to the Plan during the course of Work.

Emergency Generator Systems for
Search and Rescue Station Located
In Port Au Choix, NL

1.4 COMPLIANCE
REQUIREMENTS

- .1 Comply with the Occupational Health and Safety Act for the Province of Newfoundland and Labrador, and the Occupational Health and Safety Regulations made pursuant to the Act.
- .2 Comply with Canada Labour Code Part II, (entitled Occupational Health and Safety) and the Canada Occupational Health and Safety Regulations (COSH) as well as any other regulations made pursuant to the Act.
 - .1 The Canada Labour Code can be viewed at:
[www.http://laws.justice.gc.ca/en/L-2/](http://laws.justice.gc.ca/en/L-2/)
 - .2 COSH can be viewed at:
[www.http://laws.justice.gc.ca/eng/SOR-86-304/ne.html](http://laws.justice.gc.ca/eng/SOR-86-304/ne.html).
 - .3 A copy may be obtained at: Canadian Government Publishing Public Works & Government Services Canada Ottawa, Ontario, K1A 0S9 Tel: (819) 956-4800 (1-800-635-7943) Publication No. L31-85/2000 E or F).
- .3 Observe construction safety measures of:
 - .1 Part 8 of National Building Code.
 - .2 Municipal by-laws and ordinances.
- .4 In case of conflict or discrepancy between any specified requirements, the more stringent shall apply.
- .6 Maintain Workers Compensation Coverage in good standing for duration of Contract. Provide proof through submission of Certificate of Clearance from Workplace Health, Safety and Compensation Commission (Assessment Services Department) of Newfoundland and Labrador.
- .7 Obtain and maintain worker medical

surveillance documentation where
prescribed by legislation or regulation.

1.5 RESPONSIBILITY

- .1 Be responsible for health and safety of persons on site, safety of property and for protection of persons and environment adjacent to the site to extent that they may be affected by conduct of Work.
- .2 Comply with and enforce compliance by all workers, sub-contractors and other persons granted access to work site with safety requirements of Contract Documents, applicable Federal, Provincial, and local by-laws, regulations, and ordinances, and with site specific Health and Safety Plan.

1.6 SITE CONTROL
AND ACCESS

- .1 Control the Work and entry points to Work Site. Approve and grant access only to workers and authorized persons. Immediately stop and remove non-authorized persons.
 - .1 Departmental Representative will provide names of those persons authorized by Departmental Representative to enter onto Work Site and will ensure that such authorized persons have the required knowledge and training on Health and Safety pertinent to their reason for being at the site, however, Contractor remains responsible for the health and safety of authorized persons while at the Work Site.
- .2 Isolate Work Site from other areas of the premises by use of appropriate means.
 - .1 Erect fences, hoarding, barricades and temporary lighting as required to effectively delineate the Work Site, stop non-authorized entry, and to protect pedestrians and vehicular

traffic around and adjacent to the
Work and create a safe environment.

.2 Post signage at entry points and other
strategic locations indicating
restricted access and conditions for
access.

.3 Provide safety orientation session to
persons granted access to Work Site.
Advise of hazards and safety rules to be
observed while on site.

.4 Ensure persons granted site access wear
appropriate PPE. Supply PPE to inspection
authorities who require access to conduct
tests or perform inspections.

.5 Secure Work Site against entry when
inactive or unoccupied and to protect
persons against harm. Provide security
guard where adequate protection cannot be
achieved by other means.

1.7 PROTECTION

.1 Give precedence to safety and health of
persons and protection of environment over
cost and schedule considerations for Work.

.2 Should unforeseen or peculiar safety
related hazard or condition become evident
during performance of Work, immediately
take measures to rectify situation and
prevent damage or harm. Advise
Departmental Representative verbally and
in writing.

1.8 FILING OF NOTICE

.1 File Notice of Project with pertinent
provincial health and safety authorities
prior to beginning of Work.

1.9 PERMITS

.1 Post permits, licenses and compliance
Certificates at Work Site.

Emergency Generator Systems for
Search and Rescue Station Located
In Port Au Choix, NL

Page 6
2020-03-30

- .2 Where a particular permit or compliance certificate cannot be obtained, notify Departmental Representative in writing and obtain approval to proceed before carrying out applicable portion of work.

1.10 HAZARD
ASSESSMENTS

- .1 Perform site specific health and safety hazard assessment of the Work and its site.
- .2 Carryout initial assessment prior to commencement of Work with further assessments as needed during progress of work, including when new trades and subcontractors arrive on site.
- .3 Record results and address in Health and Safety Plan.
- .4 Keep documentation on site for entire duration of the Work.

1.11 PROJECT/SITE
CONDITIONS

- .1 The following are known or potential project related safety hazards at site:
 - .1 Heavy lifting.
 - .2 Working at heights.
 - .3 Cutting tools and other construction power tools.
 - .4 Sharp objects (construction debris).
 - .5 Electric shock.
- .2 Above items shall not be construed as being complete and inclusive of potential health, and safety hazards encountered during work.
- .3 Include above items into hazard assessment process.

Emergency Generator Systems for
Search and Rescue Station Located
In Port Au Choix, NL

Page 7
2020-03-30

1.12 MEETINGS

- .1 Contractor to hold pre-construction health and safety meeting prior to commencement of Work. Ensure attendance of:
 - .1 Superintendent of Work.
 - .2 Contractor's designated Health & Safety Site Representative.
 - .3 Subcontractor's Health and Safety Site Representative.
 - .4 Health and Safety Site Coordinator.
- .2 Conduct regularly scheduled tool box and safety meetings during the Work in conformance with Occupational Health and Safety regulations.
- .3 Keep documents on site.

1.13 HEALTH AND
SAFETY PLAN

- .1 Prior to commencement of Work, develop written Health and Safety Plan specific to the work. Implement, maintain, and enforce Plan for entire duration of Work and until final demobilization from site.
- .2 Health and Safety Plan shall include the following components:
 - .1 List of health risks and safety hazards identified by hazard assessment.
 - .2 Control measures used to mitigate risks and hazards identified.
 - .3 On-site Contingency and Emergency Response Plan as specified below.
 - .4 On-site Communication Plan as specified below.
 - .5 Name of Contractor's designated Health & Safety Site Representative and information showing proof of his/her competence and reporting relationship in Contractor's company.
 - .6 Names, competence and reporting relationship of other supervisory

personnel used in the Work for
occupational health and safety
purposes.

- .3 On-site Contingency and Emergency Response Plan shall include:
 - .1 Operational procedures, evacuation measures and communication process to be implemented in the event of an emergency.
 - .2 Evacuation Plan: site and floor plan layouts showing escape routes, marshaling areas. Details on alarm notification methods, fire drills, location of fire fighting equipment and other related data.
 - .3 Name, duties and responsibilities of persons designated as Emergency Warden(s) and deputies.
 - .4 Emergency Contacts: name and telephone number of officials from:
 - .1 General Contractor and subcontractors.
 - .2 Pertinent Federal and Provincial Departments and Authorities having jurisdiction.
 - .3 Local emergency resource organizations.
- .4 On-site Communication Plan:
 - .1 Procedures for sharing of work related safety information to workers and subcontractors, including emergency and evacuation measures.
- .5 Address all activities of the Work including those of subcontractors.
- .6 Review Health and Safety Plan regularly during the Work. Update as conditions warrant to address emerging risks and

Emergency Generator Systems for
Search and Rescue Station Located
In Port Au Choix, NL

hazards, such as whenever new trade or subcontractor arrive at Work Site.

- .7 Departmental Representative will respond in writing, where deficiencies or concerns are noted and may request re-submission of the Plan with correction of deficiencies or concerns.
- .8 Post copy of the Plan, and updates, prominently on Work Site.

1.14 SAFETY SUPERVISION

- .1 Employ Health & Safety Site Representative responsible for daily supervision of health and safety of the Work.
- .2 Health & Safety Site Representative may be the Superintendent of the Work or other person designated by Contractor and shall be assigned the responsibility and authority to:
 - .1 Implement, monitor and enforce daily compliance with health and safety requirements of the Work
 - .2 Monitor and enforce Contractor's site-specific Health and Safety Plan.
 - .3 Conduct site safety orientation session to persons granted access to Work Site.
 - .4 Ensure that persons allowed site access are knowledgeable and trained in health and safety pertinent to their activities at the site or are escorted by a competent person while on the Work Site.
 - .5 Stop the Work as deemed necessary for reasons of health and safety.
- .3 Health & Safety Site Representative must:
 - .1 Be qualified and competent person in occupational health and safety.
 - .2 Have site-related working experience specific to activities of the Work.
 - .3 Be on Work Site at all times during

execution of the Work.

- .4 All supervisory personnel assigned to the Work shall also be competent persons.
- .5 Inspections:
 - .1 Conduct regularly scheduled safety inspections of the Work on a minimum daily basis. Record deficiencies and remedial action taken.
 - .2 Conduct Formal Inspections on a minimum monthly basis. Use standardized safety inspection forms. Distribute to subcontractors.
 - .3 Follow-up and ensure corrective measures are taken.
- .6 Keep inspection reports and supervision related documentation on site.

1.15 TRAINING

- .1 Use only skilled workers on Work Site who are effectively trained in occupational health and safety procedures and practices pertinent to their assigned task.
- .2 Maintain employee records and evidence of training received. Make data available to Departmental Representative upon request.
- .3 When unforeseen or peculiar safety-related hazard, or condition occur during performance of Work, follow procedures in place for Employee's Right to Refuse Work in accordance with Acts and Regulations of Province having jurisdiction and advise Departmental Representative verbally and in writing.
- .4 All workers dealing with hazardous materials are required to provide evidence

of training, in accordance with Provincial regulations.

1.16 MINIMUM
SITE SAFETY RULES

- .1 Notwithstanding requirement to abide by federal and provincial health and safety regulations; ensure the following minimum safety rules are obeyed by persons granted access to Work Site:
 - .1 Wear appropriate PPE pertinent to the Work or assigned task; minimum being hard hat, safety footwear, safety glasses and safety vest.
 - .2 Immediately report unsafe condition at site, near-miss accident, injury and damage.
 - .3 Maintain site and storage areas in a tidy condition free of hazards causing injury.
 - .4 Obey warning signs and safety tags.
- .2 Brief persons of disciplinary protocols to be taken for non compliance. Post rules on site.

1.17 CORRECTION OF
NON-COMPLIANCE

- .1 Immediately address health and safety non-compliance issues identified by authority having jurisdiction or by Departmental Representative.
- .2 Provide Departmental Representative with written report of action taken to correct non-compliance of health and safety issues identified.
- .3 Departmental Representative will stop Work if non-compliance of health and safety regulations is not corrected in a timely manner.

1.18 INCIDENT
REPORTING

- .1 Investigate and report the following incidents to Departmental Representative:
 - .1 Incidents requiring notification to

Emergency Generator Systems for
Search and Rescue Station Located
In Port Au Choix, NL

Provincial Department of Occupational
Safety and Health, Workers Compensation
Board or to other regulatory Agency.

- .2 Medical aid injuries.
- .3 Property damage in excess of
\$10,000.00.

- .2 Submit report in writing.

1.19 HAZARDOUS
PRODUCTS

- .1 Comply with requirements of Workplace
Hazardous Materials Information System
WHMIS).
- .2 Keep MSDS data sheets for all products
delivered to site.
 - .1 Post on site and submit copy to
Departmental Representative.

1.20 SITE RECORDS

- .1 Maintain on Work Site copy of safety
related documentation and reports
stipulated to be produced in compliance
with Acts and Regulations of authorities
having jurisdiction and of those documents
specified herein.
- .2 Upon request, make available to
Departmental Representative or authorized
Safety Officer for inspection.

1.21 POSTING OF
DOCUMENTS

- .1 Ensure applicable items, articles, notices
and orders are posted in conspicuous
location on Work Site in accordance with
Acts and Regulations of Province having
jurisdiction.
- .2 Post other documents as specified herein,
including:
 - .1 Site specific Health and Safety Plan.
 - .2 WHMIS data sheets.

Emergency Generator Systems for
Search and Rescue Station Located
In Port Au Choix, NL

Page 1
2020-03-30

1.1 DEFINITIONS

- .1 Hazardous Material: Product, substance, or organism that is used for its original purpose; and that is either dangerous goods or a material that may cause adverse impact to the environment or adversely affect health of persons, animals, or plant life when released into the environment.

1.2 DISPOSAL OF
WASTES AND
HAZARDOUS
MATERIALS

- .1 Do not bury rubbish and waste materials on site.
- .2 Do not dispose of hazardous waste or volatile materials, such as mineral spirits, paints, thinners, oil or fuel into waterways, storm or sanitary sewers or waste landfill sites.
- .3 Store, handle and dispose of hazardous materials and hazardous waste in accordance with applicable federal and provincial laws, regulations, codes and guidelines.
- .4 Dispose of construction waste materials and demolition debris, resulting from work, at approved landfill sites only. Carryout such disposal in strict accordance with provincial and municipal rules and regulations. Separate out and prevent improper disposal of items banned from landfills.
- .5 Establish methods and undertake construction practices which will minimize waste and optimize use of construction materials. Separate at source all construction waste materials, demolition debris and product packaging and delivery containers into various waste categories in order to maximize recycling abilities of various materials and avoid disposal of debris at landfill site(s) in a "mixed state". Where recycling firms, specializing in recycling of specific materials exist, transport such materials to

Emergency Generator Systems for
Search and Rescue Station Located
In Port Au Choix, NL

Page 2
2020-03-30

the recycling facility and avoid disposal at landfill sites.

- .6 Communicate with landfill operator prior to commencement of work, to determine what specific construction, demolition and renovation waste materials have been banned from disposal at the landfill and at transfer stations.

1.3 POLLUTION
CONTROL

- .1 Control emissions from equipment and plant to local authorities emission requirements.
- .2 Cover or wet down dry materials and rubbish to prevent blowing dust and debris.
- .3 Have emergency spill response equipment and rapid clean-up kit, appropriate to work, at site. Locate adjacent to work and where hazardous materials are stored. Provide personal protective equipment as required for clean-up.
- .4 Report, to Federal and Provincial Department of the Environment, spills of petroleum and other hazardous materials as well as accidents having potential of polluting the environment. Also notify Departmental Representative and submit a written spill report to Departmental Representative within 24 hours of occurrence.

Emergency Generator Systems for
Search and Rescue Station Located
In Port Au Choix, NL

Page 1
2020-03-30

1.1 SECTION
INCLUDES

- .1 Inspection and testing, administrative and enforcement requirements.

1.2 INSPECTION

- .1 Facilitate Departmental Representative's access to Work. If part of Work is being fabricated at locations other than construction site, make preparations to allow access to such Work whenever it is in progress.
- .2 Give timely notice requesting inspection of Work designated for special tests, inspections or approvals by Departmental Representative or by inspection authorities having jurisdiction.
- .3 If Contractor covers or permits to be covered Work designated for special tests, inspections or approvals before such is made, uncover Work until particular inspections or tests have been fully and satisfactorily completed and until such time as Departmental Representative gives permission to proceed. Pay costs to uncover and make good such Work.
- .4 In accordance with the General Conditions, Departmental Representative may order any part of Work to be examined if Work is suspected to be not in accordance with Contract Documents.

1.3 INDEPENDENT
INSPECTION AGENCIES

- .1 Departmental Representative may engage and pay for service of Independent Inspection and Testing Agencies for purpose of inspecting and testing portions of Work except for the following which remain part of Contractor's responsibilities:
 - .1 Inspection and testing required by laws, ordinances, rules, regulations or orders of public authorities.

Emergency Generator Systems for
Search and Rescue Station Located
In Port Au Choix, NL

Page 2
2020-03-30

.2 Inspection and testing performed exclusively for Contractor's convenience.

.3 Tests as specified within various sections designated to be carried out by Contractor under the supervision of Departmental Representative.

.4 Additional tests specified in Clause 1.3.2.

.2 Where tests or inspections by designated Testing Agency reveal work not in accordance with contract requirements, Contractor shall pay costs for additional tests or inspections as Departmental Representative may require to verify acceptability of corrected work.

.3 Employment of inspection and testing agencies by Departmental Representative does not relax responsibility to perform Work in accordance with Contract Documents.

1.4 ACCESS TO WORK

.1 Furnish labour and facility to provide access to the work being inspected and tested.

.2 Co-operate to facilitate such inspections and tests.

.3 Make good work disturbed by inspections and tests.

1.5 PROCEDURES

.1 Notify Departmental Representative sufficiently in advance of when work is ready for tests, in order for Departmental Representative to make attendance arrangements with Testing Agency. When directed by Departmental Representative, notify such Agency directly.

.2 Submit representative samples of materials specified to be tested. Deliver in required

Emergency Generator Systems for
Search and Rescue Station Located
In Port Au Choix, NL

Page 3
2020-03-30

quantities to Testing Agency. Submit with reasonable promptness and in an orderly sequence so as not to cause delay in Work.

- .3 Provide labour and facilities to obtain and handle samples on site. Provide sufficient space on site for Testing Agency's exclusive use to store equipment.

1.6 REJECTED WORK

- .1 Remove and replace defective Work, whether result of poor workmanship, use of defective or damaged products and whether incorporated in Work or not, which has been identified by Departmental Representative as failing to conform to Contract Documents.
- .2 Make good damages to existing or new work, including work of other Contracts, resulting from removal or replacement of defective work.

1.7 TESTING BY
CONTRACTOR

- .1 Provide all necessary instruments, equipment and qualified personnel to perform tests designated as Contractor's responsibilities herein or elsewhere in the Contract Documents.

Emergency Generator Systems for
Search and Rescue Station Located
In Port Au Choix, NL

Page 1
2020-03-30

1.1 SANITARY
FACILITIES

- .1 Provide sanitary facilities for work force in accordance with governing regulations and ordinances.
- .2 Post notices and take such precautions as required by local health authorities. Keep area and premises in sanitary condition.

1.2 WATER SUPPLY

- .1 Arrange, pay for and maintain temporary water supply in accordance with governing regulations and ordinances.

1.3 CONSTRUCTION
SIGN AND NOTICES

- .1 Contractor or subcontractor advertisement signboards are not permitted on site.
- .2 Only notices of safety or instructions are permitted on site.
- .3 Maintenance and Disposal of Site Signs:
 - .1 Maintain approved signs and notices in good condition for duration of project and dispose of off site on completion of project or earlier if directed by Departmental Representative.

1.4 REMOVAL OF
TEMPORARY
FACILITIES

- .1 Remove temporary facilities from site when directed by Departmental Representative.

Emergency Generator Systems for
Search and Rescue Station Located
In Port Au Choix, NL

PART 1 - GENERAL

1.1 SECTION
INCLUDES

- .1 Barriers.
- .2 Traffic Controls.

1.2 INSTALLATION
AND REMOVAL

- .1 Provide temporary controls in order to execute work expeditiously.
- .2 Remove from site all such work after use.

1.3 HOARDING

- .1 Erect temporary site enclosure using new 1.2 m high snow fence wired to rolled steel "T" bar fence posts spaced at 2.4 m centres. Provide one lockable truck gate. Maintain fence in good repair.

1.4 GUARD RAILS
AND BARRICADES

- .1 Provide as required by governing authorities and to approval of Departmental Representative.

1.5 ACCESS TO SITE

- .1 Provide and maintain access to adjacent facilities.

1.6 PUBLIC
TRAFFIC FLOW

- .1 Provide and maintain competent signal flag operators, traffic signals, barricades and flares, lights, or lanterns as required to perform work and protect the public.

1.7 FIRE ROUTES

- .1 Maintain access to property including overhead clearances for use by emergency response vehicles.

1.8 PROTECTION FOR
OFF-SITE AND PUBLIC
PROPERTY

- .1 Protect surrounding private and public property from damage during performance of work.
- .2 Be responsible for damage incurred.

1.1 GENERAL

- .1 Use new material and equipment unless otherwise specified.
- .2 Within 7 days of written request by Departmental Representative, submit following information for any materials and products proposed for supply:
 - .1 name and address of manufacturer;
 - .2 trade name, model and catalogue number;
 - .3 performance, descriptive and test data;
 - .4 manufacturer's installation or application instructions;
 - .5 evidence of arrangements to procure.
 - .6 evidence of manufacturer delivery problems or unforeseen delays.
- .3 Provide material and equipment of specified design and quality, performing to published ratings and for which replacement parts are readily available.
- .4 Use products of one manufacturer for equipment or material of same type or classification unless otherwise specified.
- .5 Permanent labels, trademarks and nameplates on products are not acceptable in prominent locations, except where required for operating instructions, or when located in mechanical or electrical rooms.

1.2 PRODUCT QUALITY
AND REFERENCED
STANDARDS

- .1 Contractor shall be solely responsible for submitting relevant technical data and independent test reports to confirm whether a product or system proposed for use meets contract requirements and specified standards.
- .2 Final decision as to whether a product or system meets contract requirements rest solely with the Departmental Representative

Emergency Generator Systems for
Search and Rescue Station Located
In Port Au Choix, NL

in accordance with the General Conditions.

1.3 ACCEPTABLE
MATERIALS AND
ALTERNATIVES

- .1 Acceptable Materials: When materials specified include trade names or trade marks or manufacturer's or supplier's name as part of the material description, select and only use one of the names listed for incorporation into the Work.
- .2 Alternative Materials: Submission of alternative materials to trade names or manufacturer's names specified must be done during the bidding period following procedures indicated in the Instructions to Bidders.
- .3 Substitutions: After acceptance of bid, substitution of a specified material will be dealt with as a change to the Work in accordance with the General Conditions of the Contract.

1.4 MANUFACTURERS
INSTRUCTIONS

- .1 Unless otherwise specified, comply with manufacturer's latest printed instructions for materials and installation methods to be used. Do not rely on labels or enclosure provided with products. Obtain written instructions directly from manufacturers.
- .2 Notify Departmental representative in writing of any conflict between these specifications and manufacturers instructions, so that Departmental Representative will designate which document is to be followed.

1.5 AVAILABILITY

- .1 Immediately notify Departmental Representative in writing of unforeseen or unanticipated material delivery problems by manufacturer. Provide support documentation as per Clause 1.1.2 above.

1.6 WORKMANSHIP

- .1 Ensure quality of work is of highest standard, executed by workers experienced and skilled in respective duties for which they are employed.
- .2 Remove unsuitable or incompetent workers from site as stipulated in General Conditions.
- .3 Ensure cooperation of workers in laying out work. Maintain efficient and continuous supervision on site at all times.
- .4 Coordinate work between trades and subcontractors.
- .5 Coordinate placement of openings, sleeves and accessories.

1.7 FASTENINGS -
GENERAL

- .1 Provide metal fastenings and accessories in same texture, colour and finish as base metal in which they occur. Prevent electrolytic action between dissimilar metals. Use non-corrosive fasteners, anchors and spacers for securing exterior work and in humid areas.
- .2 Space anchors within limits of load bearing or shear capacity and ensure that they provide positive permanent anchorage. Wood or organic material plugs not acceptable.
- .3 Keep exposed fastenings to minimum, space evenly and lay out neatly.
- .4 Fastenings which cause spalling or cracking of material to which anchorage is made, are not acceptable.
- .5 Do not use explosive actuated fastening

Emergency Generator Systems for
Search and Rescue Station Located
In Port Au Choix, NL

devices unless approved by Departmental Representative. See Section 01 35 29 on Health and Safety in this regard.

1.8 FASTENINGS -
EQUIPMENT

- .1 Use fastenings of standard commercial sizes and patterns with material and finish suitable for service.
- .2 Use heavy hexagon heads, semi-finished unless otherwise specified.
- .3 Bolts may not project more than one diameter beyond nuts.
- .4 Use plain type washers on equipment, sheet metal and soft gasket lock type washers where vibrations occur and, use resilient washers with stainless steel.

1.9 STORAGE,
HANDLING AND
PROTECTION

- .1 Deliver, handle and store materials in manner to prevent deterioration and soiling and in accordance with manufacturer's instructions when applicable.
- .2 Store packaged or bundled materials in original and undamaged condition with manufacturer's seal and labels intact. Do not remove from packaging or bundling until required in Work. Provide additional cover where manufacturer's packaging is insufficient to provide adequate protection.
- .3 Store products subject to damage from weather in weatherproof enclosures.
- .4 Store cementitious products clear of earth or concrete floors, and away from walls.
- .5 Keep sand, when used for grout or mortar materials, clean and dry. Store sand on wooden

Emergency Generator Systems for
Search and Rescue Station Located
In Port Au Choix, NL

platforms and cover with waterproof
tarpaulins during inclement weather.

- .6 Store sheet materials and lumber on flat, solid supports and keep clear of ground. Slope to shed moisture.
- .7 Store and mix paints in heated and ventilated room. Remove oily rags and other combustible debris from site daily. Take every precaution necessary to prevent spontaneous combustion.
- .8 Immediately remove damaged or rejected materials from site.
- .9 Touch-up damaged factory finished surfaces to Departmental Representative's satisfaction. Use touch-up materials to match original. Do not paint over name plates.

1.10 CONSTRUCTION
EQUIPMENT AND PLANT

- .1 On request, prove to the satisfaction of Departmental Representative that the construction equipment and plant are adequate to manufacture, transport, place and finish work to quality and production rates specified. If inadequate, replace or provide additional equipment or plant as directed.
- .2 Maintain construction equipment and plant in good operating order. Prevent oil and other contaminant leaks. Should any contaminant leak onto ground or into the water, take immediate and appropriate measures to contain, cleanup and dispose in an environmentally responsible manner.

Emergency Generator Systems for
Search and Rescue Station Located
In Port Au Choix, NL

Page 1
2020-03-30

PART 1 - GENERAL

1.1 GENERAL

- .1 Conduct cleaning and disposal operations to comply with local ordinances and anti-pollution laws.
- .2 Store volatile waste in covered metal containers, and remove from premises at end of each working day.
- .3 Prevent accumulation of wastes which create hazardous conditions.
- .4 Provide adequate ventilation during use of volatile or noxious substances.

1.2 CLEANING DURING CONSTRUCTION

- .1 Maintain project grounds and public properties in a tidy condition, free from accumulations of waste material and debris. Clean areas on a daily basis.
- .2 Provide on-site garbage containers for collection of waste materials and debris.
- .3 Remove waste materials and debris from site on a daily basis.

1.3 FINAL CLEANING

- .1 In preparation for acceptance of the Work perform final cleaning.

1.1 RELATED SECTIONS .1 01 74 11 - Cleaning.

- 1.2 WASTE AUDIT .1 At project start-up, conduct waste audit of:
- .1 Site conditions identifying salvageable and non-salvageable items and waste resulting from demolition and removal work.
 - .2 Projected waste resulting from product packaging and from material leftover after installation work.
- .2 Develop written list. Record type, composition and quantity of various salvageable items and waste anticipated, reasons for waste generation and operational factors which contribute to waste.

- 1.3 WASTE REDUCTION .1 Based on waste audit, develop waste reduction program.
- .2 Structure program to prioritize actions, with waste reduction as first priority, followed by salvage and recycling effort, then disposal as solid waste.
- .3 Identify materials and equipment to be:
- .1 Protected and turned over to Departmental Representative when indicated.
 - .2 Salvaged for resale by Contractor.
 - .3 Sent to recycling facility.
 - .4 Sent to waste processing/landfill site for their recycling effort.
 - .5 Disposed of in approved landfill site.
- .4 Reduce construction waste during installation work. Undertake practices which will minimize waste and optimize full use of new materials on site, such as:
- .1 Use of a central cutting area to allow

for easy access to off-cuts;

.2 Use of off-cuts for blocking and bridging elsewhere.

.3 Use of effective and strategically placed facilities on site for storage and staging of left-over or partially cut materials to allow for easy incorporation into work whenever possible avoiding unnecessary waste.

- .5 Develop other strategies and innovative procedures to reduce waste such as minimizing the extent of packaging used for delivery of materials to site, etc.

1.4 MATERIAL SOURCE
SEPARATION PROCESS

- .1 Develop and implement material source separation process at commencement of work as part of mobilization and waste management at site.

- .2 Provide on-site facilities to collect, handle and store anticipated quantities of reusable, salvageable and recyclable materials.

.1 Use suitable containers for individual collection of items based on intended purpose.

.2 Locate to facilitate deposit but without hindering daily operations of existing building tenants.

.3 Clearly mark containers and stockpiles as to purpose and use.

- .3 Perform demolition and removal of existing structure components and equipment following a systematic deconstruction process.

.1 Separate materials and equipment at source, carefully dismantling, labelling and stockpiling alike items for the following purposes:

- .1 Reinstallation into the work where indicated.
- .2 Salvaging reusable items not needed in project which Contractor may sell to other parties. Sale of such items not permitted on site.
- .3 Sending as many items as possible to locally available recycling facility.
- .4 Segregating remaining waste and debris into various individual waste categories for disposal in a "non-mixed state" as recommended by waste processing/landfill sites.
- .4 Isolate product packaging and delivery containers from general waste stream. Send to recycling facility or return to supplier/manufacturer.
- .5 Send leftover material resulting from installation work for recycling whenever possible.
- .6 Establish methods whereby hazardous and toxic waste materials, and their containers, encountered or used in the course work are properly isolated, stored on site and disposed in accordance with applicable laws and regulations from authorities having jurisdiction.
- .7 Isolate and store existing materials and equipment identified for re-incorporation into the Work. Protect against damage.

1.5 WORKER TRAINING
AND SUPERVISION

- .1 Provide adequate training to workforce, through meetings and demonstrations, to emphasize purpose and worker

responsibilities in carrying out the Waste Management Plan.

- .2 Waste Management Coordinator: designate full-time person on site, experienced in waste management and having knowledge of the purpose and content of Waste Management Plan to:
 - .1 Oversee and supervise waste management during work.
 - .2 Provide instructions and directions to all workers and subcontractors on waste reduction, source separation and disposal practices.
- .3 Post a copy of Plan in a prominent location on site for review by workers.

1.6 CERTIFICATION
OF MATERIAL
DIVERSION

- .1 Submit to Departmental Representative, copies of certified weigh bills from authorized waste processing sites and sale receipts from recycling/reuse facilities confirming receipt of building materials and quantity of waste diverted from landfill.
- .2 Submit data at pre-determined project milestones as determined by Departmental Representative.
- .3 Compare actual quantities diverted from landfill with projections made during waste audit.

1.7 DISPOSAL
REQUIREMENTS

- .1 Burying or burning of rubbish and waste materials is prohibited.
- .2 Disposal of waste, volatile materials, mineral spirits, oil, paint, paint thinner

or unused preservative material into waterways, storm, or sanitary sewers is prohibited.

- .3 Do not dispose of preservative treated wood through incineration.
- .4 Do not dispose of preservative treated wood with other materials destined for recycling or reuse.
- .5 Dispose of treated wood, end pieces, wood scraps and sawdust at a sanitary landfill.
- .6 Dispose of waste only at approved waste processing facility or landfill sites approved by authority having jurisdiction.
- .7 Contact the authority having jurisdiction prior to commencement of work, to determine what, if any, demolition and construction waste materials have been banned from disposal in landfills and at transfer stations. Take appropriate action to isolate such banned materials at site of work and dispose in strict accordance with provincial and municipal regulations.
- .8 Transport waste intended for landfill in separated condition, following rules and recommendations of Landfill Operator in support of their effort to divert, recycle and reduce amount of solid waste placed in landfill.
- .9 Collect, bundle and transport salvaged materials to be recycled in separated categories and condition as directed by recycling facility. Ship materials only to approved recycling facilities.

- .10 Sale of salvaged items by Contractor to other parties not permitted on site.

Emergency Generator Systems for
Search and Rescue Station Located
In Port Au Choix, NL

Page 1
2020-03-30

1.1 PROJECT RECORD
DOCUMENTS

- .1 Departmental Representative will provide two white print sets of contract drawings and two copies of Specifications.
- .2 Maintain at site one set of the contract drawings and specifications to record actual "As-Built" site conditions.
- .3 At project completion, submit full manual of products used in new work (complete with manufacturer's data sheets, warranty data, user manuals, etc.). Maintenance manuals to be submitted in hard copy (2 copies) and in electronic format (pdf file format).

Emergency Generator Systems for
Search and Rescue Station Located
In Port Au Choix, NL

Page 1
2020-03-30

1.1 INTENT

- .1 Undertake commissioning to bring the facility to a fully operational state and free of deficiencies in the most effective and timely manner available.
- .2 Commissioning incorporates inspection and quality assurance activities as construction progresses, including start up and demonstration, performance verification, fine tuning, and operator training.
- .3 Bear all costs associated with the required personnel and test equipment as outlined in specification sections and all costs with organizing and managing the activities of the applicable subtrades as identified in this section.
- .4 Fully document all tests and inspections performed during the construction, at start up, and during performance verification and fine tuning. Incorporate into final commissioning documentation.
- .5 Provide direct training to designated staff responsible for the operation and maintenance of the equipment and systems.

1.2 COMMISSIONING

- .1 Conduct commissioning once identified prerequisite activities are completed for a system and approved by the Departmental Representative.
- .2 Engineer to issue a commissioning plan based on the complexity of systems. Develop and implement a detailed schedule of commissioning related activities.
- .3 Test all electrical components and operating procedures by challenging these systems to realistic operating conditions and train operational staff.

Emergency Generator Systems for
Search and Rescue Station Located
In Port Au Choix, NL

Page 1
2020-03-30

PART 1 GENERAL

1.1 SECTIONS INCLUDES

- .1 Methods and procedures for demolishing, salvaging, recycling and removing sitework items designated to be removed in whole or in part, and for backfilling resulting trenches and excavations. All areas disturbed during trenching to be reinstated to pre-construction conditions (this includes any grassed or paved areas).

1.2 RELATED SECTIONS

- .1 Section 01 33 00 - Submittal Procedures
- .2 Section 01 35 29.06 - Health and Safety Requirements
- .3 Section 01 35 43 - Environmental Procedures
- .4 Section 01 45 00 - Quality Control
- .5 Section 01 74 21 - Construction/Demolition Waste Management and Disposal.

1.3 SUBMITTALS

- .1 Shop drawings:
 - .1 Submit for approval drawings, diagrams or details showing sequence of demolition work and supporting structures and underpinning, where required by authorities having jurisdiction.
 - .2 Submit drawings stamped and signed by qualified professional engineer licensed in Province of Newfoundland and Labrador, Canada.
- .2 Submit plan indicating:
 - .1 Descriptions of and anticipated quantities of materials to be salvaged, reused, recycled and landfilled.
 - .2 Schedule of selective demolition.

Emergency Generator Systems for
Search and Rescue Station Located
In Port Au Choix, NL

Page 2
2020-03-30

- .3 Submit copies of certified weigh bills, bills of lading from authorized disposal sites and reuse and recycling facilities for material removed from site upon request from Owner's Representative.

1.4 QUALITY ASSURANCE

- .1 Convene pre-installation meeting one week prior to beginning work of this section to:
 - .1 Verify project requirements.
 - .2 Review installation and substrate conditions.
 - .3 Co-ordination with building subtrades.
- .2 Arrange for site visit with Owner's Representative to examine existing site conditions adjacent to demolition work, prior to start of Work.

1.5 DELIVERY, STORAGE AND HANDLING

- .1 Protect existing items designated to remain and items designated for salvage. In event of damage to such items, replace or make repairs to approval of Owner's Representative and at no cost to Owner.
- .2 Remove and store materials to be salvaged in a manner to prevent damage.
- .3 Store and protect in accordance with requirements for maximum preservation of material.

1.6 SITE CONDITIONS

- .1 In all circumstances ensure that demolition work does not adversely affect adjacent water courses groundwater and wildlife, or contribute to excess air and noise pollution.
- .2 Do not dispose of waste or volatile materials such as mineral spirits, oil, petroleum based lubricants, or toxic cleaning solutions into watercourses, storm or sanitary sewers. Ensure proper disposal procedures are maintained throughout project.

Emergency Generator Systems for
Search and Rescue Station Located
In Port Au Choix, NL

Page 3
2020-03-30

- .3 Do not pump water containing suspended materials into watercourses, storm or sanitary sewers, or onto adjacent properties.
- .4 Control disposal or runoff of water containing suspended materials or other harmful substances in accordance with local authorities.
- .5 Protect trees, plants and foliage on site and adjacent properties where indicated.

1.7 EXISTING CONDITIONS

- .1 Prior to start of any demolition work, remove contaminated or hazardous materials as defined by authorities having jurisdiction from site and dispose of at designated disposal facilities.

1.8 SCHEDULING

- .1 Notify Owner's Representative in writing when unforeseen delays occur.

PART 2 PRODUCTS (NOT APPLICABLE)

PART 3 EXECUTION

3.1 PREPARATION

- .1 Inspect site with Owner's Representative and verify extent and location of items designated for removal, disposal, alternative disposal, recycling, salvage and items to remain.
- .2 Locate and protect utilities. Preserve active utilities traversing site in operating condition.
- .3 Notify and obtain approval of utility companies before starting demolition.

Emergency Generator Systems for
Search and Rescue Station Located
In Port Au Choix, NL

Page 4
2020-03-30

3.2 REMOVAL OPERATIONS

- .1 Remove items as indicated. Do not disturb items designated to remain in place.
- .2 Interim removal of stockpiled material may be required by Owner's Representative if it is deemed to interfere with operations of Owner's Representative, Owner or other contractors.

3.3 RESTORATION

- .1 Restore areas and existing works outside areas of demolition to match conditions of adjacent, undisturbed areas.
- .2 Use soil treatments and procedures which are not harmful to health, are not injurious to plants, and do not endanger wildlife, adjacent water courses or ground water.

3.4 CLEAN UP

- .1 Upon completion of work, remove debris, trim surfaces and leave work site clean.
- .2 Use cleaning solutions and procedures which are not harmful to health, are not injurious to plants, and do not endanger wildlife, adjacent water courses or ground water.

END OF SECTION

Emergency Generator Systems for
Search and Rescue Station Located
In Port Au Choix, NL

Page 1
2020-03-30

PART 1 GENERAL

1.1 GENERAL

- .1 This Section covers items common to Sections of Division 26. This section supplements requirements of Division 1, and Division 33. Refer to Sections where applicable for bid depository.

1.2 REFERENCES

- .1 Canadian Standards Association (CSA)
 - .1 CSA C22.1, Canadian Electrical Code, Part 1, Safety Standard for Electrical Installations.
 - .2 CAN/CSA-22.3 No. 7-15, Underground Systems.
 - .3 CAN3-C235, Preferred Voltage Levels for AC Systems, 0 to 50,000 V.

1.3 CARE, OPERATION AND START-UP

- .1 Instruct Departmental Representative and operating personnel in the operation, care and maintenance of systems, system equipment and components.
- .2 Operating instructions to include following:
 - .1 Wiring diagrams, control diagrams, and control sequence for each principal system and item of equipment.
 - .2 Start up, proper adjustment, operating, lubrication, and shutdown procedures.
 - .3 Safety precautions.
 - .4 Procedures to be followed in event of equipment failure.
 - .5 Other items of instruction as recommended by manufacturer of each system or item of equipment.
- .3 Arrange and pay for services of manufacturer's factory service engineer to supervise start-up of installation, check, adjust, balance and calibrate components and instruct operating personnel.
- .4 Provide these services for such period, and for as many visits as necessary to put equipment in operation and

Emergency Generator Systems for
Search and Rescue Station Located
In Port Au Choix, NL

Page 2
2020-03-30

ensure that operating personnel are conversant with all aspects of its care and operation.

1.4 DESIGN REQUIREMENTS

- .1 Operating voltages: to CAN3-C235
- .2 Motors, electric heating, control and distribution devices and equipment to operate satisfactorily at 60 Hz within normal operating limits established by above standard. Equipment to operate in extreme operating conditions established in above standard without damage to equipment.

1.5 SUBMITTALS

- .1 Submit drawings stamped and signed by professional engineer registered or licensed in Province of Newfoundland and Labrador, Canada.
- .2 Submit wiring diagrams and installation details of equipment indicating proposed location, layout and arrangement, control panels, accessories, and other items that must be shown to ensure coordinated installation.
- .3 Identify on wiring diagrams circuit terminals and indicate internal wiring for each item of equipment and interconnection between each item of equipment.
- .4 Indicate of drawings clearances for operation, maintenance, and replacement of operating equipment devices.
- .5 Quality Control: in accordance with Section 01 45 00 - Quality Control.
 - .1 Provide CSA certified equipment and material. Where CSA certified equipment and material is not available, submit such equipment and material to authority having jurisdiction for approval before delivery to site.
 - .2 Submit test results of installed electrical systems and instrumentation.
 - .3 Submit, upon completion of Work, load balance report as described in sentence 3.4.6.

Emergency Generator Systems for
Search and Rescue Station Located
In Port Au Choix, NL

Page 3
2020-03-30

- .4 Submit certificate of acceptance from authority having jurisdiction upon completion of Work to Departmental Representative.
 - .6 Manufacturer's Field Reports: submit to Departmental Representative within seven (7) working days of review, verifying compliance of Work and electrical system and instrumentation testing, as described in paragraph 3.6-FIELD QUALITY CONTROL.
 - .7 Single Line Electrical Diagrams
 - .1 Provide single line electrical diagrams in glazed frames as follows:
 - .1 Electrical distribution system: locate in each main electrical room.
 - .2 Drawings: 600 x 600 mm minimum size.
- 1.6 PERMITS, FEES AND INSPECTION
 - .1 Submit to Electrical Inspection Division and Supply Authority necessary number of drawings and specifications for examination and approval prior to commencement of work.
 - .2 Pay associated fees.
 - .3 Departmental Representative will provide drawings and specifications required by Electrical Inspection Division and Supply Authority at no cost.
 - .4 Notify Departmental Representative of changes required by Electrical Inspection Division prior to making changes.
 - .5 Furnish Certificates of Acceptance from Electrical Inspection Division or authorities having jurisdiction on completion of work to Departmental Representative.
- 1.7 CO-ORDINATION
 - .1 Co-ordinate work with work of other divisions to avoid conflict.
 - .2 Locate distribution systems, equipment, and materials to provide minimum interference and maximum usable space.

Emergency Generator Systems for
Search and Rescue Station Located
In Port Au Choix, NL

Page 4
2020-03-30

- .3 Locate all existing underground services and make all parties aware of their existence and location.
 - .4 Where interference occurs, Departmental Representative must approve relocation of equipment and materials regardless of installation order.
 - .5 Notwithstanding the review of shop drawings, this division may be required to relocate electrical equipment which interferes with the equipment of other trades, due to lack of co-ordination by this Division. The cost of this relocation shall be the responsibility of this Division. The Departmental Representative shall decide the extent of relocation required.
- 1.8 CUTTING AND PATCHING
- .1 Inform all other divisions in time, concerning required openings. Where this requirement is not met, bear the cost of all cutting. Openings shall be the responsibility of Division 26. Obtain written approval of Structural engineer before drilling any beams or floors.
- 1.9 PROTECTION
- .1 Protect exposed live equipment during construction for personnel safety.
 - .2 Shield and mark all live parts "LIVE 120 VOLTS", or with appropriate voltage in English.
 - .3 Arrange for installation of temporary doors for rooms containing electrical distribution equipment. Keep these doors locked except when under direct supervision of electrician.
- 1.10 RECORD DRAWINGS
- .1 Obtain and pay for three sets of white prints. As the job progresses, mark these prints to accurately indicate installed work. Have the white prints available for inspection at the site at all times and present for scrutiny at each job meeting.

Emergency Generator Systems for
Search and Rescue Station Located
In Port Au Choix, NL

Page 5
2020-03-30

- .2 Show on the record drawings the installed inverts of all services entering and leaving the building and the property. Dimension underground services at key points of every run, in relation to the structure and building.
- .3 Indicate exact location of all services for future work. Show and dimension all work embedded in the structure.
- .4 Submit record drawings within 30 days prior to start of commissioning.

1.11 INSPECTION OF WORK

- .1 The Departmental Representative will make periodic visits to the site during construction to ascertain reasonable conformity to plans and specifications but will not execute quality control. The Contractor shall be responsible for the execution of his work in conformity with the construction documents and with the requirements of the inspection authority.

1.12 SCHEDULING OF WORK

- .1 Work shall be scheduled in phases as per other divisions of the specifications.
- .2 Become familiar with the phasing requirements for the work and comply with these conditions.
- .3 No additional monies will be paid for contractor's requirement to comply with work phasing conditions.

1.13 FIRE RATING OF PENETRATIONS

- .1 Maintain fire ratings around conduits passing through floors, ceilings and fire rated walls.
- .2 Use 3M brand or equal fire barrier products at each penetration.
- .3 Acceptable products for fire barrier products shall be 3M #CP25 fire barrier caulk, #303 putty, #FS 195 wrap and #CS195 sheet.

Emergency Generator Systems for
Search and Rescue Station Located
In Port Au Choix, NL

Page 6
2020-03-30

- .4 Acceptable manufacturers: Nelson, Fire Stop Systems, 3M or approved equal. Material of same manufacturer to be used throughout project.

PART 2 PRODUCTS

2.1 ELECTRIC MOTORS, EQUIPMENT AND CONTROLS

- .1 Supplier and installer responsibility is indicated in Motor, Control and Equipment Schedule on electrical drawings.
- .2 Control wiring and conduit is specified in Division 26 for standard of quality.

2.2 MATERIALS AND EQUIPMENT

- .1 Provide materials and equipment in accordance with Section 01 61 00 - Common Product Requirements.
- .2 Equipment and material to be CSA certified. Where there is no alternative to supplying equipment, which is not CSA certified, obtain special approval from Electrical Inspection Division.
- .3 Factory assemble control panels and component assemblies.

2.3 FINISHES

- .1 Shop finish metal enclosure surfaces by application of rust resistant primer inside and outside, and at least two coats of finish enamel.
 - .1 Paint outdoor electrical equipment "equipment green" finish to EEMAC Y1-1.
 - .2 Paint indoor switchgear and distribution enclosures light grey to EEMAC 2Y-1.

2.4 WARNING SIGNS

- .1 As specified and to meet requirements of Electrical Inspection Department and Departmental Representative.
- .2 Porcelain enamel decal signs, minimum size 175 x 250 mm.

Emergency Generator Systems for
Search and Rescue Station Located
In Port Au Choix, NL

Page 7
2020-03-30

2.5 WIRING TERMINATIONS

- .1 Lugs, terminals, screws used for termination of wiring to be suitable for either copper or aluminum conductors.

2.6 EQUIPMENT IDENTIFICATION

- .1 Identify electrical equipment with nameplates and labels as follows:
 - .1 Nameplates: Lamicoid 3 mm thick plastic engraving sheet, black white face, black white core, mechanically attached with self tapping screws.
 - .2 Sizes as follows:

NAMEPLATE SIZES

Size 1	10 x 50 mm	1 line	3 mm high letters
Size 2	12 x 70 mm	1 line	5 mm high letters
Size 3	12 x 70 mm	2 lines	3 mm high letters
Size 4	20 x 90 mm	1 line	8 mm high letters
Size 5	20 x 90 mm	2 lines	5 mm high letters
Size 6	25 x 100 mm	1 line	12 mm high letters
Size 7	25 x 100 mm	2 lines	6 mm high letters

- .2 Labels:
 - .1 Embossed plastic labels with 6 mm high letters unless specified otherwise.
- .3 Wording on nameplates and labels to be approved by Departmental Representative prior to manufacture.
- .4 Allow for average of twenty-five (25) letters per nameplate and label.
- .5 Identification to be English (and French where applicable).
- .6 Nameplates for terminal cabinets and junction boxes to indicate system name and voltage characteristics.

Emergency Generator Systems for
Search and Rescue Station Located
In Port Au Choix, NL

Page 8
2020-03-30

-
- .7 Disconnects, starters and contactors: indicate equipment being controlled and voltage.
 - .8 Terminal cabinets and pull boxes: indicate system name and voltage.
 - .9 Transformers: indicate capacity, primary and secondary voltages and transformer number.

2.7 WIRING IDENTIFICATION

- .1 Identify wiring with permanent indelible identifying markings, either numbered or coloured plastic tapes, on both ends of phase conductors of feeders and branch circuit wiring.
- .2 Maintain phase sequence and colour coding throughout.
- .3 Colour code: to CSA C22.1, Canadian Electrical Code.
- .4 Use colour coded wires in communication cables, matched throughout system.

2.8 CONDUIT AND CABLE IDENTIFICATION

- .1 Colour code conduits, boxes and metallic sheathed cables.
- .2 Code with plastic tape or paint at points where conduit or cable enters wall, ceiling, or floor, and at 15 m intervals.
- .3 Colours: 25 mm wide prime colour and 20 mm wide auxiliary colour.

<u>Conduit System</u>	<u>Prime Color</u>	<u>Auxiliary Color</u>
up to 250 V	Yellow	
up to 600 V	Yellow	Green
up to 5 kV	Yellow	Blue
up to 15 kV	Yellow	Red
Telephone	Green	
Other Communication Systems	Green	Blue
Fire Alarm	Red	
Emergency Voice	Red	Blue
Other Security Systems	Red	Yellow

Emergency Generator Systems for
Search and Rescue Station Located
In Port Au Choix, NL

Page 9
2020-03-30

PART 3 EXECUTION

3.1 NAMEPLATES AND LABELS

- .1 Ensure manufacturer's nameplates, CSA labels and identification nameplates are visible and legible after equipment is installed.

3.2 LOCATION OF OUTLETS

- .1 Locate outlets as per drawings.

3.3 CONDUIT AND CABLE INSTALLATION

- .1 Install conduit and sleeves prior to pouring of concrete. Sleeves through concrete: schedule 40 steel pipe, sized for free passage of conduit, and protruding 50 mm.
- .2 If plastic sleeves are used in fire rated walls or floors, remove before conduit installation.
- .3 Install cables, conduits and fittings to be embedded or plastered over, neatly and close to building structure so furring can be kept to minimum.

3.4 MOUNTING HEIGHTS

- .1 Mounting height of equipment is from finished floor to centreline of equipment unless specified or indicated otherwise.
- .2 If mounting height of equipment is not specified or indicated, verify before proceeding with installation.

3.5 CO-ORDINATION OF PROTECTIVE DEVICES

- .1 Ensure circuit protective devices such as overcurrent trips, relays and fuses are installed to required values and settings.

3.6 FIELD QUALITY CONTROL

- .1 All electrical work to be carried out by qualified, licensed electricians or apprentices as per the conditions of the Provincial Act respecting manpower vocational training and qualification. Employees

Emergency Generator Systems for
Search and Rescue Station Located
In Port Au Choix, NL

Page 10
2020-03-30

registered in a provincial apprentice's program shall be permitted, under the direct supervision of a qualified licensed electrician, to perform specific tasks - the activities permitted shall be determined based on the level of training attained and the demonstration of ability to perform specific duties.

- .2 The work of this division to be carried out by a contractor who holds a valid Code 1 Electrical Contractor License as issued by the Province.
- .3 Perform tests in Accordance with this section as noted and Section 01 91 13 - General Commissioning (Cx) Requirements.
- .4 Load Balance:
 - .1 Measure phase current to panelboard with normal loads (lighting) operating at time of acceptance. Adjust branch circuit connections as required to obtain best balance of current between phases and record changes.
 - .2 Measure phase voltages at loads and adjust transformer taps to within 2% of rated voltage of equipment.
 - .3 Submit, at completion of work, report listing phase and neutral currents on panelboards, dry-core transformers and motor control centres, operating under normal load. State hour and date on which each load was measured, and voltage at time of test.
- .5 Conduct and pay for following tests:
 - .1 Power generation and distribution system including phasing, voltage, grounding and load balancing.
 - .2 Circuits originating from branch distribution panels.
 - .3 Motors, heaters and associated control equipment including sequenced operations of systems where applicable.
 - .4 Systems: communications.
- .6 Furnish manufacturer's certificate or letter confirming that entire installation as it pertains to each system has been installed to manufacturer's instructions.

Emergency Generator Systems for
Search and Rescue Station Located
In Port Au Choix, NL

Page 11
2020-03-30

- .7 Insulation resistance testing.
 - .1 Megger and record circuits, feeders and equipment up to 350 V with a 500 V instrument.
 - .2 Megger and record 350 - 600 V circuits, feeders and equipment with a 1000 V instrument.
 - .3 Check resistance to ground before energizing and record value.
- .8 Carry out tests in presence of Departmental Representative.
- .9 Provide instruments, meters, equipment and personnel required to conduct tests during and conclusion of project.
- .10 Submit test results for Departmental Representative's review and include in Commissioning Manuals specified in Section 01 91 13 - Commissioning (Cx) Requirements.

3.7 CLEANING

- .1 Clean and touch up surfaces of shop-painted equipment scratched or marred during shipment or installation, to match original paint.
- .2 Clean and prime exposed non-galvanized hangers, racks and fastenings to prevent rusting.

END OF SECTION

Emergency Generator Systems for
Search and Rescue Station Located
In Port Au Choix, NL

Page 1
2020-03-30

PART 1 GENERAL

1.1 SECTION INCLUDES

- .1 Materials and installation for wire and box connectors.

1.2 RELATED SECTIONS

- .1 Section 26 05 00 - Common Work Results for Electrical.

1.3 REFERENCES

- .1 Canadian Standards Association (CSA)
 - .1 CAN/CSA-C22.2 No.18, Outlet Boxes, Conduit Boxes and Fittings.
 - .2 CAN/CSA-C22.2 No.65, Wire Connectors (Tri-National Standard with UL 486A-486B and NMX-J-543-ANCE-03).
- .2 Electrical and Electronic Manufacturers' Association of Canada (EEMAC)
 - .1 EEMAC 1Y-2, Bushing Stud Connectors and Aluminum Adapters (1200 Ampere Maximum Rating).
- .3 National Electrical Manufacturers Association (NEMA)

PART 2 PRODUCTS

2.1 MATERIALS

- .1 Pressure type wire connectors to: CSA C22.2 No.65, with current carrying parts of copper sized to fit copper conductors as required.
- .2 Fixture type splicing connectors to: CSA C22.2 No.65, with current carrying parts of copper sized to fit copper conductors 10 AWG or less.
- .3 Bushing stud connectors: to EEMAC 1Y-2 to consist of:
 - .1 Connector body and stud clamp for stranded copper conductors.
 - .2 Clamp for copper bar.
 - .3 Stud clamp bolts.
 - .4 Bolts for copper bar.
 - .5 Sized for conductors and bars as indicated.

Emergency Generator Systems for
Search and Rescue Station Located
In Port Au Choix, NL

Page 2
2020-03-30

- .4 Clamps or connectors for armoured cable, aluminum sheathed cable, mineral insulated cable, flexible conduit, non-metallic sheathed cable as required to: CAN/CSA-C22.2 No.18.
- .5 Terminal blocks for all pull boxes and junction boxes located on pedestals and under wharf panels.

PART 3 EXECUTION

3.1 INSTALLATION

- .1 Remove insulation carefully from ends of conductors and:
 - .1 Install mechanical pressure type connectors and tighten screws with appropriate compression tool recommended by manufacturer. Installation shall meet secureness tests in accordance with CSA C22.2 No.65.
 - .2 Install fixture type connectors and tighten. Replace insulating cap.
 - .3 Install bushing stud connectors in accordance with EEMAC 1Y-2.

END OF SECTION

Emergency Generator Systems for
Search and Rescue Station Located
In Port Au Choix, NL

Page 1
2020-03-30

Part 1 **General**

1.1 RELATED SECTIONS

- .1 Section 26 05 20 - Wire and Box Connectors (0-1000 V).
- .2 Refer to drawings for wiring type required under different applications.

1.2 REFERENCES

- .1 Canadian Standards Association (CSA)
 - .1 CSA C22.2 No .0.3, Test Methods for Electrical Wires and Cables.
 - .2 CAN/CSA-C22.2 No. 131, Type TECK 90 Cable.

PART 2 **PRODUCTS**

2.1 BUILDING WIRES

- .1 Conductors: stranded for 10 AWG and larger. Minimum size: 12 AWG.
- .2 Copper and ACM alloy conductors: size as indicated, with 600 V insulation of cross-linked thermosetting polyethylene material rated RW90 XLPE. Related to new emergency generator feeders. RWU90 XLPE not required under interior floor slabs.
- .3 Copper conductors: size as indicated, with thermoplastic insulation type TWH rated at 600 V, typically used for insulated ground wires.
- .4 Type ACM conductors permitted for feeders above 60 amps.

2.2 TECK Cable

- .1 Cable: to CAN/CSA-C22.2 No. 131.
- .2 Conductors:
 - .1 Grounding conductor: copper.

Emergency Generator Systems for
Search and Rescue Station Located
In Port Au Choix, NL

Page 2
2020-03-30

- .2 Circuit conductors: copper and ACM alloy, size as indicated.
 - .3 Insulation:
 - .1 Cross-linked polyethylene XLPE, rating - 600 V.
 - .4 Inner jacket: polyvinyl chloride material.
 - .5 Armour: interlocking aluminum, compliant to applicable Building Code classification for this project.
 - .6 Overall covering: thermoplastic polyvinyl chloride material.
 - .7 Fastenings:
 - .1 One-hole steel straps to secure surface cables 50 mm and smaller. Two-hole steel straps for cables larger than 50 mm.
 - .2 Channel type supports for two or more cables at 1500 mm centers.
 - .3 Threaded rods: 6 mm dia. to support suspended channels.
 - .8 Connectors:
 - .1 Watertight and/or type approved for TECK cable, as indicated.
- 2.3 CONTROL CABLES
- .1 Type LVT: 2 soft annealed copper conductors, sized as indicated, with thermoplastic insulation, outer covering of thermoplastic jacket. Low energy 300 V control cable: stranded annealed copper conductors sized as indicated, with PVC insulation type TW -40° C polyethylene insulation with shielding of tape coated with paramagnetic material wire braid over each conductor and overall covering of PVC jacket.

Emergency Generator Systems for
Search and Rescue Station Located
In Port Au Choix, NL

Page 3
2020-03-30

PART 3 EXECUTION

3.1 FIELD QUALITY CONTROL

- .1 Perform tests in accordance with Section 26 05 00 -
Common Work Results for Electrical.
- .2 Perform tests using method appropriate to site
conditions and to approval of Departmental
Representative and local authority having jurisdiction
over installation.
- .3 Perform tests before energizing electrical system.
- .4 No splices permitted in panelboard feeders in new
construction. Splices in re-work or renovation projects
only with pre-approval by Departmental Representative.

3.2 GENERAL CABLE INSTALLATION

- .1 Install cable in trenches in accordance with drawings
and as directed by Departmental Representative.
- .2 Terminate cables in accordance with Section 26 05 20 -
Wire and Box Connectors (0-1000 V).
- .3 Cable Colour Coding: to Section 26 05 00 Common Work
Results for Electrical.
- .4 Conductor length for parallel feeders to be identical.
- .5 Lace or clip groups of feeder cables at distribution
centres, pull boxes, and termination points.
- .6 Wiring in walls: typically drop or loop vertically from
above to better facilitate future renovations.
Generally wiring from below and horizontal wiring in
walls to be avoided unless indicated.
- .7 Branch circuit wiring for surge suppression receptacles
and permanently wired computer and electronic equipment
to be 2-wire circuits only, i.e. common neutrals not
permitted.

Emergency Generator Systems for
Search and Rescue Station Located
In Port Au Choix, NL

Page 4
2020-03-30

- .8 Provide numbered wire collars for control wiring.
Numbers to correspond to control shop drawing legend.
Obtain wiring diagram for control wiring.

3.3 INSTALLATION OF BUILDING WIRES

- .1 Install wiring as follows:
 - .1 In conduit systems in accordance with Section 26 05 34- Conduits, Conduit Fastenings and Conduit Fittings.
 - .2 In underground ducts in accordance with Section 26 05 43.01- Installation of Cables in Trenches and in Ducts.
 - .3 In trenches in accordance with Section 26 05 43.01- Installation of Cables in Trenches and in Ducts.
 - .4 Overhead service conductors in accordance with Section 26 24 01 - Service Equipment.

3.4 INSTALLATION OF TECK CABLE 0 -1000 V

- .1 Install cables.
 - .1 Group cables wherever possible on channels.
- .2 Install cable concealed, securely supported by straps and hangers.

END OF SECTION

Emergency Generator Systems for
Search and Rescue Station Located
In Port Au Choix, NL

Page 1
2020-03-30

PART 1 GENERAL

1.1 INSTALLATION TOOLS

- .1 Include with the material one complete set of installation tools. Tools to include all hydraulic pumps, fittings, compression dyes, cutting tools, measuring devices necessary to install all components.

PART 2 EXECUTION

2.1 INSTALLATION

- .1 Install terminations, and splices in accordance with manufacturer's instructions.
- .2 Bond and ground as required to CSA C22.2 No. 41.

END OF SECTION

Emergency Generator Systems for
Search and Rescue Station Located
In Port Au Choix, NL

Page 1
2020-03-30

PART 1 GENERAL

1.1 RELATED SECTIONS

- .1 Section 01 91 13 - General Commissioning (Cx) Requirements.
- .2 Section 26 05 00 - Common Work Results for Electrical.
- .3 Grounding conductors for all distribution grounding to be insulated copper, uninsulated where in contact with earth. Copper conductors shall, at a minimum, be used in the following areas: grounding of transformer neutrals, service entrance switch ground of neutral, padmount transformer grounding, ground rider conductors from main ground station to sub-closets, telephone and data system grounds and circuits rated less than 60 amps. Where type ACM conductors are used for circuits rated 60 amps or greater, type ACM bonding conductor is permitted.

1.2 REFERENCES

- .1 American National Standards Institute (ANSI)/Institute of Electrical and Electronics Engineers (IEEE)
 - .1 ANSI/IEEE 837, Qualifying Permanent Connections Used in Substation Grounding.
- .2 Canadian Standards Association, (CSA)
 - .1 CAN/CSA Z32, Electrical Safety and Essential Electrical Systems in Health Care Facilities, where applicable.

PART 2 PRODUCTS

2.1 EQUIPMENT

- .1 Clamps for grounding of conductor: size as indicated to electrically conductive underground water pipe.
- .2 Copper conductor: minimum 6 m long for each concrete encased electrode, bare, stranded, tinned, soft annealed, size as indicated.
- .3 Rod electrodes: copper clad steel 19 mm dia by 3 m long.

Emergency Generator Systems for
Search and Rescue Station Located
In Port Au Choix, NL

Page 2
2020-03-30

- .4 Plate electrodes: copper, surface area 0.2 m², 1.6 mm thick.
- .5 Grounding conductors: bare stranded copper, soft annealed, size as indicated.
- .6 Insulated grounding conductors: green, type TW.
- .7 Ground bus: copper, size as indicated, complete with insulated supports, fastenings, connectors.
- .8 Non-corroding accessories necessary for grounding system, type, size, material as indicated, including but not necessarily limited to:
 - .1 Grounding and bonding bushings.
 - .2 Protective type clamps.
 - .3 Bolted type conductor connectors, as required by local authority having jurisdiction.
 - .4 Thermit welded type conductor connectors, as indicated.
 - .5 Bonding jumpers, straps.
 - .6 Pressure wire connectors.

PART 3 EXECUTION

3.1 INSTALLATION GENERAL

- .1 Install complete permanent, continuous grounding system including, electrodes, conductors, connectors, accessories. Where EMT is used, run insulated copper ground wire in conduit.
- .2 Install connectors in accordance with manufacturer's instructions.
- .3 Protect exposed grounding conductors from mechanical injury.
- .4 Make buried connections, and connections to conductive water main, electrodes, using copper welding by thermit process.
- .5 Use mechanical connectors for grounding connections to equipment provided with lugs.
- .6 Soldered joints not permitted.

Emergency Generator Systems for
Search and Rescue Station Located
In Port Au Choix, NL

Page 3
2020-03-30

- .7 Install bonding wire for flexible conduit, connected at both ends to grounding bushing, solderless lug, clamp or cup washer and screw. Neatly cleat bonding wire to exterior of flexible conduit.
- .8 Install flexible ground straps for bus duct enclosure joints, where such bonding is not inherently provided with equipment.
- .9 Install separate ground conductor to outdoor lighting standards.
- .10 Connect building structural steel and metal siding to ground by welding copper to steel.
- .11 Make grounding connections in radial configuration only, with connections terminating at single grounding point. Avoid loop connections.
- .12 Bond single conductor, metallic armoured cables to cabinet at supply end and load end.
- .13 Ground secondary service pedestals.

3.2 MANHOLES

- .1 Install conveniently located grounding electrode and size 3/0 stranded copper conductor in each manhole.
- .2 Install ground rod in each manhole so that top projects through bottom of manhole. Provide with lug to which grounding connection can be made.

3.3 ELECTRODES

- .1 Install rod, plate electrodes and make grounding connections.
- .2 Bond separate, multiple electrodes together.
- .3 Use size 2/0, 3/0 or 4/0 AWG copper conductors for connections to electrodes as required by code.
- .4 Make special provision for installing electrodes that will give acceptable resistance to ground value where rock or sand terrain prevails. Ground as indicated.

Emergency Generator Systems for
Search and Rescue Station Located
In Port Au Choix, NL

Page 4
2020-03-30

3.4 SYSTEM AND CIRCUIT GROUNDING

- .1 Install system and circuit grounding connections to neutral of primary 600 V system, secondary 208 V system.

3.5 EQUIPMENT GROUNDING

- .1 Install grounding connections to typical equipment included in, but not necessarily limited to following list. Service equipment, transformers, switchgear, duct systems, frames of motors, motor control centres, starters, control panels, building steel work, generators, elevators and escalators, distribution panels, outdoor lighting.

3.6 GROUNDING BUS

- .1 Install copper grounding bus mounted on insulated supports on wall of electrical room.
- .2 Ground items of electrical equipment in electrical room to ground bus with individual bare stranded copper connections size as required by code.

3.7 PERMAFROST

- .1 Drive three -19 mm diam x 3 m copper clad ground rods at least 1.8 m apart in original undisturbed ground. If rods will not penetrate permafrost, drive at angle not more than 60° from vertical, and in same direction. Rods must be driven, not trenched.
- .2 Install ground wire from service neutral bar to rods and where buried use bare copper not smaller than size 1AWG7- strand or size 4AWG solid, and at least 460 mm below ground. Bond ground conductor, or short tap from it, to outside metal sheathing of building close to power service conduit. Use lug or cast clamp, with bronze or plated bolt, nut and washers (not sheet metal screw or wood screw). Remove paint from sheathing for good contact. Conduit is required only on outside wall of building. Indoors, run bare and fasten as specified for equipotential bonding wire.
- .3 Install electrode interconnections where metal parts, circuits or grounding conductors and/or electrodes are in proximity to lightning rod conductors.

Emergency Generator Systems for
Search and Rescue Station Located
In Port Au Choix, NL

Page 5
2020-03-30

3.8 FIELD QUALITY CONTROL

- .1 Perform tests in accordance with Section 26 05 00 - Common Work Results - Electrical and Section 01 19 13 - Commissioning (Cx) Requirements.
- .2 Perform ground continuity and resistance tests using method appropriate to site conditions and to approval of Departmental Representative and local authority having jurisdiction over installation.
- .3 Perform tests before energizing electrical system.
- .4 Disconnect ground fault indicator during tests.

END OF SECTION

Emergency Generator Systems for
Search and Rescue Station Located
In Port Au Choix, NL

Page 1
2020-03-30

1.1 General

1.2 REALTED SECTIONS

- .1 Section 01 33 00 - Submittal Procedures.
- .2 Section 01 91 13 - General Commissioning (Cx) Requirements.
- .3 Section 26 05 00 - Common Work Results for Electrical.

1.3 SUBMITTALS

- .1 Submit shop drawings and product data for cabinets.
- .2 Provide manufacturer's printed product literature, specifications and datasheet and include product characteristics, performance criteria, physical size, finish and limitations.
- .3 Provide drawings stamped and signed by professional engineer registered or licensed in the Province of Newfoundland and Labrador, Canada.

PART 2 PRODUCTS

2.1 SPLITTERS

- .1 Sheet metal enclosure, welded corners and formed hinged cover suitable for locking in closed position.
- .2 Main and branch lugs to match required size and number of incoming and outgoing conductors as indicated.
- .3 At least three spare terminals on each set of lugs in splitters less than 400 A.

2.2 JUNCTION AND PULL BOXES

- .1 PVC Junction boxes complete with bolt on gasket covers. Junction boxes to contain terminal blocks as indicated on drawings.

Emergency Generator Systems for
Search and Rescue Station Located
In Port Au Choix, NL

Page 2
2020-03-30

- .2 Covers with 25 mm minimum extension all around, for flush-mounted pull and junction boxes.

2.3 CABINETS

- .1 Type E: sheet steel, hinged door and return flange overlapping sides, handle, lock and catch, for surface mounting.
- .2 Type T: sheet steel cabinet, with hinged door, latch, lock, 2 keys, containing 19 mm fir plywood backboard for surface flush mounting.

PART 3 EXECUTION

3.1 SPLITTER INSTALLATION

- .1 Install splitters and mount plumb, true and square to the building lines.
- .2 Extend splitters full length of equipment arrangement except where indicated otherwise.

3.2 JUNCTION, PULL BOXES AND CABINETS INSTALLATION

- .1 Install pull boxes in inconspicuous but accessible locations.
- .2 Mount cabinets with top not higher than 2 m above finished floor.
- .3 Install terminal block as indicated.
- .4 Only main junction and pull boxes are indicated.

3.3 IDENTIFICATION

- .1 Provide equipment identification in accordance with Section 26 05 00 - Common Work Results for Electrical.
- .2 Install size 2 identification labels indicating system name voltage and phase.

Emergency Generator Systems for
Search and Rescue Station Located
In Port Au Choix, NL

Page 3
2020-03-30

END OF SECTION

Emergency Generator Systems for
Search and Rescue Station Located
In Port Au Choix, NL

Page 1
2020-03-30

PART 1 GENERAL

1.1 RELATED SECTIONS

- .1 Section 26 05 00 - Common Work Results for Electrical.
- .2 Section 26 05 34 - Conduits, Conduit Fastenings and Fittings.

1.2 REFERENCES

- .1 Canadian Standards Association (CSA)
 - .1 CSA C22.1, Canadian Electrical Code, Part 1.

PART 2 PRODUCTS

2.1 OUTLET AND CONDUIT BOXES GENERAL

- .1 Size boxes in accordance with CSA C22.1.
- .2 102 mm square or larger outlet boxes as required for special devices.
- .3 Gang boxes where wiring devices are grouped.
- .4 Blank cover plates for boxes without wiring devices.
- .5 Combination boxes with barriers where outlets for more than one system are grouped.

2.2 GALVANIZED STEEL OUTLET BOXES

- .1 Electro-galvanized steel single and multi gang flush device boxes for flush installation, minimum size 76 x 50 x 38 mm or as indicated. 102 mm square outlet boxes when more than one conduit enters one side with extension and plaster rings as required.
- .2 Electro-galvanized steel utility boxes for outlets connected to surface-mounted EMT conduit, minimum size 102 x 54 x 48 mm.
- .3 102 mm square or octagonal outlet boxes for lighting fixture outlets.

Emergency Generator Systems for
Search and Rescue Station Located
In Port Au Choix, NL

Page 2
2020-03-30

- .4 102 mm square outlet boxes with extension and plaster rings for flush mounting devices in finished plaster walls.
- 2.3 CONDUIT BOXES
 - .1 Cast FS or FD aluminum boxes with factory-threaded hubs and mounting feet for surface wiring of switches and receptacle.
- 2.4 OUTLET BOXES FOR NON-METALLIC SHEATHED CABLE
 - .1 Electro-galvanized, sectional, screw ganging steel boxes, minimum size 76 x 50 x 63 mm with two double clamps to take non-metallic sheathed cables. For use in wood stud construction only.
- 2.5 FITTINGS - GENERAL
 - .1 Bushing and connectors with nylon insulated throats.
 - .2 Knock-out fillers to prevent entry of debris.
 - .3 Conduit outlet bodies for conduit up to 32 mm and pull boxes for larger conduits.
 - .4 Double locknuts and insulated bushings on sheet metal boxes.
 - .5 Double split rings for AC-90 terminations.
- 2.6 SERVICE FITTINGS
 - .1 'High tension' receptacle fitting made of 2-piece die-cast aluminum with brushed aluminum housing finish for 1 duplex receptacles. Bottom plate with two knockouts for centered or offset installation.
 - .2 Pedestal type 'low tension' fitting made of 2-piece die cast aluminum with brushed aluminum housing finish to accommodate two amphenol jack connectors.

Emergency Generator Systems for
Search and Rescue Station Located
In Port Au Choix, NL

Page 3
2020-03-30

PART 3 EXECUTION

3.1 INSTALLATION

- .1 Support boxes independently of connecting conduits.
- .2 Fill boxes with paper, sponges or foam or similar approved material to prevent entry of debris during construction. Remove upon completion of work.
- .3 For flush installations mount outlets flush with finished wall using plaster rings to permit wall finish to come within 6 mm of opening.
- .4 Provide correct size of openings in boxes for conduit. Reducing washers are not allowed.
- .5 Vacuum clean interior of outlet boxes before installation of wiring devices.
- .6 Identify systems for outlet boxes as required.

END OF SECTION

Emergency Generator Systems for
Search and Rescue Station Located
In Port Au Choix, NL

Page 1
2020-03-30

PART 1 **GENERAL**

1.1 REFERENCES

.1 Canadian Standards Association (CSA)

- .1 CAN/CSA C22.2 No. 18, Outlet Boxes, Conduit Boxes, and Fittings and Associated Hardware, a National Standard of Canada.
- .2 CSA C22.2 No. 45, Rigid Metal Conduit.
- .3 CSA C22.2 No. 56, Flexible Metal Conduit and Liquid-Tight Flexible Metal Conduit.
- .4 CSA C22.2 No. 83, Electrical Metallic Tubing.
- .5 CSA C22.2 No. 211.2, Rigid PVC (Unplasticized) Conduit.
- .6 CAN/CSA C22.2 No. 227.3, Non-metallic Mechanical Protection Tubing (NMPT), a National Standard of Canada.

1.2 SUBMITTALS

.1 Product data: submit manufacturer's printed product literature, specifications and datasheets.

- .1 Submit cable manufacturing data.

.2 Quality assurance submittals:

- .1 Test reports: submit certified test reports.
- .2 Certificates: submit certificates signed by manufacturer certifying that materials comply with specified performance characteristics and physical properties.
- .3 Instructions: submit manufacturer's installation instructions.

PART 2 **PRODUCTS**

2.1 CONDUITS

- .1 Rigid metal conduit: to CSA C22.2 No. 45, hot dipped galvanized steel threaded.

Emergency Generator Systems for
Search and Rescue Station Located
In Port Au Choix, NL

Page 2
2020-03-30

- .2 Epoxy coated conduit: to CSA C22.2 No. 45, with zinc coating and corrosion resistant epoxy finish inside and outside.
- .3 Electrical metallic tubing (EMT): to CSA C22.2 No. 83, with couplings.
- .4 Rigid PVC conduit: to CSA C22.2 No. 211.2.
- .5 Flexible metal conduit: to CSA C22.2 No. 56, aluminum liquid-tight flexible metal.
- .6 FRE conduit: to CSA C22.2.
- .7 Flexible PVC conduit: to CAN/CSA-C22.2 No. 227.3,

2.2 CONDUIT FASTENINGS

- .1 One-hole steel straps to secure surface conduits 50 mm and smaller. Two-hole steel straps for conduits larger than 50 mm.
- .2 Beam clamps to secure conduits to exposed steel work.
- .3 Channel type supports for two or more conduits at 1.5 m oc.
- .4 Threaded rods, 6 mm dia., to support suspended channels.

2.3 CONDUIT FITTINGS

- .1 Fittings: manufactured for use with conduit specified. Coating: same as conduit.
- .2 Factory Fiberglass "ells" where 90°, 45 ° or 22.5 ° bends are required for 25 mm and larger conduits.
- .3 Ensure conduit bends other than factory "ells" are made with an approved bender. Making offsets and other bends by cutting and rejoining 90-degree bends are not permitted.
- .4 Connectors and couplings for EMT. Steel set-screw type, size as required.

Emergency Generator Systems for
Search and Rescue Station Located
In Port Au Choix, NL

Page 3
2020-03-30

2.4 EXPANSION FITTINGS FOR RIGID CONDUIT

- .1 Weatherproof expansion fittings with internal bonding assembly suitable for 100 mm linear expansion.
- .2 Watertight expansion fittings with integral bonding jumper suitable for linear expansion and 19 mm deflection in all directions.
- .3 Weatherproof expansion fittings for linear expansion at entry to panel.

2.5 FISH CORD

- .1 Polypropylene.

PART 3 **EXECUTION**

3.1 MANUFACTURER'S INSTRUCTIONS

- .1 Compliance: comply with manufacturer's written recommendations or specifications, including product technical bulletins, handling, storage and installation instructions, and datasheets.

3.2 INSTALLATION

- .1 Install all conduit, conduit fittings and accessories in accordance with the latest edition of the Canadian Electrical Code in a manner that does not alter, change or violate any part of the installed system components or the CSA/UL certification of these components.
- .2 Install conduits to conserve headroom in exposed locations and cause minimum interference in spaces through which they pass.
- .3 Conceal conduits except in mechanical and electrical service rooms and in unfinished areas.
- .4 Surface mount conduits except in finished areas or as indicated.
- .5 Use rigid hot dipped galvanized steel threaded conduit for exposed work below 2.4 m above finished floor.

Emergency Generator Systems for
Search and Rescue Station Located
In Port Au Choix, NL

Page 4
2020-03-30

- .6 Use electrical metallic tubing (EMT) except in cast concrete and above 2.4 m not subject to mechanical injury, as well as concealed work in masonry construction.
- .7 Use rigid PVC conduit underground and buried in or under concrete slab on grade.
- .8 Use flexible metal conduit for connection to motors in dry areas, connection to recessed incandescent fixtures without a prewired outlet box, connection to surface or recessed light fixtures and work in movable metal partitions.
- .9 Use liquid tight flexible metal conduit for connection to motors or vibrating equipment in damp, wet or corrosive locations.
- .10 Install conduit sealing fittings in hazardous areas. Fill with compound.
- .11 Minimum conduit size for lighting and power circuits: 19 mm. 12 mm conduit is acceptable for switch leg drops only where one two-wire circuit and ground is required.
- .12 Bend conduit cold. Replace conduit if kinked or flattened more than 1/10th of its original diameter.
- .13 Mechanically bend steel conduit over 19 mm dia.
- .14 Field threads on rigid conduit must be of sufficient length to draw conduits up tight.
- .15 Install fish cord in empty conduits.
- .16 Remove and replace blocked conduit sections. Do not use liquids to clean out conduits.
- .17 Dry conduits out before installing wire.

3.3 SURFACE CONDUITS

- .1 Run parallel or perpendicular to building lines.
- .2 Group conduits wherever possible on suspended channels.

Emergency Generator Systems for
Search and Rescue Station Located
In Port Au Choix, NL

Page 5
2020-03-30

- .3 Do not pass conduits through structural members except as indicated.
- .4 Do not locate conduits less than 75 mm parallel to steam or hot water lines with minimum of 25 mm at crossovers.
- 3.4 CONCEALED CONDUITS
 - .1 Run parallel or perpendicular to building lines.
 - .2 Do not install horizontal runs in masonry walls.
 - .3 Do not install conduits in terrazzo or concrete toppings.
- 3.5 CONDUITS IN CAST-IN-PLACE CONCRETE
 - .1 Locate to suit reinforcing steel. Install in centre one third of slab. Use rigid PVC conduit.
 - .2 Install sleeves where conduits pass through slab or wall.
 - .3 Provide oversized sleeve for conduits passing through waterproof membrane, before membrane is installed. Use cold mastic between sleeve and conduit.
 - .4 Do not place conduits in slabs in which slab thickness is less than 4 times conduit diameter.
 - .5 Encase conduits completely in concrete with minimum 25 mm concrete cover.
 - .6 Organize conduits in slab to minimize cross-overs.
- 3.6 CONDUITS IN CAST-IN-PLACE SLABS ON GRADE
 - .1 Run conduits 25 mm and larger below slab and encased in 75 mm concrete envelope. Provide 50 mm of sand over concrete envelope below floor slab.
- 3.7 CONDUITS UNDERGROUND
 - .1 Slope conduits to provide drainage.

Emergency Generator Systems for
Search and Rescue Station Located
In Port Au Choix, NL

Page 6
2020-03-30

- .2 Waterproof joints (PVC excepted) with heavy coat of bituminous paint.

3.8 CLEANING

- .1 Proceed in accordance with Section 01 74 11 - Cleaning.
- .2 On Completion and verification of performance of installation, remove surplus materials, excess materials rubbish, tools and equipment.

END OF SECTION

Emergency Generator Systems for
Search and Rescue Station Located
In Port Au Choix, NL

Page 1
2020-03-30

Part 1 **General**

1.1 RELATED SECTIONS

- .1 Section 01 74 21 - Construction/Demolition Waste Management and Disposal.
- .2 Section 01 91 13 - General Commissioning (Cx) Requirements.
- .3 Section 26 05 00 - Common Work Results for Electrical.
- .4 Section 31 23 33.01 - Excavating, Trenching and Backfilling.

1.2 REFERENCES

- .1 Canadian Standards Association, (CSA)
- .2 Insulated Cable Engineers Association, Inc. (ICEA)

PART 2 **PRODUCTS**

2.1 CABLE PROTECTION

- .1 38 x 140 mm planks pressure treated with copper naphthenate or 5% pentachlorophenol solution, water repellent preservative.

2.2 MARKERS

- .1 Concrete type cable markers: 600 x 600 x 100 mm with words: cable, joint or conduit impressed in top surface, with arrows to indicate change in direction of cable and duct runs.
- .2 Wooden post type markers: 89 x 89 mm, 1.5 m long, pressure treated with copper naphthenate or 5% pentachlorophenol solution, water repellent preservative, with nameplate fastened near post top, on side facing cable or conduit to indicate depth and direction of duct and cable runs.

Emergency Generator Systems for
Search and Rescue Station Located
In Port Au Choix, NL

Page 2
2020-03-30

-
- .1 Nameplate: aluminum anodized 89 x 125 mm, 1.5 mm thick mounted on cedar post with mylar label 0.125 mm thick with words Cable, Joint or Conduit with arrows to indicate change in direction.

PART 3 EXECUTION

3.1 DIRECT BURIAL OF CABLES

- .1 After sand bed specified in Section 31 23 33.01 - Excavating, Trenching and Backfilling, is in place, lay cables maintaining 75 mm clearance from each side of trench to nearest cable. Do not pull cable into trench.
- .2 Provide offsets for thermal action and minor earth movements. Offset cables 150 mm for each 60 m run, maintaining minimum cable separation and bending radius requirements.
- .3 Make termination and splice only as indicated leaving 0.6 m of surplus cable in each direction.
- .1 Make splices and terminations in accordance with manufacturer's instructions using approved splicing kits.
- .4 Underground cable splices not acceptable.
- .5 Minimum permitted radius at cable bends for rubber, plastic or lead covered cables, 8 times diameter of cable; for metallic armoured cables, 12 times diameter of cables or in accordance with manufacturer's instructions.
- .6 Cable separation:
- .1 Maintain 75 mm minimum separation between cables of different circuits.
- .2 Maintain 300 mm horizontal separation between low and high voltage cables.
- .3 When low voltage cables cross high voltage cables maintain 300 mm vertical separation with low voltage cables in upper position.
- .4 At crossover, maintain 75 mm minimum vertical separation between low voltage cables and 150 mm between high voltage cables.

Emergency Generator Systems for
Search and Rescue Station Located
In Port Au Choix, NL

Page 3
2020-03-30

- .5 Maintain 300 mm minimum lateral and vertical separation for fire alarm and control cables when crossing other cables, with fire alarm and control cables in upper position.
 - .6 Install treated planks on lower cables 0.6 m in each direction at crossings.
 - .7 After sand protective cover specified in Section 31 23 33.01 - Excavating, Trenching and Backfilling, is in place, install continuous row of overlapping 38 x 140 mm pressure treated planks as indicated to cover length of run.
- 3.2 CABLE INSTALLATION IN DUCTS
- .1 Install cables as indicated in ducts.
 - .1 Do not pull spliced cables inside ducts.
 - .2 Install multiple cables in duct simultaneously.
 - .3 Use CSA approved lubricants of type compatible with cable jacket to reduce pulling tension.
 - .4 To facilitate matching of colour coded multiconductor control cables reel off in same direction during installation.
 - .5 Before pulling cable into ducts and until cables are properly terminated, seal ends of lead covered cables with wiping solder; seal ends of non-leaded cables with moisture seal tape.
 - .6 After installation of cables, seal duct ends with duct sealing compound.
- 3.3 MARKERS
- .1 Mark cable every 150 m along cable runs and changes in direction.
 - .2 Mark underground splices.
 - .3 Where markers are removed to permit installation of additional cables, reinstall existing markers.
 - .4 Install wooden post type markers.

Emergency Generator Systems for
Search and Rescue Station Located
In Port Au Choix, NL

Page 4
2020-03-30

- .5 Lay concrete markers flat and centred over cable with top flush with finish grade.

3.4 FIELD QUALITY CONTROL

- .1 Perform tests in accordance with Section 26 05 00 - Common Work Results - Electrical and Section 01 91 13 - Commissioning (Cx) Requirements.
- .2 Perform tests using qualified personnel. Provide necessary instruments and equipment.
- .3 Check phase rotation and identify each phase conductor of each feeder.
- .4 Check each feeder for continuity, short circuits and grounds. Ensure resistance to ground of circuits is not less than 50 megohms.
- .5 Pre-acceptance tests.
 - .1 After installing cable but before splicing and terminating, perform insulation resistance test with 1000 V megger on each phase conductor.
 - .2 Check insulation resistance after each splice and/or termination to ensure that cable system is ready for acceptance testing.
- .6 Acceptance Tests
 - .1 Ensure that terminations and accessory equipment are disconnected.
 - .2 Ground shields, ground wires, metallic armour and conductors not under test.
 - .3 High Potential (Hipot) Testing.
 - .1 Conduct hipot testing at 100 % of original factory test voltage in accordance with manufacturer's recommendations.
 - .4 Leakage Current Testing.
 - .1 Raise voltage in steps from zero to maximum values as specified by manufacturer for type of cable being tested.
 - .2 Hold maximum voltage for time period, specified by manufacturer.

Emergency Generator Systems for
Search and Rescue Station Located
In Port Au Choix, NL

Page 5
2020-03-30

- .3 Record leakage current at each step.
- .7 Provide Departmental Representative with list of test results showing location at which each test was made, circuit tested and result of each test. Include results in Commissioning Manual.
- .8 Remove and replace entire length of cable if cable fails to meet any of test criteria.

END OF SECTION

Emergency Generator Systems for
Search and Rescue Station Located
In Port Au Choix, NL

Page 1
2020-03-30

1.1 General

1.2 SECTION INCLUDES

- .1 Service equipment and installation.

1.3 RELATED SECTIONS

- .1 Section 26 05 28 - Grounding - Secondary.
- .2 Section 26 05 31 - Splitters, Junction, Pull Boxes and Cabinets.
- .3 Section 26 24 16.01 - Panelboards Breaker Type.
- .4 Section 26 28 16.02 - Moulded Case Circuit Breakers.
- .5 Section 26 28 23 - Disconnect Switches - Fused and Non-Fused.

PART 2 PRODUCTS

2.1 EQUIPMENT

- .1 Fused disconnect switch: in accordance with Section 26 28 23 - Disconnect Switches - Fused and Non-Fused, rating as indicated.
- .2 Enclosed circuit breaker: in accordance with Section 26 28 16.02 - Moulded Case Circuit Breakers, rating as indicated.
- .3 Panelboard breaker type: in accordance with Section 26 24 16.01 - Panelboards Breaker Type.
- .4 Cabinet type 'A' for utility revenue metering, Junction box, Pull box and Splitter box: in accordance with Section 26 05 31 - Splitters, Junction, Pull Boxes and Cabinets, size as indicated.

Emergency Generator Systems for
Search and Rescue Station Located
In Port Au Choix, NL

Page 2
2020-03-30

PART 3 EXECUTION

3.1 INSTALLATION

- .1 Install service equipment.
- .2 Connect to incoming service.
- .3 Connect to outgoing load circuits.
- .4 Install ground fault equipment.
- .5 Make grounding connections in accordance with Section 26
05 28 - Grounding - Secondary.
- .6 Make provision for power supply authority's metering.

END OF SECTION

Emergency Generator Systems for
Search and Rescue Station Located
In Port Au Choix, NL

Page 1
2020-03-30

PART 1 GENERAL

1.1 SECTION INCLUDES

- .1 Materials and installation for standard and custom breaker type panelboards.

1.2 RELATED SECTIONS

- .1 Section 01 33 00 - Submittal Procedures.
- .2 Section 01 91 13 - General Commissioning (Cx) Requirements.
- .3 Section 26 05 00 - Common Work Results for Electrical.
- .4 Section 26 28 16.02 - Moulded Case Circuit Breakers.

1.3 REFERENCES

- .1 Canadian Standards Association (CSA)
 - .1 CSA C22.2 No.29, Panelboards and enclosed Panelboards.

1.4 SUBMITTALS

- .1 Drawings to include electrical detail of panel, branch breaker type, quantity, ampacity and enclosure dimension.

PART 2 PRODUCTS

2.1 PANELBOARDS

- .1 Panelboards: to CSA C22.2 No.29 and product of one manufacturer.
 - .1 Install circuit breakers in panelboards before shipment.
 - .2 In addition to CSA requirements manufacturer's nameplate must show fault current that panel including breakers has been built to withstand.

Emergency Generator Systems for
Search and Rescue Station Located
In Port Au Choix, NL

Page 2
2020-03-30

-
- .2 250 and 600 V panelboards: bus and breakers rated for 10,000 and 18,000 A (symmetrical) minimum interrupting capacity respectively or as indicated on electrical drawings.
 - .3 Sequence phase bussing with odd numbered breakers on left and even on right, with each breaker identified by permanent number identification as to circuit number and phase.
 - .4 Panelboards: mains, number of circuits, and number and size of branch circuit breakers as indicated.
 - .5 Two keys for each panelboard and key panelboards alike.
 - .6 Tin plated aluminum bus with neutral of same ampere rating as mains.
 - .7 Mains: suitable for bolt-on breakers.
 - .8 Trim with concealed front bolts and hinges.
 - .9 Trim and door finish: baked grey enamel.
- 2.2 CUSTOM BUILT PANELBOARD ASSEMBLIES
- .1 125 mm relay section on one or both sides of panels as indicated for installation of low voltage remote control switching components.
 - .2 Double stack panels as indicated.
 - .3 Contactors in mains as indicated.
 - .4 Feed through lugs as indicated.
- 2.3 BREAKERS
- .1 Breakers: to Section 26 28 16.02 - Moulded Case Circuit Breakers.
 - .2 Breakers with thermal and magnetic tripping in panelboards except as indicated otherwise.
 - .3 Main breaker: separately mounted on top or bottom of panel to suit cable entry. When mounted vertically, down position should open breaker.

Emergency Generator Systems for
Search and Rescue Station Located
In Port Au Choix, NL

Page 3
2020-03-30

- .4 Lock-on devices for 10% of 15 to 30 A breakers installed as indicated. Turn over unused lock-on devices to Departmental Representative.
- .5 Lock-on devices for receptacles, fire alarm, clock outlet, emergency, door supervisory, intercom, stairway, exit and night light circuits as indicated.

2.4 EQUIPMENT IDENTIFICATION

- .1 Provide equipment identification in accordance with Section 26 05 00 - Common Work Results - Electrical.
- .2 Nameplate for each panelboard size 4 engraved as indicated.
- .3 Nameplate for each circuit in distribution panelboards size 2 engraved as indicated.
- .4 Complete circuit directory with typewritten legend showing location and load of each circuit.

PART 3 EXECUTION

3.1 INSTALLATION

- .1 Locate panelboards as indicated and mount securely, plumb, true and square, to adjoining surfaces.
- .2 Install surface mounted panelboards on plywood backboards. Where practical, group panelboards on common backboard.
- .3 Mount panelboards to height specified in Section 26 05 00 - Common Work Results for Electrical or as indicated.
- .4 Connect loads to circuits.
- .5 Connect neutral conductors to common neutral bus with respective neutral identified.

END OF SECTION

Emergency Generator Systems for
Search and Rescue Station Located
In Port Au Choix, NL

Page 1
2020-03-30

PART 1 GENERAL

1.1 SECTION INCLUDES

- .1 Switches, receptacles, wiring devices, cover plates and their installation.

1.2 RELATED SECTIONS

- .1 Section 01 33 00 - Submittal Procedures.
- .2 Section 01 91 13 - General Commissioning (Cx) Requirements.
- .3 Section 26 05 00 - Common Work Results for Electrical.

1.3 REFERENCES

- .1 Canadian Standards Association (CSA)
 - .1 CSA-C22.2 No.42, General Use Receptacles, Attachment Plugs and Similar Devices.
 - .2 CSA-C22.2 No.42.1, Cover Plates for Flush-Mounted Wiring Devices (Bi-national standard, with UL 514D).
 - .3 CSA-C22.2 No.55, Special Use Switches.
 - .4 CSA-C22.2 No.111, General-Use Snap Switches (Bi-national standard, with UL 20, twelfth edition).

PART 2 PRODUCTS

2.1 RECEPTACLES

- .1 As noted on drawings.

2.2 COVER PLATES

- .1 As noted on drawings.

PART 3 EXECUTION

3.1 INSTALLATION

- .1 Receptacles:

Emergency Generator Systems for
Search and Rescue Station Located
In Port Au Choix, NL

Page 2
2020-03-30

.1 Install receptacles as per details.

END OF SECTION

Emergency Generator Systems for
Search and Rescue Station Located
In Port Au Choix, NL

Page 1
2020-03-30

PART 1 GENERAL

1.1 RELATED SECTIONS

- .1 Section 01 78 00 - Closeout Submittals.
- .2 Section 01 91 13 - General Commissioning (Cx) Requirements.
- .3 Section 26 05 00 - Common Work Results for Electrical.

1.2 REFERENCES

- .1 Canadian Standards Association (CSA)
 - .1 CSA C22.2No.248.12, Low Voltage Fuses Part 12: Class R (Bi-National Standard with, UL 248-12 (1st Edition)).

1.3 SUBMITTALS

- .1 Submit fuse performance data characteristics for each fuse type and size above 600 A. Performance data to include: average melting time-current characteristics.

1.4 DELIVERY AND STORAGE

- .1 Ship fuses in original containers.
- .2 Do not ship fuses installed in switchboard.
- .3 Store fuses in original containers in storage cabinet moisture free location.

1.5 MAINTENANCE MATERIALS

- .1 Provide maintenance materials in accordance with Section 01 78 00 - Closeout Submittals.
- .2 Three spare fuses of each type and size installed above 600 A.
- .3 Six spare fuses of each type and size installed up to and including 600 A.

Emergency Generator Systems for
Search and Rescue Station Located
In Port Au Choix, NL

Page 2
2020-03-30

PART 2 PRODUCTS

2.1 FUSES GENERAL

- .1 Fuse type references L1, L2, J1, R1, etc. have been adopted for use in this specification.
- .2 Fuses: product of one manufacturer for entire project.

2.2 FUSE TYPES

- .1 Class L fuses (formerly HRC-L).
 - .1 Type L1, time delay, capable of carrying 500% of its rated current for 10 s minimum.
 - .2 Type L2, fast acting.
- .2 Class J fuses (formerly HRCI- J).
 - .1 Type J1, time delay, capable of carrying 500% of its rated current for 10 s minimum.
 - .2 Type J2, fast acting.
- .3 Class R -R fuses (formerly HRCI- R). For UL Class RK1 fuses, peak let-through current and its' peak let-through values not to exceed limits of UL 198E-1982, table 10.2.
 - .1 Type R1, (UL Class RK1), time delay, capable of carrying 500% of its rated current for 10 s minimum, to meet UL Class RK1 maximum let-through limits.
 - .2 Type R2, time delay, capable of carrying 500% of its rated current for 10 s minimum.
 - .3 Type R3, (UL Class RK1), fast acting Class R, to meet UL Class RK1 maximum let-through limits.
- .4 Class -C fuses (formerly HRCII- C).

2.3 FUSE STORAGE CABINET

- .1 Fuse storage cabinet, manufactured from 2.0 mm thick aluminum 750 mm high, 600 mm wide, 300 mm deep, hinged, lockable front access door finished in accordance with Section 26 05 00 - Common Work Results - Electrical.

Emergency Generator Systems for
Search and Rescue Station Located
In Port Au Choix, NL

Page 3
2020-03-30

PART 3 EXECUTION

3.1 INSTALLATION

- .1 Install fuses in mounting devices immediately before energizing circuit. Ensure correct fuses fitted to physically matched mounting devices.
 - .1 Install Class R rejection clips for HRCI-R fuses.
- .2 Ensure correct fuses fitted to assigned electrical circuit.
- .3 Where UL Class RK1 fuses are specified, install warning label "Use only UL Class RK1 fuses for replacement" on equipment.
- .4 Install spare fuses in fuse storage cabinet.

END OF SECTION

Emergency Generator Systems for
Search and Rescue Station Located
In Port Au Choix, NL

Page 1
2020-03-30

PART 1 GENERAL

1.1 RELATED SECTIONS

- .1 Section 01 33 00 - Submittal Procedures.
- .2 Section 01 91 13 - General Commissioning (Cx) Requirements.
- .3 Section 26 05 00 - Common Work Results for Electrical.

1.2 SUBMITTALS

- .1 Include time-current characteristic curves for breakers with ampacity of 600 A and over or with interrupting capacity of 22,000 A symmetrical (rms) and over at system voltage.

PART 2 PRODUCTS

2.1 BREAKERS GENERAL

- .1 Bolt-on moulded case circuit breaker: quick- make, quick-break type, for manual and automatic operation with temperature compensation for 40°C ambient.
- .2 Common-trip breakers: with single handle for multi-pole applications.
- .3 Magnetic instantaneous trip elements in circuit breakers to operate only when value of current reaches setting. Trip settings on breakers with adjustable trips to range from 3-8 times current rating.
- .4 Circuit breakers with interchangeable trips as indicated.
- .5 Circuit breakers to have minimum of 10,000 A symmetrical rms interrupting capacity rating.

Emergency Generator Systems for
Search and Rescue Station Located
In Port Au Choix, NL

Page 2
2020-03-30

2.2 THERMAL MAGNETIC BREAKERS DESIGN A

- .1 Moulded case circuit breaker to operate automatically by means of thermal and magnetic tripping devices to provide inverse time current tripping and instantaneous tripping for short circuit protection.

2.3 OPTIONAL FEATURES

- .1 Include:
 - .1 shunt trip.
 - .2 on-off locking device.
 - .3 handle mechanism.

2.4 ENCLOSURE

- .1 Mounted in NEMA 1 type enclosure, sprinkler proof as indicated.

PART 3 EXECUTION

3.1 INSTALLATION

- .1 Install circuit breakers as indicated.

END OF SECTION

Emergency Generator Systems for
Search and Rescue Station Located
In Port Au Choix, NL

Page 1
2020-03-30

PART 1 GENERAL

1.1 RELATED SECTIONS

- .1 Section 01 33 00 - Submittal Procedures.
- .2 Section 01 91 13 - General Commissioning (Cx) Requirements.
- .3 Section 26 05 00 - Common Work Results for Electrical.

PART 2 PRODUCTS

2.1 DISCONNECT SWITCHES

- .1 Fusible and non-fusible, disconnect switch in CSA Enclosure type 1, size as indicated.
- .2 Provision for padlocking in on-off switch position by three locks.
- .3 Mechanically interlocked door to prevent opening when handle in ON position.
- .4 Fuses: size as indicated, to Section 26 28 13.01 - Fuses - Low Voltage.
- .5 Fuseholders: suitable without adaptors, for type and size of fuse indicated.
- .6 Quick-make, quick-break action.
- .7 ON-OFF switch position indication on switch enclosure cover.

2.2 EQUIPMENT IDENTIFICATION

- .1 Provide equipment identification in accordance with Section 26 05 00 - Common Work Results - Electrical.
- .2 Indicate name of load controlled on size 4 nameplate.

Emergency Generator Systems for
Search and Rescue Station Located
In Port Au Choix, NL

Page 2
2020-03-30

PART 3 EXECUTION

3.1 INSTALLATION

- .1 Install disconnect switches complete with fuses as indicated.

END OF SECTION

Emergency Generator Systems for
Search and Rescue Station Located
In Port Au Choix, NL

Page 1
2020-03-30

PART 1 **GENERAL**

1.1 SCOPE OF WORK

- .1 Testing and commissioning are called for throughout the individual specifications. This does not relieve this trade from providing all testing and commissioning necessary to ensure that systems and equipment operate as required and that they interface with other systems and equipment as required.

1.2 SECTION INCLUDES

- .1 Commissioning of all building electrical systems and component including:
 - .1 Testing and adjustment.
 - .2 Demonstrations and Training.
 - .3 Instructions of all procedures for personnel.
 - .4 Updating as-built data.
 - .5 Co-ordination of Operation and Maintenance material.

1.3 RELATED SECTION

- .1 Section 01 77 00 - Closeout Procedures.
- .2 Section 01 91 13 - General Commissioning (Cx) Requirements.
- .3 Section 26 05 00 - Common Work Results for Electrical.

1.4 REFERENCES

- .1 CSA (Canadian Standards Association).
- .2 Underwriters Laboratories of Canada.

1.5 QUALITY ASSURANCE

- .1 Provide qualified trades persons, certified testing agencies, factory trained and approved by the Commissioning Team Leader.

Emergency Generator Systems for
Search and Rescue Station Located
In Port Au Choix, NL

Page 2
2020-03-30

- .2 Submit the names of all personnel to be used during the Commissioning activities for Departmental Representative's Approval.

1.6 COMMISSIONING

- .1 The purpose of the commissioning process is to fully test all new building systems including architectural, mechanical and electrical components and operating procedures by challenging these systems to realistic operation conditions.
- .2 The Commissioning activities shall be coordinated by the General Contractor.
- .3 Commissioning activities for the electrical systems must have available up to date as-built drawing information and accurate Operations and Maintenance Manuals. These documents shall be a major part of this activity.
- .4 Contractor shall be responsible to update all documentation with information and any changes duly noted during the Commissioning exercise.
- .5 Contractor shall arrange for all outside suppliers, equipment manufacturers, test agencies and others as identified in the commissioning sections of this specification. The cost associated with this requirement shall be included as part of the tender price.

1.7 SUBMITTALS

- .1 A commissioning document shall be prepared by the Departmental Representative prior to conducting these activities for use by the Commissioning Team.
- .2 The electrical sub-contractor shall be responsible for ensuring all activities are properly documented in this manual and coordinated through the General Contractor.
- .3 As-built drawings and data books must be available two weeks prior to commissioning for review and use by the consultant and Commissioning Team prior to the start of the commissioning activities.

Emergency Generator Systems for
Search and Rescue Station Located
In Port Au Choix, NL

Page 3
2020-03-30

1.8 PREPARATION

- .1 Provide test instruments required for all activities as defined in the commissioning documents.
- .2 Verify all systems are in compliance with the requirements of the commissioning documents prior to the pre-commissioning check out operation.
- .3 Confirm all scheduled activities have identified personnel available.
- .4 Where systems or equipment do not operate as required, make the necessary corrections or modifications, re-test and re-commission.

1.9 SYSTEM DESCRIPTION

- .1 Perform all start up operations, control adjustment, trouble shooting, servicing and maintenance of each item of equipment as defined in the commissioning documentation.
- .2 DFO will provide list of personnel to receive instructions and will co-ordinate their attendance at agreed upon times.
- .3 Prepare and insert additional data in the operations and maintenance manuals and update as-built drawings when need for additional data becomes apparent during the commissioning exercise.
- .4 Where instruction is specified in the commissioning manual, instruct personnel in all phases of operation and maintenance using operation and maintenance manuals as the basis of instruction.
- .5 Conduct presentation on DFOs' premises. DFO will provide space.

1.10 FINAL REPORT

- .1 This trade shall assemble all testing data and commissioning reports and submit them to the Departmental Representative.
- .2 Each form shall bear signature of recorder, and that of supervisor of reporting organizer.

Emergency Generator Systems for
Search and Rescue Station Located
In Port Au Choix, NL

Page 4
2020-03-30

1.11 SCHEDULE OF ACTIVITIES

- .1 Commissioning activities shall be conducted based on pre-established schedule with all members of the commissioning team, refer to Section 01 91 13 - General Commissioning (Cx) Requirements.
- .2 In addition, there will be two meetings held through the contract duration to introduce the parties of the commissioning team, establish the schedules and deadlines for the various activities and review the Commissioning Manual.
- .3 Adhering to the established schedule is very important as the co-ordination and scheduling of the participants will be difficult to alter once this is established. Close co-ordination of this schedule is important.
- .4 In the event project cannot be commissioned in the allotted time slot, the contractor shall pay for all costs associated with assembling the Commissioning Team at a later date. If the contractor has not performed his duties to reach commissioning stage as outlined earlier, he will incur all expenses of other trades and the Commissioning Team due to his non-compliance.

END OF SECTION

Emergency Generator Systems for
Search and Rescue Station Located
In Port Au Choix, NL

Page 1
2020-03-30

1.1 GENERAL

1.2 GENERAL

- .1 This section describes the extent of services to be provided for wiring of equipment supplied by others.
- .2 Within the context of this section, Others means:
 - .1 The Owner, as defined in the Contract.
 - .2 Other contractors supplying and installing equipment to the contract.

1.3 EXTENT OF SERVICES PROVIDED

- .1 The work of this contract is to include all power and control wiring of equipment which is provided by Division 26.
- .2 All power and control wiring will be the responsibility of this contractor. Coordinate with owners and other trades for exact requirements.

1.4 RESPONSIBILITY OF DIVISION 26

- .1 It is the responsibility of the Division 26 subcontractor to verify final requirements for wiring of all equipment noted. Verification of wiring requirements to include:
 - .1 Confirmation of electrical characteristics.
 - .2 Location of connection point.
 - .3 Method of connection (i.e. direct or plug-in etc.)
- .2 Obtain and become familiar with shop drawings for all relevant equipment.
- .3 No claim for extra will be entertained for wiring equipment which has been indicated, or changes to installed wiring where installation proceeded prior to verification of electrical requirements.

Emergency Generator Systems for
Search and Rescue Station Located
In Port Au Choix, NL

Page 2
2020-03-30

PART 2 PRODUCTS (NOT APPLICABLE)

PART 3 EXECUTION (NOT APPLICABLE)

END OF SECTION

PART 1 GENERAL

1.1 REFERENCES

- .1 American Society for Testing and Materials (ASTM).
 - .1 ASTM C117, Standard Test Method for Material Finer Than 0.075 mm (No. 200) Sieve in Mineral Aggregates by Washing.
 - .2 ASTM C136, Standard Test Method for Sieve Analysis of Fine and Coarse Aggregates.
 - .3 ASTM D422, Standard Test Method for Particle-Size Analysis of Soils.
 - .4 ASTM D698, Standard Test Method for Laboratory Compaction Characteristics of Soil Using Standard Effort (12,400 ft-lbf/ft³) (600 kN-m/m³).
 - .5 ASTM D1557, Test Method for Laboratory Compaction Characteristics of Soil Using Modified Effort (56,000 ft-lbf/ft³) (2,700 kN-m/m³).
 - .6 ASTM D4318, Standard Test Methods for Liquid Limit, Plastic Limit, and Plasticity Index of Soils.
- .2 Canadian General Standards Board (CGSB).
 - .1 CAN/CGSB-8.1, Sieves, Testing, Woven Wire, Inch Series.
 - .2 CA/CGSB-8.2, Sieves, Testing, Woven Wire, Metric
- .3 Canadian Standards Association (CSA)
 - .1 CAN/CSA-A3000, Cementitious Materials Compendium (Consists of A3001, A3002, A3003, A3004 and A3005).
 - .1 CSA-A3001, Cementitious Materials for Use in Concrete.
 - .2 CSA-A23.1/A23.2, Concrete Materials and Methods of Concrete Construction/ Methods of Test and Standard Practices for Concrete.

1.2 DEFINITIONS

- .1 Excavation types (no distinction as this is a lump sum project):

- .1 Rock excavation: excavation of material from solid masses of igneous, sedimentary or metamorphic rock which, prior to its removal, was integral with its parent mass, and boulders or rock fragments having individual volume in excess of 1 m³. Frozen material not classified as rock.
- .2 Common excavation: excavation of materials of whatever nature, which are not included under definitions of rock excavation.
- .2 Unclassified excavation: excavation of deposits of whatever character encountered in work.
- .3 Topsoil: material capable of supporting good vegetative growth and suitable for use in top dressing, landscaping and seeding.
- .4 Waste material: excavated material unsuitable for use in work or surplus to requirements.
- .5 Borrow material: material obtained from locations outside area to be graded, and required for construction of fill areas or for other portions of work.
- .6 Unsuitable materials:
 - .1 Weak and compressible materials under excavated areas.
 - .2 Frost susceptible materials under excavated areas.
 - .3 Frost susceptible materials:
 - .1 Fine grained soils with plasticity index less than 10 when tested to ASTM D4318, and gradation within limits specified when tested to ASTM D422 and ASTM C136: Sieve sizes to CAN/CGSB-8.1.

<u>Sieve Designation</u>	<u>%Passing</u>
2.00 mm	100
0.10 mm	45-100
0.02 mm	10-80
<u>0.005 mm</u>	<u>0-45</u>

- .2 Coarse grained soils containing more than 20% by mass passing 0.075 mm sieve.

1.3 EXISTING CONDITIONS

.1 Buried services:

- .1 Before commencing work verify location of buried services on and adjacent to site.
- .2 Prior to commencing excavation work, notify applicable Owner or authorities having jurisdiction, establish location and state of use of buried utilities and structures. Owners or authorities having jurisdiction to clearly mark such locations to prevent disturbance during work.
- .3 Confirm locations of buried utilities by careful test excavations.
- .4 Maintain and protect from damage, water, sewer, electric, telephone and other utilities and structures encountered as indicated.
- .5 Where utility lines or structures exist in area of excavation, obtain direction of Owner's Representative before removing or re-routing.
- .6 Record location of maintained, re-routed and abandoned underground lines.
- .7 Confirm locations of recent excavations adjacent to area of excavation.

.2 Existing buildings and surface features:

- .1 Conduct, with Owner's Representative condition survey of existing buildings, trees and other plants, lawns, fencing, service poles, wires, rail tracks, pavement, survey bench marks and monuments which may be affected by work.
- .2 Protect existing buildings and surface features from damage while work is in progress. In event of damage, immediately make repair to approval of Owner's Representative.
- .3 Where required for excavation, cut roots or branches as approved by Owner's Representative.

PART 2 PRODUCTS

2.1 MATERIALS

- .1 Backfill Type 1 (Class A) and Type 2 fill:

- .1 Crushed, pit run or screened stone, gravel or sand.
- .2 Gradations to be within limits specified when tested to ASTM C136 and ASTM C117. Sieve sizes to CAN/CGSB-8.1.

Sieve Designation	%Passing	
	<u>Type1</u>	<u>Type2</u>
75 mm	-	100
50 mm	-	-
37.5 mm	-	-
25 mm	100	-
19 mm	75-100	-
12.5 mm	-	-
9.5 mm	50-100	-
4.75 mm	30-70	22-85
2.00 mm	20-45	-
0.425 mm	10-25	5-30
0.180 mm	-	-
<u>0.075 mm</u>	<u>3-8</u>	<u>0-10</u>

- .2 Type 3 fill: selected material from excavation or other sources, approved by Owner's Representative for use intended, unfrozen and free from rocks larger than 75 mm, cinders, ashes, sods, refuse or other deleterious materials.

PART 3 EXECUTION

3.1 SITE PREPARATION

- .1 Remove obstructions, ice and snow, from surfaces to be excavated within limits indicated.

3.2 PREPARATION/PROTECTION

- .1 Protect existing features in accordance with applicable local regulations.
- .2 Keep excavations clean, free of standing water, and loose soil.
- .3 Where soil is subject to significant volume change due to change in moisture content, cover and protect to Owner's Representative's approval.

- .4 Protect natural and man-made features required to remain undisturbed. Unless otherwise indicated or located in an area to be occupied by new construction, protect existing trees from damage. Protect buried services that are required to remain undisturbed.

3.3 SHORING, BRACING AND UNDERPINNING

- .1 Maintain sides and slopes of excavations in safe condition by appropriate methods and in accordance with Occupational Health and Safety Act for the Province of Newfoundland and Labrador.
- .2 Obtain permit from authority having jurisdiction.
- .3 Construct temporary works to depths, heights and locations as required.
- .4 During backfill operation:
 - .1 Remove sheeting and shoring from excavations.
 - .2 Do not remove bracing until backfilling has reached respective levels of such bracing.
- .5 Upon completion of substructure construction remove excess materials from site and restore as indicated.

3.4 DEWATERING AND HEAVE PREVENTION

- .1 Keep excavations free of water while work is in progress.
- .2 Submit for Owner's Representative's review details of proposed dewatering or heave prevention methods.
- .3 Avoid excavation below groundwater table if quick condition or heave is likely to occur.
- .4 Protect open excavations against flooding and damage due to surface run-off.
- .5 Dispose of water in accordance with Section 01 35 43 - Environmental Procedures and in manner not detrimental to public and private property, or any portion of work completed or under construction.

3.5 EXCAVATION

- .1 Excavation must not interfere with bearing capacity of adjacent foundations.
- .2 Keep excavated and stockpiled materials a safe distance away from edge of trench as directed by Owner's Representative.
- .3 Restrict vehicle operations directly adjacent to open trenches.
- .4 Dispose of surplus and unsuitable excavated material off site.
- .5 Do not obstruct flow of surface drainage or natural watercourses.
- .6 Earth bottoms of excavations to be undisturbed soil, level, free from loose, soft or organic matter.
- .7 Notify Owner's Representative when bottom of excavation is reached.
- .8 Obtain Owner's Representative approval of completed excavation.
- .9 Remove unsuitable material from trench bottom to extent and depth as directed by Owner's Representative.
- .10 Correct unauthorized over-excavation as follows:
 - .1 Fill under bearing surfaces and footings with concrete specified for footings.
 - .2 Fill under other areas with Type 2 fill compacted to not less than 95% of corrected maximum dry density.
- .11 Hand trim, make firm and remove loose material and debris from excavations. Where material at bottom of excavation is disturbed, compact foundation soil to density at least equal to undisturbed soil.

3.6 FILL TYPES AND COMPACTION

- .1 Use fill of types as indicated or specified below. Compaction densities are percentages of maximum

densities obtained from ASTM D698 corrected maximum dry density.

- .1 Use Type 3 fill to subgrade level. Compact to 95%.
- .2 Type 2 to underside of Class A topping. Class A topping to surface (topped with asphalt where applicable).
- .3 To correct over excavation in trenches: use Type 2 fill to underside of sand bedding compacted to 95%.

3.7 BEDDING AND SURROUND OF UNDERGROUND SERVICES

- .1 Place and compact granular material for bedding and surround of underground services as indicated.
- .2 Place bedding and surround material in unfrozen condition.

3.8 BACKFILLING

- .1 Vibratory compaction equipment: approved by Owner's Representative.
- .2 Do not proceed with backfilling operations until Owner's Representative has inspected and approved installations.
- .3 Areas to be backfilled to be free from debris, snow, ice, water and frozen ground.
- .4 Do not use backfill material which is frozen or contains ice, snow or debris.
- .5 Place backfill material in uniform layers not exceeding 150 mm compacted thickness up to grades indicated. Compact each layer before placing succeeding layer.
- .6 Backfill around installations.
 - .1 Place bedding and surround material as specified elsewhere.
 - .2 Do not backfill around or over cast-in-place concrete within 24 hours after placing of concrete.

- .3 Place layers simultaneously on both sides of installed work to equalize loading. Difference not to exceed 600 mm.

3.9 RESTORATION

- .1 Upon completion of work, remove waste materials and debris, trim slopes, and correct defects as directed by Owner's Representative.
- .2 Clean and reinstate areas affected by work as directed by Owner's Representative.

END OF SECTION

Emergency Generator Systems for
Search and Rescue Station Located
In Port Au Choix, NL

Page 1
2020-03-30

PART 1 - GENERAL

1.1 DESCRIPTION

- .1 This section specifies requirements for supply and installation of treated timber and necessary fastenings for fabrication, placing, and ballasting of timber cribwork.

1.2 SAFETY
REQUIREMENTS

- .1 Worker protection:
 - .1 Workers must wear gloves, respirators, dust masks, long sleeved clothing, eye protection, protective clothing when handling, drilling, sawing, cutting or sanding preservative treated wood and applying preservative materials.
 - .2 Workers must not eat, drink or smoke while applying preservative material.
 - .3 Clean up spills of preservative materials immediately with absorbent material. Safely discard of absorbent material to sanitary landfill.

1.3 REFERENCES

- .1 American Society for Testing and Materials (ASTM International)
 - .1 ASTM A307-07b, Specification for Carbon Steel Bolts and Studs, 60,000 PSI Tensile.
 - .2 ASTM C136-06, Standard Test Method for Sieve Analysis of Fine and Coarse Aggregates.
- .2 American Wood-Preserver's Association (AWPA)
 - .1 AWP A M4-06, Standard for the Care of Preservation - Treated Wood Products.
- .3 Canadian Standards Association (CSA International)

Emergency Generator Systems for
Search and Rescue Station Located
In Port Au Choix, NL

Page 2
2020-03-30

- .1 CSA B111-1974(R2003), Wire Nails, Spikes and Staples.
- .2 CAN/CSA-G40.21-04, General Requirements for Rolled or Welded Structural Quality Steel/Structural Steel.
- .3 CAN/CSA G164-M92(R2003), Hot Dip Galvanizing of Irregularly Shaped Articles.
- .4 CAN/CSA-O80 Series-97 (R2007), Wood Preservation.

- .4 Canadian Wood Council
 - .1 Wood Design Manual.
- .5 National Lumber Grades Authority (NLGA)
 - .1 Standard Grading Rules for Canadian Lumber 2000 edition.

1.4 SUBMITTALS

- .1 Ballast:
 - .1 Submit proposed placing method to Departmental Representative for approval, prior to placing of concrete ballast.

PART 2 - PRODUCTS

2.1 MATERIALS

- .1 Timber: Use timber graded and stamped in accordance with applicable grading rules and standards of associations or agencies approved to grade lumber by Canadian Lumber Standards Accreditation Board of CSA.
- .2 Species: Douglas Fir, Pacific Coast Hemlock and Eastern Hemlock.
- .3 Grade: No. 1 Structural.
- .4 Grading authority: NLGA.

Emergency Generator Systems for
Search and Rescue Station Located
In Port Au Choix, NL

Page 3
2020-03-30

- .5 Preservative treatment: To CSA O80 for coastal waters. Supply timbers in lengths required. Cut and field treat timbers only as may be necessary to suit site conditions. Contractor will have on site sufficient lengths and thickness of treated timber to permit leveling of cribs after ballasting operations.
- .6 Miscellaneous steel: Medium structural steel conforming to CSA Specification G40.21 "Structural Quality Steels".
 - .1 Hot dip galvanized: to CAN/CSA-G164. Minimum weight of zinc coating as stated in Table 1 of this Standard. Fabricator to adhere to recommendations in Appendix A and B of Standard.
 - .2 Wire nails, spikes, staples: to CSA-B111.
 - .3 Bolts, nuts, washers: to ASTM A307.
 - .4 Drift Bolts: to G40.21 from round stock, button head and diamond or wedge point.
 - .5 Washers:
 - .1 Round Plate Washers: for 19 mm diameter machine bolts, 79 mm diameter by 7.9 mm thick, with hole diameter of 21 mm. Washers to G40.21.
 - .2 Square washers not permitted to be used.
 - .6 All hardware galvanized.
- .7 Ballast for filling cribs: 35MPa Class C1 exposure concrete mix.

PART 3 - EXECUTION

3.1 PREPARATION

- .1 Seat cribs on hard bottom, as noted on drawings.

Emergency Generator Systems for
Search and Rescue Station Located
In Port Au Choix, NL

Page 4
2020-03-30

- .2 Contractor to confirm with Departmental Representative that bottom is adequate for cribwork placement.
- .3 Before construction, stockpile sufficient ballast to completely fill cribs. Provide suitable plant and equipment to keep crib in proper position and alignment during sinking operations.

3.2 CRIB CONSTRUCTION

- .1 Levelling Pieces:
 - .1 Place treated timber levelling pieces beneath bottom timbers to conform to shape of base area.
 - .2 Place levelling pieces horizontally.
 - .3 Secure succeeding pieces at intersections of bottom timbers and vertical posts, and other levelling pieces with machine bolts.
- .2 Bottom timbers:
 - .1 Place bottom timbers lengthwise, and crosswise to form bottom three courses of cribs.
 - .2 Crosswise bottom timbers to be of one piece.
 - .3 Lengthwise bottom timbers to be of one piece.
 - .4 Secure three courses of bottom timbers together with machine bolts at every intersection with each other and with vertical posts.
- .3 Ballast floor:
 - .1 Place ballast floor on pockets on bottom or middle course of bottom timbers.
 - .2 Secure each ballast floor timber to bottom timbers with drift bolts securing adjacent ballast floor timbers to same bottom timber.

Emergency Generator Systems for
Search and Rescue Station Located
In Port Au Choix, NL

Page 5
2020-03-30

- .4 Longitudinals:
 - .1 Longitudinals one length for individual cribs below LNT.
 - .2 Longitudinals minimum 6100 mm long above LNT.
 - .3 Where cribs are married together, longitudinals of sufficient length to span a minimum of a half a bay of one crib and one and a half bays of the adjacent crib.
 - .4 Butt join exterior and interior longitudinals a minimum distance of 600 mm from crosstie with joint in centre of a 1200 mm long joiner block.
 - .5 Secure block to lower timber with drift bolt at centre and secure longitudinals and splice at ends to block with drift bolts.
 - .6 Stagger joints in longitudinal timbers. Do not join in same bay or on same vertical post.
 - .7 Secure longitudinals to intersection of cross ties with drift bolt and to intersection of vertical posts with machine bolt every third course of longitudinals, along with the top course.
 - .8 Countersink machine bolts on exterior face above LNT.
- .5 Cross ties: one length across cribs.
 - .1 Secure cross ties to intersection of longitudinals with drift bolt and to intersection of vertical posts with machine bolt every third course of cross tie, along with the top course.
 - .2 One row of crossties and verticals may be eliminated from one crib where cribs marry together above +400 mm LNT.
- .6 Vertical posts: one length from bottom of cribwork to top of cribwork. Locate one vertical post at corner of each crib and at intersection of crossties with longitudinals.

Emergency Generator Systems for
Search and Rescue Station Located
In Port Au Choix, NL

Page 6
2020-03-30

- .7 Blocking: install treated timber filler blocking as indicated on drawings (cribs are solid blocked all around perimeter).
- .8 Levelling: treated timber required for levelling of cribwork after ballasting, must be full width continuous over entire length to be levelled.
- .9 Bolt Sizing and Holing:
 - .1 Drift Bolts: length of drift bolts equal to thickness of timbers fastened less 50 mm, unless otherwise specified. Bore holes for drift bolts 2 mm smaller diameter than bolt and for full length of bolt.
 - .2 Machine Bolts: length of machine bolts equal to thickness of timbers fastened plus thickness of washers plus 40 mm. Where bolts are countersunk, the length, as noted above, less depth of countersink. Thread machine bolts for 64 mm. Bore holes for machine bolts to same diameter as bolts.

3.3 HANDLING TREATED TIMBER

- .1 Handle treated material without damaging original treatment.
 - .1 Replace treated timber with major damage to original treatment, as instructed by Departmental Representative.
- .2 Field treatment: to CAN/CSA-080. Apply and saturate cuts, minor surface damage, abrasions, and nail and spike holes with preservative.
- .3 Ripping of treated timber not permitted without prior approval of Departmental Representative.

3.4 PROTECTION

- .1 Protect work from damage resulting from work on other sections and from damage

Emergency Generator Systems for
Search and Rescue Station Located
In Port Au Choix, NL

Page 7
2020-03-30

resulting from environmental conditions.

- .2 Repair or replace portion or entire crib
at no additional cost if damaged by work.