

**Basin Dredging****Pinkney's Point SCH****Yarmouth County, N.S.****R.112118.001**

Sitework, Demolition and Removals

Page 1

PART 1 - GENERAL

- |                                |  |
|--------------------------------|--|
| 1.1 <u>Description of Work</u> | This Section includes but is not limited to the following: <ul style="list-style-type: none"><li>.1 All normal removals as required to complete the work. All items to be verified by a site visit prior to submission of a tender. All available plans of the existing structures are available for viewing at the Project Manager's office, 1713 Bedford Row, Halifax, N.S.</li><li>.2 Any derricks, gas lines or buildings to be removed by others unless otherwise indicated.</li></ul>  |
| 1.2 <u>Related Work</u>        | <ul style="list-style-type: none"><li>.1 Refer to other specification sections for related information.</li><li>.2 Refer to <b>Section 01 33 00</b> for Shop Drawing/Submission requirements.</li></ul>  |
| 1.3 <u>Submissions</u>         | <ul style="list-style-type: none"><li>.1 Methodology:<ul style="list-style-type: none"><li>.1 When requested provide methodology for carrying out the work</li></ul></li><li>.2 Provide submission in accordance with <b>Section 01 33 00</b>.</li></ul>   |
| 1.4 <u>Protection</u>          | <ul style="list-style-type: none"><li>.1 Prevent movement, settlement or damage of adjacent structures. Provided bracing and shoring as required. In event of damage, immediately replace such items or make repairs to approval of <i>Departmental Representative</i> and at no additional cost to <i>Departmental Representative</i>.</li><li>.2 Prevent debris from going adrift and becoming a menace to navigation.</li><li>.3 All damage to existing structures, roadways, pipelines, electrical systems not specified for removal to be repaired at the</li></ul> |

**Basin Dredging****Pinkney's Point SCH****Yarmouth County, N.S.****R.112118.001**

## Sitework, Demolition and Removals

Page 2

---

Contractor's cost to the satisfaction of the  
*Departmental Representative.*

1.5 Measurement for  
Payment

- .1 Sitework, demolition and removals will be measured in accordance with **Section 01 29 00.**

PART 2 - PRODUCTS

Not applicable.

PART 3 - EXECUTION

3.1 Preparation

- .1 Inspect site and verify with *Departmental Representative* items designated for removal and items to be preserved.
- .2 Locate and protect utility lines. Preserve in operating condition active utilities traversing site.
- .3 Provide temporary power and lighting as shown on the plan or as required by the *Departmental Representative.*
- .4 Existing fill and vent pipes, oil waste tanks and underground storage tanks to be protected from any damages. All repairs to damages as a result of Contractor's operations to be at his cost and to the satisfaction of the *Departmental Representative.*

3.2 Removal

- .1 Remove items indicated.
- .2 Do not disturb adjacent structures designated to remain in place.
- .3 At end of each day's work, leave work in safe condition so no part is in danger of toppling or falling.

3.3 Disposal of  
Material

- .1 Disposal of materials not designated for salvage or re-use in work, will be the
-

**Basin Dredging****Pinkney's Point SCH****Yarmouth County, N.S.****R.112118.001**

## Sitework, Demolition and Removals

Page 3

---

contractor's responsibility, and must be disposed of off-site.

- .2 The material to be disposed is to be transported and disposed of in an environmentally acceptable manner to the satisfaction of the *Departmental Representative*, and in accordance with any local, Municipal, Provincial and Federal restrictions and regulations.

3.4 Restoration

- .1 Upon completion of work, remove debris, trim surfaces and leave work site clean.
- .2 Reinstate areas and existing works outside areas of demolition to conditions that existed prior to commencement of work. Match condition of adjacent, undisturbed areas.
-