



Centralized Ctrl Sys1

> Product information

3. Indoor unit

Sys.	Model name	Product image*1	Qty	Capacity(kW)		Sensible capacity(kW)		Power input (kW)	Current (A)	Air flow rate (m3/min)	External static pressure	
				Rated	Corrected	Rated	Corrected	Rated				
RIGHT WING	PEFY-P63VMA-E		1	Cooling	7.10	-	5.50	-	0.12	1.01	13.5 - 16.0 - 19.0	*3
				Heating	8.00	-			0.10	0.9		
				Conditions			Dimension(mm)			Net weight		
					D.B.(deg C)	W.B.(deg C)	Humidity(%)	H X W X D		(kg)		
				Cooling	23.0	16.3	50	250 x 1,100 x 732		32		
Heating	20.0	-	-									

Sys.	Model name	Product image*1	Qty	Capacity(kW)		Sensible capacity(kW)		Power input (kW)	Current (A)	Air flow rate (m3/min)	External static pressure	
				Rated	Corrected	Rated	Corrected	Rated				
RIGHT WING	PEFY-P80VMH-E-F		2	Cooling	9.00	-	3.45	-	0.16	0.67	9	*3
				Heating	8.50	-			0.16	0.67		
				Conditions			Dimension(mm)			Net weight		
					D.B.(deg C)	W.B.(deg C)	Humidity(%)	H X W X D		(kg)		
				Cooling	35.0	32.0	81	380 x 1,000 x 900		50		
Heating	0.0	0.0	100									

4. Branch/Header/Twinning kit


Sys.	Model name	Product image*1	Qty	Description
RIGHT WING	CMY-Y302S-G2		1	-
	CMY-Y202S-G2		1	-
	CMY-Y102LS-G2		3	-
	CMY-Y200VBK2		1	-

- GENERAL NOTES**
1. WORK TO FIGURED DIMENSIONS ONLY
 2. ALL DIMENSIONS IN MILLIMETER UNLESS OTHERWISE STATED
 3. CO-ORDINATE WITH ARCHITECTURAL DRAWINGS FOR EXACT LOCATIONS OF APPLIANCES
 4. ALL PIPES SIZES ARE INTERNAL DIAMETER
 5. ALL TAP OFF FROM RISER PIPES SHOULD GO WITH CONCEALED VALVES FOR CONTROL

REV	DATE	DESCRIPTION	APPROVAL

CLIENT

ARCHITECT

SERVICES ENGINEERS
 MFA Partnership Mechanical & Electrical Consulting Engineers 2nd Floor Plot 10B, Block 132 DCS Street, U3 Estate, Lekki Phase 1 (Ocean side), Lagos. Tel: 234-1-3429060 Email: admin@mfapartnership.com
CHECKED BY CA APPROVED BY CAA MADE BY ITN

JOB TITLE
CANADIAN HIGH COMMISSION, CHANCERY LAGOS NIGERIA AT 4, ANIFOWOSHE STREET, V/I LAGOS
DRAWING TITLE
VRF AIRCONDITIONING SYSTEM EQUIPMENT SCHEDULE - RIGHT WING
DRAWING NO. M374/M209
SCALE NTS
DATE SEPT., 2018
REV -

DRAWING PHASE
WORK IN PROGRESS
PRELIMINARY
COMMENTS
APPROVAL
TENDER
CONSTRUCTION <input checked="" type="checkbox"/>