



**RETURN BIDS TO:
RETOURNER LES SUBMISSION À :**

Parks Canada Agency Bid Receiving Unit
National Contracting Services

Bid Fax: 1-866-246-6893

Bid Email: soumissionsouest-bidswest@canada.ca

This is the only acceptable email address for responses to bid solicitation. Bids submitted by email directly to the Contracting Authority or to any other email address may not be accepted.

The maximum email file size is 25 megabytes. PCA is not responsible for any transmission errors. Emails with links to bid documents will not be accepted.

**REVISION 002 TO A
INVITATION TO TENDER**

**RÉVISION 002 INVITATION À
SOUMISSIONER
DEMANDE D'OFFRES À
COMMANDES**

The referenced document is hereby revised; unless otherwise indicated, all other terms and conditions of the offer remain the same.

Ce document est par la présente révisé; sauf indication contraire, les modalités de l'offre demeurent les mêmes.

Issuing Office - Bureau de distribution :
Parks Canada Agency
Calgary, AB

Title - Sujet : Prince of Wales Trail Improvements – Waterton Lakes National Park	
Solicitation No. - N° de l'invitation : 5P420-20-0100/A	Date : July 27, 2020
Amendment No. - N° de modification : 002	
Client Reference No. - N° de référence du client :	
GETS Reference No. N° de référence de SEAG : PW-20-00920451	

Solicitation Closes - L'invitation prend fin : At - à : 2:00 PM On - le : July 30, 2020	Time Zone - Fuseau horaire MDT
--------------------------------------------------------------------------------------------------------------------	------------------------------------------

F.O.B. - F.A.B. : Plant - Usine : <input type="checkbox"/> Destination : <input checked="" type="checkbox"/> Other - Autre : <input type="checkbox"/>		
Address Enquiries to - Adresser toutes demande de renseignements à : Brinthan Balakumar		
Telephone No. - N° de telephone : 587-832-1894	Fax No. -N° de télécopieur : (866) 246-6893	Email Address – Courriel : Brinthan.balakumar@canada.ca
Destination of Goods, Services, and Construction - Destination des biens, services, et construction : See Herein		

TO BE COMPLETED BY THE BIDDER - À REMPLIR PAR LE SOUMISSIONNAIRE

Vendor/ Firm Name - Nom du fournisseur/ de l'entrepreneur :	
Address - Adresse :	
Telephone No. - N° de telephone :	Fax No. - N° de télécopieur :
Name of person authorized to sign on behalf of the Vendor/Firm Nom de la personne autorisée a signer au nom du fournisseur/ de l'entrepreneur	
Signature :	Date :

Solicitation No. - N° de l'invitation :
5P420-20-0100/A

Amd. No. - N° de la modif. :
002

Contracting Authority - Autorité contractante :
Brinthan Balakumar

Client Ref. No. - N° de réf. du client :

Title – Titre :
Prince of Wales Trail Improvements – Waterton Lakes National Park

Amendment 002

This amendment is raised to distribute information from the site visit.

A. Site Visit Information

Vendor	Representative's Name
Oskar Construction	Oskar Pietrasik
Jacobs	Duncan Stirk
Mcknight Enterprises Ltd	Billy Vooyes
Link Builders	Kelly Toews
Link Builders	Clint Baerg

B. Question and Answers

Q1: Where are the sensitive archaeological zones referenced in the contract documents?

A1: See Drawing 2 – Archaeological Notes

Q2: Is the Archaeological Monitoring a requirement of the contractor?

A2: See Project Specifications Section 01 11 00 Clause 1.9.2

Q3: The contract documents make specific reference to the requirement for archaeological monitoring. During what activities will the archaeologist be on site?

A3: See Drawing 2 – Archaeological Notes.

Q4: Is any of the work within a known archaeological zone?

A4: There are several archaeological sensitive zones within Waterton Lakes National Park, including some within close proximity to this project.

Q5: Is the contractor permitted to close any of the four zones to the public during construction?

A5: See Project Specifications Section 01 28 01 Clause 1.5.3 and Clause 1.11.2. Small duration closures will be considered where necessary for public safety concerns.

Q6: Is fencing required around the work area?

A6: See Project Specifications Section 01 28 01 Clause 1.11. Fencing may not be possible within Zone 4 – Prince of Wales Lookout due to the high winds often encountered. PCA will not require a fence at that location if a suitable plan to keep the public away from the jobsite is proposed. Site security is the general contractor's responsibility.

Q7: Where is the owner supplied stone material to be used at the Lookout located?

A7: The owner supplied stone is located within the Operations Yard at Waterton Lakes National Park.

Q8: Is the stone at the Lookout to be placed "wild" or "cut to fit"?

A8: The stone at the Lookout is to be placed "wild".

Q9: Will the owner consider allowing work at the Lookout to extend to 2021?

A9: The intent is to complete the Lookout this fall when fewer visitors are in the area.

Q10: Is the Prince of Wales Hotel open year round?

A10: The hotel is open to guests June 30 to September 21 2020, and May 21 to September 20 2021.

Q11: At what depth is bedrock at the Lookout area?

A11: The depth of bedrock at the Lookout area is unknown.

Q12: If bedrock is encountered at the Lookout prior to excavating to design elevation is the contractor required to cut into the bedrock?

A12: If the contractor encounters bedrock at an unexpected elevation the situation will be addressed in the field.

Q13: Can the Prince of Wales Lookout exposed concrete be washed or sandblasted?

A13: See Project Specifications Section 03 30 00 Clause 3.3.3.

Q14: Is a containment system required to capture the water used when exposing the aggregate?

A14: Yes, concrete contaminated water needs to be captured and disposed of off site. The general contractor's plan will need to be outlined for PCA review and comment in the Erosion and Sediment Control Plan, see Project Specifications Section 01 35 43 Clause 1.5.6.

Q15: Where is the excavated material to be hauled?

A15: See Drawing 2 and 3 General Notes.

Q16: Is testing required of the materials being removed from site?

A16: No additional materials testing will be required.

Q17: Are Trailhead Type 1 and Type 2 sign locations accessible by vehicle?

A17: With the exception of the signs for Crypt Lake, all Type 1 and Type 2 sign locations are accessible by vehicle. Due to its remote location the signs for Crypt Lake are contractor supply only, the owner will install at a later date.

Q18: Are the signs located within the Prince of Wales Trails Improvement project site?

A18: See Drawing 23 for sign locations.

Q19: Are there any restriction around the tack coat at Linnet Lake?

A19: To be applied within a 24-hour window before placement of asphalt while still following manufactures installation procedures.

Q20: The existing benches at Linnet Lake are to be removed. Does this include removing the concrete bases?

A20: The existing benches and associated concrete bases at Linnet Lake are to be removed under the scope of work for Item 5 – Seat Area Improvements

ALL OTHER TERMS & CONDITIONS REMAIN UNCHANGED