



RETURN BIDS TO:

RETOURNER LES SOUMISSIONS À:

Bid Receiving Public Works and Government
Services Canada/Réception des soumissions Travaux
publics et Services gouvernementaux Canada
800 Burrard Street, Room 219
800, rue Burrard, pièce 219
Vancouver
British Columbia
V6Z 0B9
Bid Fax: (604) 775-9381

**SOLICITATION AMENDMENT
MODIFICATION DE L'INVITATION**

The referenced document is hereby revised; unless otherwise
indicated, all other terms and conditions of the Solicitation
remain the same.

Ce document est par la présente révisé; sauf indication contraire,
les modalités de l'invitation demeurent les mêmes.

Comments - Commentaires

**Vendor/Firm Name and Address
Raison sociale et adresse du
fournisseur/de l'entrepreneur**

Issuing Office - Bureau de distribution
Public Works and Government Services Canada - Pacific
Region
800 Burrard Street, Room 219
800, rue Burrard, pièce 219
Vancouver
British C
V6Z 0B9

Title - Sujet IOS Guardhouse	
Solicitation No. - N° de l'invitation F1700-204430/A	Amendment No. - N° modif. 005
Client Reference No. - N° de référence du client F1700-204430	Date 2020-07-27
GETS Reference No. - N° de référence de SEAG PW-SPWY-041-8790	
File No. - N° de dossier PWY-0-43025 (041)	CCC No./N° CCC - FMS No./N° VME
Solicitation Closes - L'invitation prend fin at - à 02:00 PM on - le 2020-07-31	
Time Zone Fuseau horaire Pacific Daylight Saving Time PDT	
F.O.B. - F.A.B. Plant-Usine: <input type="checkbox"/> Destination: <input checked="" type="checkbox"/> Other-Autre: <input type="checkbox"/>	
Address Enquiries to: - Adresser toutes questions à: Sezginalp (PWY), Kipp	Buyer Id - Id de l'acheteur pwy041
Telephone No. - N° de téléphone (604) 367-5341 ()	FAX No. - N° de FAX (604) 775-6633
Destination - of Goods, Services, and Construction: Destination - des biens, services et construction: DFO - Institute of Ocean Science - Sidney, BC	

Instructions: See Herein

Instructions: Voir aux présentes

Delivery Required - Livraison exigée	Delivery Offered - Livraison proposée
Vendor/Firm Name and Address Raison sociale et adresse du fournisseur/de l'entrepreneur	
Telephone No. - N° de téléphone Facsimile No. - N° de télécopieur	
Name and title of person authorized to sign on behalf of Vendor/Firm (type or print) Nom et titre de la personne autorisée à signer au nom du fournisseur/ de l'entrepreneur (taper ou écrire en caractères d'imprimerie)	
Signature	Date

Solicitation No. - N° de l'invitation
F1700-204430

Amd. No. - N° de la modif.
005

Buyer ID - Id de l'acheteur
pwy041

Client Ref. No. - N° de réf. du client

File No. - N° du dossier

CCC No./N° CCC - FMS No./N° VME

Solicitation Amendment 005 is raised to issue Addendum 005

1. Please find Addendum 005

All other terms and conditions remain unchanged.

The following Addendum supersedes information contained in drawings and specifications issued for the project to the extent referenced. The following changes in the tender documents are effective immediately. This Addendum will form part of the contract documents.

1.0 DRAWINGS:

- 1.1 2/ A2.10 Floor Plan, Window W6 & A0.20 Window Legend: provide vinyl "frosted" privacy film to interior light of WC window.
- 1.2 2/ A7.10 WC East Elevation: Window W6 is not shown- refer to A0.20 Window Legend, Plan 2/A2.10 & 1/ A3.10 East Elevation for configuration.

1.0 SPECIFICATIONS:

- 2.1 Section 08 44 13 Aluminum Curtainwall, part 1.6 Quality Assurance:
 - 1.6.1: replace with: "Installer with minimum of 5 years specialized experience in performing work of this Section;"
 - 1.6.2: delete entirely.
- 2.2 Section 01 14 00 Work Restrictions, part 1.5 Trenching and Excavation:
 - Add:
 - .3 The Departmental Representative will require weekly updates on cultural observer hours and a description of the work being done by the contractor while cultural observers are present. These weekly updates will be sent through signed email by the contractor to the Departmental Representative
- 2.3 Section 23 05 02 – Heating Ventilation and Air Conditioning
 - 1.20.1: delete entirely;
 - 2.12.5: add "Equivalent alternate products, having the same characteristics, will not be excluded."
- 3.0 BIDDER QUESTIONS:**
- 3.1 Q: Please confirm the count of roller shades required, there is some ambiguity in the counts;
 - A: Provide a roller shade at all vision windows as shown in elevations and Window Legend on sheet A0.20, including glazed transoms above doors, but excluding the W/C window.
- 3.2 Q: On drawing C-02 we have two questions related to the valve on the incoming water service:
 - a. Is this permitted to be there?

b. Is it possible to relocate the incoming water service further north to enter into the building's mechanical room ...?

A: Adjusting the proposed location of the waterline will be considered during the construction phase.

3.3 Q: Please provide the rim elevations for the manholes on C-02 and C-03 as identified in the attached sketch;

A: Below are the approximate rim elevations:

- DMH1 9.56m
- DMH2 8.17m
- SMH1 8.20m
- SMH2 7.49m
- SMH3 7.37m
- SMH4 5.43m
- SMH5 5.34m

3.4 Q: Please provide a drain profile elevation for all the manholes on drawing C-03;

A: The Contractor is to rely on the provided drawings. No additional drawings will be prepared.

3.5 Q: Please confirm PL1 ,PL2 and WT connection plate material on S2.01 are these steel plates ? if so please verify thickness.

A: All the connection plate material and its thickness are shown on the drawings. The connection plate material is Sheet Steel to ASTM A446 as per note #3 of the Steel Stud section on the General Notes on S101. The plate thickness is per the designation as noted on note #8 of the Steel Stud section on the General Notes on S101. For example, thickness of PL1 is specified as 54 Mil in the Connection Plate Schedule on S201. Thus, its thickness is equal to $54/1000=0.054$ inch as per note above.

3.6 Q: Could you please clarify if the VP membrane is required on exterior wall assembly "W2". Details on A5.10 and A5.20 at the insulated back-pan locations. Typically when curtainwall is used in a situation like this the curtainwall is sealed with membrane continuously around the frame perimeter into the glazing pocket. The VP membrane would not be required on the sheathing at these locations as the curtainwall is providing the building seal. Please could you review this and confirm that the VP Barrier will not be required at these locations if the curtainwall assembly is membraned at the perimeter, around the steel support angles and to VP membrane at the jambs.

A: Retain the Vapour-Permeable membrane in wall type W2, for a continuous installation across all exterior framed walls and parapets.

3.7 Q: We request a cash allowance further to the requirements surrounding cultural observers noted in 01 14 00 paragraph 1.5. This would ensure fairness to all bidders and handling of unforeseen site conditions.

A: A cash allowance will not be issued. Rather, the Departmental Representative will require weekly updates on cultural observer hours and a description of the work being done by the contractor while cultural observers are present. These weekly updates will be through signed email by the contractor to the Departmental Representative. A change order will then be issued for all cultural observers hours. Therefore, cost of cultural observers should not be included in a bidder's bid price.

3.8 Q: I was wondering if you would be able to tell me the make and model of the existing door closers in the facility? The door hardware spec is written for the door closers to match existing.

A: Provide LCN 4040XP with hold-open feature, or equivalent.

End of Addendum 05

