

1 - GENERAL

1.01 DESCRIPTION

- .1 This section specifies requirements for demolishing wholly or in part various items designated to be removed or partially removed including other miscellaneous items described in this sections.
- .2 Removal and Reinstallation or disposal for construction operations will include:
 - .1 Mobilization and demobilization of all equipment to make work progress for the duration of this contract.
 - .2 Submittal of an environmental mitigation plan(s), its implementation(s) and any subsequent necessary update(s).
 - .3 Submittal of a Health and Safety Plan(s), it's implementation(s) and Any subsequent update(s).
 - .4 Removal, loading, trucking and disposal of any/all materials within the limits shown to construct the toe-in for armour/filter stone. Material is to be disposed of at the Neguac Containment Cell. (Neguac Harbour).
 - .5 Have located done for all overhead or underground utilities by appropriate agencies.
 - .6 Removal of all other items required to gain access to the work areas, for the progress of the work.

1.03 PROTECTION

- .1 Protect existing objects designated to remain. In event of damage, immediately replace or make repairs to approval of and at no additional cost to Canada.
- .2 Remove all floating debris from water on a routine and timely basis.

1.04 MEASUREMENT FOR PAYMENT

- .1 Removal and Reinstallation or disposal for construction operations will include:
 - .1 Mobilization and demobilization of all equipment to make work progress for the duration of this contract.
 - .2 Submittal of an environmental mitigation plan(s), its implementation(s) and any subsequent necessary update(s).
 - .3 Submittal of a Health and Safety Plan(s), it's implementation(s) and Any subsequent update(s).
 - .4 Removal, loading, trucking and disposal of any/all materials within the limits shown to construct the toe-in for armour/filter stone. Material is to be disposed of at the Neguac Containment Cell. (Neguac Harbour).
 - .5 Have located done for all overhead or underground utilities by appropriate agencies.
 - .6 Removal of all other items required to gain access to the work areas, for the progress of the work.
- .2 All items listed under this section will be paid in a lump sum price.

1.05 SUBMISSIONS

- .1 Methodology:
 - .1 When requested provide methodology for carrying out the work.
 - .2 Provide submission in accordance with Section 01 33 00.

2 - PRODUCTS

2.01 NOT USED

- .1 Not used.

3 - EXECUTION

3.01 PREPARATION

- .1 Inspect site and verify with Departmental Representative items designated for removal and items to be preserved.
- .2 Locate and protect utility lines. Preserve in operating condition, active utilities traversing site.
- .3 Should existing conditions such as beach topography vary significantly from those shown on the drawings, inform the Departmental Representative who will provide direction.

3.02 SALVAGING

- .1 Stockpile salvageable material, to eliminate loosing material during tide differences and the environment.

3.04 EXECUTION

- .1 Inspect site and verify with Departmental Representative objects designated for removal.
- .2 Locate and protect utility lines. Preserve in operating condition active utilities traversing site.

3.05 REMOVAL

- .1 Remove in their entirety all materials and objects specified for removal.
- .2 Do not disturb adjacent work designated to remain in place.

3.06 DISPOSAL OF MATERIAL

- .1 All demolished materials, except materials designated to be reused, will become property of contractor and will be removed from site and disposed of to the satisfaction of Departmental Representative and in accordance with environmental guidelines. It is the sole responsibility of the contractor to dispose of all demolished materials at an approved disposal site. Ensure that disposal site is approved and willing to accommodate any materials disposed of from work site.
- .2 Contractor shall obtain and pay for all necessary permits and disposal fees for use of an approved waste disposal site.

3.07 RESTORATION

- .1 Upon completion of work, remove debris, trim surfaces and leave work site in clean condition.
- .2 Reinstate areas and existing works outside areas of demolition to conditions that existed prior to commencement of work.

END OF SECTION