

**DEPARTMENT OF FISHERIES AND OCEANS
CANADIAN COAST GUARD
NEWFOUNDLAND AND LABRADOR**

Robin Hood Bay Laydown Area
Sugar Loaf Road, St. John's



PROJECT NO.: F6839-205502
DATE: April 28, 2020

SPECIFICATIONS

Project No: F6839-205502
Title: Contractor Services for Robin Hood Bay Laydown Area
Site of work: Sugar Loaf Road, St. John's, NL

Background Information:

Canadian Coast Guard requires an extension to the existing laydown area. Laydown area to be used for storage of containers, building materials and prefabricated towers.

Description of Work:

Work under this Contract includes but is not necessarily limited to the provision of all labour, materials, and equipment required to:

Construct a 60m x 90m laydown pad at the Robin Hood Bay Communication Site

1.0 General

Contractor is to submit a **project/site specific** Health and Safety Plan for undertaking the work prior to mobilizing for ANY fieldwork. All work to be undertaken in accordance with applicable federal, provincial, and municipal legislation and standards. In the event of conflict between any provisions of above authorities the most stringent provision governs.

Contractor to provide detailed work plan indicating work methods/procedures to be implemented and products to be utilized. Also, work plan to include anticipated schedule for the undertaking of all work.

Contractor is to provide detailed cost estimate for provision of the identified services within the time period identified in the transmittal letter. All travel expenses to be in accordance with Treasury Board guidelines.

Upon completion of work Contractor to provide written notification indicating that all work has been completed and is ready for inspection.

2.0 Work Required

The Work to be performed under this scope of work shall include all labour, materials and equipment necessary to complete the following:

- 2.1.1 Grubbing of existing vegetation and overburden. Stockpile as directed by engineer on site.
- 2.1.2 Supply and place blast rock on site as directed by CCG engineer. Use 3500 m³ for estimate. Provide a placed cost per m³ should more be required as an extra.
- 2.1.3 Supply and place Class A on rock pad and adjacent pad as directed by CCG engineer. Use 800 m³ for estimate. Provide a placed cost per m³ should more be required as an extra.
- 2.1.4 Fill to be compacted in maximum one meter lifts. Complete pad to be compacted after grade. Any variations from grade to be corrected.
- 2.1.5 Original/copy of scale slips to be provided to engineer at end of the project.
- 2.1.6 Contractor to follow latest provincial Chief Medical Officer Covid 19 preventative measures. Contractor to also comply with current CCG safe operating procedures/screening when required. Any additional PPE required are the responsibility of the contractor. Completion, Scheduling and Planning of the Works

3.0 Schedule

- 3.1. All work shall be completed within (4) four weeks from the date contract is awarded

4.0 Health and Safety Requirements

This Section describes specific safety requirements the contractor shall observe and enforce during the progress of the Work.

Summary:

4.1 Inclusion of these specific safety requirements shall not constitute a relief of the Contractor's responsibility but is a precaution against oversight or errors.

4.2 The Contractor is solely responsible for safety procedures deemed necessary by the Contractor to meet the requirements of these Specifications.

4.3 Provide all workers, including sub-trades, with adequate and appropriate safety procedures prior to commencement of their duties. Ensure all workers comply with all safety regulations required by National and Provincial Building Codes, Workmen's Compensation Board, Canada Labour Code Part II and any Provincial and municipal statutes and authorities. Take all precautions and provide all required protection to ensure the safety of the general public and the workmen in accordance with the current edition of the Occupational Health and Safety Act and Regulations for Construction Projects.

4.4 In the event of conflict between any provisions of above authorities the most stringent provision governs.

5.0 Environmental Requirements

5.1 Contractor is solely responsible for all environmental protection procedures deemed necessary to comply with all applicable Federal, Provincial and Municipal regulatory requirements.

5.2 Contractor is fully responsible for all costs associated with required remediation occurring from Contractors work on site.

5.3 Fires and burning of rubbish not permitted on site.

5.4 Do not dispose/bury rubbish or waste materials on site.

5.5 Do not dispose of waste or volatile materials such as mineral spirit, oil, paint thinner etc. into waterways, storm or sanitary sewers.

5.6 Contractor is to ensure that all equipment is in good repair and no fuels or fluids are leaking from it. Equipment in disrepair is not permitted on site and will be ordered removed. Basic petroleum spill equipment must be on site.

5.7 No maintenance beyond that of a required daily routine shall be performed on equipment while on site. No refueling to be completed within 30m of a water body.

5.8 Do not pump water suspected of containing suspended materials into waterways, sewers or drainage systems.

5.9 Contractor must comply with any/all direction and/or advice provided by the Federal, Provincial or Municipal authorities having jurisdiction.

Appendix A
Lay Down Area Location