

ARCHITECT
EXP Architects Inc.
F: +1 902 453 5555 | F: +1 902 429 5457
90 Lovell Lake Court, Suite 401
Halifax, NS B3S 0H6
CANADA
www.exp.com



• BUILDINGS • EARTH & ENVIRONMENT • ENERGY •
• INDUSTRIAL • INFRASTRUCTURE • SUSTAINABILITY •

Consultants Ingénieurs conseils





1	ISSUED FOR TENDER	07/15 2020
revisions		date
project		projet

**BIO ELLIS
BUILDING
ROOF REPAIR
BIO DARTMOUTH**

**EXISTING / DEMOLITION
ROOF DETAILS**




designed A.S.D.	conçu
date MAY, 2018	
drawn D.R.R.	dessiné
date MAY, 2018	
approved	approuvé
date	
Tender	Submission
PWGC Project Manager	Administrateur de projets TP/GC
project number	no. du projet
R.086538.001	
drawing no.	no. du dessin
A3	

- DEMOLITION KEY NOTES:**
- D1 EXISTING METAL FLASHING TO BE REMOVED.
 - D2 EXISTING WOOD BLOCKING TO BE REMOVED.
 - D3 EXISTING MEMBRANES, GYPSUM BOARD, INSULATION, AND AIR/VAPOUR BARRIER TO BE REMOVED TO EXPOSED EXISTING CONCRETE BLOCK WALL.
 - D4 EXISTING ROOF ASSEMBLY TO BE REMOVED TO EXISTING DECK.
 - D5 EXISTING CLADDING TO BE TEMPORARILY REMOVED AS REQUIRED FOR NEW WORK. MAKE GOOD EXISTING FINISHES.
 - D6 EXISTING CURTAIN WALL TO REMAIN.
 - D7 EXISTING CURTAIN WALL PRESSURE CAP TO BE TEMPORARILY REMOVED AS REQUIRED BY NEW WORK. REINSTALL PRESSURE CAP UPON COMPLETION OF NEW WORK AND MAKE GOOD ANY FINISHES.
 - D8 BOTTOM 6± COURSES OF MASONRY TO BE REMOVED (SAVE MASONRY AS REQUIRED TO MAKE GOOD EXISTING WALL) FOR FLASHING OF NEW MEMBRANES. TEMPORARY SUPPORT MASONRY ABOVE WHILE WORK IS BEING CONDUCTED TO ENSURE STABILITY OF BRICK VENEER. REINSTATE/INSTALL NEW BRICK AND INSULATION AS REQUIRED TO MAKE GOOD EXTERIOR FINISH. JOINTS AND MORTAR COLOUR OF NEW WORK TO MATCH EXISTING.
 - D9 EXISTING STEEL Z GIRT TO BE REMOVED AND SAVED FOR REINSTALLATION.
 - D10 EXISTING METAL LINER PANEL TO REMAIN.
 - D11 EXISTING STEEL ANGLE TO REMAIN.
 - D12 EXISTING GUARDRAIL TO BE REMOVED AND SAVED FOR REINSTATEMENT.
 - D13 EXISTING DOOR, FRAME, AND THRESHOLD TO BE REMOVED AND SAVED FOR REINSTATEMENT.
 - D14 EXISTING GUARDRAIL BRACKET TO REMAIN IN PLACE.



SECTION A-A
SCALE : 1:10
0mm 100 200 300 400 500 600 700 800 900 1000mm


SECTION B-B
SCALE : 1:10
0mm 100 200 300 400 500 600 700 800 900 1000mm



SECTION C-C
SCALE : 1:10
0mm 100 200 300 400 500 600 700 800 900 1000mm

SECTION D-D
SCALE : 1:10
0mm 100 200 300 400 500 600 700 800 900 1000mm

SECTION E-E
SCALE : 1:10
0mm 100 200 300 400 500 600 700 800 900 1000mm



SECTION F-F
SCALE : 1:10
0mm 100 200 300 400 500 600 700 800 900 1000mm