



Kamloops Snowbird Environmental Cleanup Project

Bidder's Meeting Friday, August 28, 2020 11:00am PDT





Agenda

- Introductions
- Bidder's Meeting Overview
- Site Overview
- General Contract Elements
- Contractor Requirements
- Video Site Tour

2





Introductions

Public Works and Government Services Canada:

Ken Ngan

Dave Osguthorpe

Andrew Smith

Department of National Defence:

Captain Cruz

Golder Associates:

Erik von Krogh

Alison Verde

Registered Bidder's

3





Bidder's Meeting Overview

- This meeting is to familiarize the bidders with the site. Anything presented today does not take precedence over the tender documents. The bidders are to refer to the tender documents in their entirety.
- Questions from bidder's should be submitted in writing to Ken Ngan – PSPC Contracting Authority and answers to be provided as addenda. No answers will be provided during this meeting.






Bidder's Meeting Overview

Virtual Meeting Rules and Instructions

- Attendees will be muted
- Materials from the meeting will be posted online following the meeting
- If there are any technical issues during the presentation – raise your hand or type a comment
- There will be a video tour of the site at the end of the presentation - If there are requests for clarification regarding the videos – raise your hand or type a comment







Bidder's Meeting Overview

Virtual Meeting Rules and Instructions

Items discussed are not a complete list and the contractor is to refer to the tender documents for all requirements

6





Project Timing Requirements

- Tender close is 14:00 PDT, Sept. 8, 2020.
- Tender award shortly after tender close.
- All work to be completed by:
 - Site Works to be completed by October 30, 2020
 - Completion of Work by November 30, 2020

7





DND Project Remarks



8



Site Overview



- Located at a private residence in North Kamloops
- Objective is to remove contaminated soils in the front yard
- Site to be handed over to home restoration contractors working on behalf of the homeowner
- Site is located in a residential neighbourhood





Site Overview



- One storey house with a basement serviced by municipal utilities and natural gas utilities
- Temporary power pole
- The structure cannot be impacted by the work

10






Constraints



11



Constraints







Site Overview



Soil CSR RL+:

- Select Metals
- Select VOCs
- •BTEX
- Select PAHs
- •LEPH, HEPH, VPH


Soil BC HWR:

- •Total Hydrocarbons >3%
- Leachable Ethylbenzene





General Site Layout








General Contract Elements

Unit Price Table

- Payment items for excavation is by volume according to difference between pre- and post-remediation surveys (m3).
- Payment for transport and disposal of soil is by manifest weight (tonne)
- Payment for provision and placement of Backfill is by manifest weight (tonne)

15





General Contract Elements

Surveys

- Surveying for Progress and Final Excavation Limits
- Pre- and Post-Construction Condition Survey
- As-built survey

16





Responsibilities:

- Prime Contractor for Health and Safety
- Qualified Professionals:
 - Environmental, Geotechnical, Structural, etc.
 - To support submittal preparation for Contractor
 - Contractor responsible for Quality Control Monitoring throughout project
- PWGSC representatives will conduct QA monitoring
- PWGSC representatives will collect confirmatory samples at excavation extents

17






Pre-Construction Submittals and Plans

- Health and Safety Plan and Emergency Procedures, including COVID-19 Plan
- Contaminated Soil Management Plan
- Excavation and Backfilling Plan
- Contaminated Material Transportation Plan
- Contaminated Material Disposal Plan
- **Environmental Protection Plan**
- Schedule
- Preconstruction As-Built Documents
- Preconstruction Condition Survey

18






Logistics:

- Traffic management
- Housekeeping and site maintenance
- Fencing
- Site security
- Hours of work M-F 0830-1730

19






Contaminated Soil Excavation

- Excavation to Contaminated Extents shown on Drawings to be validated in the field by PWGSC's representative
- PWGSC's representative responsible for collecting confirmatory samples
 - Confirmatory sample results to be received within 5 working days of sampling
 - Backfilling excavation prior to receipt of confirmatory sampling results is at the Contractor's risk
 - Additional excavation may be required if confirmatory samples do not meet the remediation objectives

20





Contaminated Soil Transport and Disposal


- Must be authorized by a Facility Authority
- Contaminated soil transport and disposal pre-work submissions:
 - Permit
 - Letter from Contractor's QP that Disposal Facility is appropriate
 - Letter from Disposal Facility that material will be accepted
- Contaminated soil transport and disposal prepayment submissions
 - Weigh scale slips
 - Certificate of Disposal from Facility

21





Backfilling and Site Restoration







Video Site Tour

- Pre-recorded video tour
- Attendees may type in specific requests to view specific site features



23





Questions

Questions from bidder's should be submitted in writing to Ken Ngan – PWGSC Contracting Authority and answers to be provided as addenda.

24



