

REQUEST FOR INFORMATION (RFI)

ect:	Troutbrook Campground Phase 2 site work	Request Date	September 3 rd 2020
tractor:	N/A	Project #	133348246
ner:	Parks Canada	Contract #	
ation:	Cape Breton, Nova Scotia	Response	
Subject	Tender Questions	Requested	
‡	1	Page	1 of 1

Contractor Request:

- 1. There is a diagram on E-001 detail 1 containing a battery rack that may be composed of steel channel and angles. Unfortunately, on the drawing it does not give any details on what materials are to be used, the dimensions, the quantity of stands required or the finish of the stands
- 2. Is there any specification for these 2 flag poles or do we just submit a price for 2 @ 9m (30'-0")?
- 3. Drawing E-101 notes that we are to dismantle, remove and relocate the existing generator and loadbank to the Cheticamp Camp Site. Can you clarify where the Cheticamp Camp Site is, if we need to allow for reconnecting the existing generator/loadbank in the new location and if a pad is already in place at the new location for the existing generator/loadbank.
- 4. All structural, mechanical & electrical drawings have a note in the title block "foundation package already installed (N.I.C.)". Please clarify if this is correct.

Request by:	Signature:	Date:

Response:

- 1. Please refer to Specification 26 33 16. Battery racks shall be manufactured by passoni or approved equivalent manufacturer. racks shall be epoxy powder coated, folded steel construction. racks shall be assembled on site. dimensions as per detail 1/e-001. width shall accommodate two levels of twin tiers of batteries as indicated in detail depth of bottom and top twin tiers min. 590mm width of rack 3392mm based on indicated battery widths. height 1000mm as indicated on detail. Please be sure to read all specifications.
- 2. As per c-004: Contractor to supply complete kit shop drawings for approval (for 2 flag poles). No Specs are are provided, Parks to approval the final product.
- 3. Please refer to Specification 26 32 13.02. Refer to the Owner for the location of the Cheticamp site and the precise location for the generator delivery. **Please be sure to read all specifications**
- 4. This refers to buildings b, e & f previously constructed not in contract. This note was added to the accessibility ramps drawing for buildings b and e (S-111) to make clear that everything else was already built (foundations and structural elements for building b/e, architectural finishes, etc). the note should not be showing in the rest of the structural drawings in the set. apologies for the confusion.

Responded by: Stantec LTD **Signature:** Rebecca Peters, M.Arch **Date:** Sept 7th 2020