

The following changes to the tender documents are effective immediately and will form part of the contract documents:

REVISIONS AND CLARIFICATIONS

- .1 Specification Section 31 23 33 - Excavation, Trenching and Backfilling –
- Delete: 2.1.1.1 Cement-Stabilized Fill material to comply with City of Winnipeg CW-2160 “Concrete Underground Structures and Works”, Table 2160.1, item C.
- Replace with: 2.1.1.1 Cement-Stabilized Fill material to comply with City of Winnipeg CW-2160 “Concrete Underground Structures and Works”, Table 2160.1, Type of structures or Used - C) Cement – Stabilized Fill or D) Flowable Cement Stabilized Fill.
- .2 Drawing S1.1 – General Notes – Cast-in-Place Concrete
- Delete: Stabilized Fill: 1.5 to 2.5 MPa Min. at 28 Days
Class of Exposure: C-2
Entrained Air/Category: 1 (5% to 8%)
Aggregate Max. 5 mm
Curing Type: Type 2 - Additional
- Replace with: Stabilized Fill: 1.5 to 2.5 MPa Min. at 28 Days
Curing Type: Type 2- Additional

END OF ADDENDUM NO. 3