

The following changes to the tender documents are effective immediately and will form part of the contract documents:

**Enquiries received during the Solicitation Period:**

1. Is the steel work galvanized or is it primed? I do not see any indications what is primed and what is galvanized other than notes on S1.1 #7, 8.

Answer: S1.1, note 7 under Structural Steel, indicates that all structural steel is to receive one coat of CISC/CPMA 1-73a quick drying shop primer.

2. Confirm that Hilti KBU anchors are correct. On Sp5 and Sp6 posts, Hilti rep that I talked to does not know of them.

Answer: Hilti KBU is incorrect, the anchors should be Hilti KBV.

END OF ADDENDUM NO. 4