

1 GENERAL

1.01 REFERENCES

- .1 Canada Green Building Council (CaGBC)
 - .1 LEED Canada-NC Version 1.0-2004, LEED (Leadership in Energy and Environmental Design): Green Building Rating System Reference Package For New Construction and Major Renovations (including Addendum 2007).
- .2 U.S. Environmental Protection Agency (EPA)/Office of Water
 - .1 EPA 832/R-92-005, Storm Water Management for Construction Activities: Developing Pollution Prevention Plans and Best Management Practices.

1.02 ACTION AND INFORMATIONAL SUBMITTALS

- .1 Submit in accordance with Section 01 33 00 - Submittal Procedures.
- .2 Sustainable Design Submittals:
 - .1 Erosion and Sedimentation Control: submit erosion and sedimentation control plan in accordance with EPA 832/R92-005 authorities having jurisdiction.

1.03 DELIVERY, STORAGE AND HANDLING

- .1 Deliver, store and handle materials in accordance with Section 01 61 00 - Common Product Requirements.

2 PRODUCTS

2.01 MATERIALS

- .1 Water: in accordance with Departmental Representative's approval.

3 EXECUTION

3.01 PREPARATION

- .1 Temporary Erosion and Sedimentation Control:
 - .1 Provide temporary erosion and sedimentation control measures to prevent soil erosion and discharge of soil-bearing water runoff or airborne dust to adjacent properties and walkways, according to requirements of authorities having jurisdiction.

3.02 APPLICATION

- .1 Apply water with distributors equipped with means of shut-off and with spray system to ensure uniform application.

3.03 CLEANING

- .1 Progress Cleaning: clean in accordance with Section 01 74 11 - Cleaning.

PWGSC
CONSTRUCTION OF A NEW
CONTAINMENT CELL
LAMEQUE WHARF
GLOUCESTER COUNTY, NB
PROJECT NO. R.112964.001 and R.112898.001

ROADWAY DUST CONTROL

SECTION 32 15 60
PAGE 2

- .1 Leave Work area clean at end of each day.
- .2 Final Cleaning: upon completion remove surplus materials, rubbish, tools and equipment in accordance with Section 01 74 11 - Cleaning.
- .3 Waste Management: separate waste materials in accordance with Section 01 74 21 - Construction/Demolition Waste Management and Disposal.
 - .1 Remove recycling containers and bins from site and dispose of materials at appropriate facility.
 - .2 Place materials defined as hazardous or toxic in designated containers.

END OF SECTION