

October 27, 2020

ADDENDUM
FOR
AAFC INDIAN HEAD RESEARCH FARM

CONTRACT NO. 59 – DUST COLLECTION SYSTEM
SOLICITATION #465-1-4-C59

Addendum No. 1

Changes to the specifications, which form part of the tender documents, are:

1. Refer to Drawing M6.1.

- 1.1 Clarification: existing compressed air system has an air dryer.
- 1.2 Clarification: existing air compressor has a capacity of 25 scfm @ 175 psi with an 80 gallon tank and a 7.5 HP motor.
- 1.3 Ensure that adequate clearance is maintained between dust collector and emergency blow back damper as per manufacturer's recommendations/requirements. Block back damper to remain outside building envelope. Dust collector location to be adjusted to suit clearance requirements. Coordinate on site.

2. Refer to Drawing M6.2.

- 2.1 Specification for dust collector 'DC' has been revised as follows:
Shaker starter not required.
Solid state automatic shaker controller to be solid state automatic pulse controller.
- 2.2 Contractor to provide a spare set of filters for the Dust Collector 'DC', Make-Up Air Units 'MUA1' and 'MUA2'.

3. Refer to Attached Sketch AD-1-SK-1

- 3.1 Provide framing and flashing as indicated at duct penetrations through exterior walls where required.

4. Refer to Attached Sketch AD-1-SK-2

- 4.1 Provide curtain mounting/attachment for all exhaust hoods as indicated.

Contractor Questions:

1. Is there some kind of curtain rod and curtain hanging detail for the specified Airdrie Canvas clear vinyl specified to be hung from the exhaust hoods?

See attached Sketch AD-1-SK-2 for curtain support details.

2. Can you confirm that ALL Dust Collector ductwork is to have welded or soldered longitudinal & transvers joints?

All dust collector ductwork is to be welded at all joints.

3. Is there a detail for architectural or structural for any exterior wall penetrations?

See attached Sketch AD-1-SK-1 for wall penetration framing details.

Approved Equals:

- Nailor Industries grilles, registers, diffusers.
- Loren Cook fans
- Thermotek make-up air unit
- Reznor make-up air unit
- Sourcetek dust collector
- Modine make-up air unit
- Camfil dust collector
- Aerovent exhaust fans
- Krueger grilles
- Eurovac dust collector
- Twin City exhaust fans
- Engineered Air make-up air unit

All equal products are to meet or exceed the performance in all respects of the original product specified.

There is no change to the date of receipt of tenders which is 2:00 pm Local Regina Time, Thursday, October 29, 2020.

Melissa Smith,
Senior Contracting Officer
AAFC, Regina, Saskatchewan