

Amendment 005

Q1) Is there any guarantee that the 24 week period will contain the Winter shutdown period?

A1) The 24 week period include the winter shutdown period and the contractor is allowed to work during this period. It should be noted that other routine bridge maintenance activities will be taking place during the winter shut down period and the work activities shall be coordinated with the Bridge Master.

Q2) Re Section 01 11 00 Page 3 Item .6 .8 – Work scope is undefined - Please supply noted document “Work with the Engineer to correct failures to elements of the traffic control system that were identified and reported in the 2018 Comprehensive Detailed Annual Inspection (CDI) report.”

A2) Please see the attached.

Q3) Re Section 01 11 00 Page 3 Item .6 .9 – The following item description is not complete. “Following the completion of the re-programming and additional programming the control systems vendor shall perform.”

A3) After the word perform add “ testing of the PLC control system to prove that the changes have not effected the sequence of operation, alarm and trip functionality of the bridge control system to the satisfaction of the Departmental Representative”.

Q4) Re Section 01 11 00 Page 3 Item .7 .1 – Work scope is undefined - Please supply list of required cables. “ Remove all abandoned existing cable throughout the bridge facility.”

A4) The answer to a similar Q6 in Amendment 004 . As it is difficult to quantify this item, an allowance of \$40,000 will be set aside for this work and it will be paid on a time and material basis.

Q5) Re Section 02 41 99 Page 2 Item 1.5 .1 – Please supply document mentioned - "Hazardous Products Inventory – Burlington Lift Bridge,2018" and “Asbestos and Lead Reassessment Survey – Burlington Lift Bridge, 2018”

A5) Please see the attached.