



RETURN BIDS TO:

RETOURNER LES SOUMISSIONS À:

Bid Receiving Public Works and Government
Services Canada/Réception des soumissions Travaux
publics et Services gouvernementaux Canada
800 Burrard Street, Room 219
800, rue Burrard, pièce 219
Vancouver
British Columbia
V6Z 0B9
Bid Fax: (604) 775-9381

SOLICITATION AMENDMENT MODIFICATION DE L'INVITATION

The referenced document is hereby revised; unless otherwise
indicated, all other terms and conditions of the Solicitation
remain the same.

Ce document est par la présente révisé; sauf indication contraire,
les modalités de l'invitation demeurent les mêmes.

Comments - Commentaires

Vendor/Firm Name and Address
Raison sociale et adresse du
fournisseur/de l'entrepreneur

Issuing Office - Bureau de distribution
Public Works and Government Services Canada - Pacific
Region
800 Burrard Street, Room 219
800, rue Burrard, pièce 219
Vancouver
British C
V6Z 0B9

Title - Sujet Boardwalk Replacement	
Solicitation No. - N° de l'invitation K2F51-210350/A	Amendment No. - N° modif. 001
Client Reference No. - N° de référence du client K2F51-210350	Date 2020-11-18
GETS Reference No. - N° de référence de SEAG PW-\$PWY-019-8863	
File No. - N° de dossier PWY-0-43124 (019)	CCC No./N° CCC - FMS No./N° VME
Solicitation Closes - L'invitation prend fin at - à 02:00 PM Pacific Standard Time PST on - le 2020-12-01 Heure Normale du Pacifique HNP	
F.O.B. - F.A.B. Plant-Usine: <input type="checkbox"/> Destination: <input checked="" type="checkbox"/> Other-Autre: <input type="checkbox"/>	
Address Enquiries to: - Adresser toutes questions à: Ngan, Ken (PWY)	Buyer Id - Id de l'acheteur pwy019
Telephone No. - N° de téléphone (604) 671-0219 ()	FAX No. - N° de FAX (604) 775-6633
Destination - of Goods, Services, and Construction: Destination - des biens, services et construction: ECCC – Vaseux-Bighorn National Wildlife Area – Vaseux Lake, BC	

Instructions: See Herein

Instructions: Voir aux présentes

Delivery Required - Livraison exigée	Delivery Offered - Livraison proposée
Vendor/Firm Name and Address Raison sociale et adresse du fournisseur/de l'entrepreneur	
Telephone No. - N° de téléphone Facsimile No. - N° de télécopieur	
Name and title of person authorized to sign on behalf of Vendor/Firm (type or print) Nom et titre de la personne autorisée à signer au nom du fournisseur/ de l'entrepreneur (taper ou écrire en caractères d'imprimerie)	
Signature	Date

This Solicitation Amendment 001 is raised to incorporate responses to questions received, and to incorporate the associated Addendum #1.

Q1. The drawings and most of the specs indicate piles can be in the form of pipe piles or helical steel piles, yet section 1.2 of the Submittals section indicates design for helical piles only. This is inconsistent, please clarify.

A1. Please refer to Addendum #1.

Q2. Are there specific environmental report/requirements that need to be met? Grout is commonly used with helical piles but is it ok to use since this is a wildlife area? Ground conditions and design loads will dictate if the screw piles alone are adequate.

A2. Please note that an application for environmental permit for this project has been submitted. Preliminary permit requirements include:

- The consulting biologist will flag out any wetlands/watercourses/sensitive environment features in the project area prior to construction start work so that the winning contractor clearly sees where they start/stop. The biologist will also provide project specific advice on working within the wet areas to minimize erosion and disturbance ahead of time. This should make things easy and clear for the winning contractor
- The installation of silt fencing is required (which is the contractor's responsibility) for the entire boardwalk areas. The consulting biologist will identify where the silt fencing is needed ahead of project start work and communicate to the contractor.
- Construction equipment for demolition and new installation cannot be more than the width of the existing boardwalk to reduce the impact on the species and vegetation
- A Canadian Wildlife permit from Environment and Climate Change Canada is required prior to any trees/shrubs, vegetation being removed if any.
- Once the successful bidder is selected, there will be a project kick off meeting with the technical authority, the contractor, and the consulting biologist. The contractor and consulting biologist will coordinate their site visits and schedule accordingly. The contractor and biologist will walk the boardwalk together before starting work and so the consultant is clear on the construction methods and the contractor is clear on the required mitigations measures.

Grout cannot be used on this site.

Please find following Addendum #1.

**All other terms and conditions remain unchanged.
End of Solicitation Amendment 001.**



Creative Thinking
Practical Results

STRUCTURAL ADDENDUM #1

Project: Boardwalk Replacement

Project No.: KEL.120812.0002

Issued By: Michael Blackman, P.Eng.

Date: 2020-11-17

Pages: 1

This Addendum forms part of, and is to be included in, the Contract Drawings and Specifications originally issued for the above-named project and no consideration will be given to any request for extras to this Contract due to the Contractor not being familiar with the Addenda. Please acknowledge receipt of this Addendum on the Bid Form.

This Addendum forms part of the Bid Documents and modifies as stated herein:

1.0 SPECIFICATIONS

1.1 Section 01 33 00 – Submittals

Delete sentence 1.2.1.1

Add sentence 1.2.1.1 "Helical pile or pipe pile foundations"

2.0 DRAWINGS

2.1 No Revision, this addendum.

End of Addendum No. 1