

EXTERIOR SITE FURNISHINGS

Rouge National Urban Park Trails Phase 3
December 3, 2020 Addendum #1

Section 32 37 00
Page 1 of 2

PART 1 - GENERAL

- | | |
|--|---|
| 1. RELATED REQUIREMENTS | 1. Section 03 30 00 Cast-in-Place Concrete |
| 2. ACTION AND INFORMATIONAL SUBMITTALS | <ol style="list-style-type: none">1. Submit product data in accordance with contract requirements.2. Submit shop drawings in accordance with contract requirements.3. Submit colour sample in accordance with contract requirements.4. Indicate dimensions, sizes, assembly, anchorage and installation details for each furnishing specified.5. Provide maintenance data for care and cleaning of site furnishings for incorporation into manual. |
| 3. WASTE MANAGEMENT AND DISPOSAL | <ol style="list-style-type: none">1. Separate waste materials for reuse and recycling in accordance with contract requirements.2. Remove from site and dispose of packaging materials at appropriate recycling facilities.3. Collect and separate for disposal paper, plastic, polystyrene, corrugated cardboard packaging material in appropriate on-site bins for recycling in accordance with Waste Management Plan.4. Separate for reuse and recycling and place in designated containers Steel, Metal and Plastic waste in accordance with Waste Management Plan.5. Fold up metal banding, flatten and place in designated area for recycling. |

PART 2 - PRODUCTS

- | | |
|-------------|---|
| 1. BOLLARDS | <ol style="list-style-type: none">1. Maglin – 650 Series Bollard<ol style="list-style-type: none">a. Manufacturer: Maglin (phone: 1-800-716-5506 x 1102) or approved equal;b. Model: MTB650-B4;c. Material: H.S. steel tube capped with cast aluminum parts;d. Custom Colour: Green RAL 6028e. Installation as per manufacturer's instructions;f. Contractor to provide product data, colour chip sample and shop drawings prior to fabrication. |
|-------------|---|

EXTERIOR SITE FURNISHINGS

Rouge National Urban Park Trails Phase 3
December 3, 2020 Addendum #1

Section 32 37 00
Page 2 of 2

2. P-GATES

1. P-Gates

- a. P Offset Walkway Gate by Maglin (1-800-716-5506 x 1102), or approved equal.
- b. All pipe weights to be schedule 40.
- c. Contractor to padlock gate immediately following installation. Keys shall be provided to PCA upon award of Substantial Completion.
- d. Custom Colour: Green RAL 6028
- e. Installation as per manufacturer's instructions:
- f. Contractor to provide product data, colour chip sample, and shop drawings prior to fabrication.

PART 3 - EXECUTION

1. INSTALLATION

1. Assemble furnishings in accordance with manufacturer's instructions.
2. Install furnishings true, plumb, anchored and firmly supported, as directed by Contract Administrator.
3. Touch-up or replace damaged finishes to approval of Contract Administrator.

----- END OF SECTION -----