



RETURN BIDS TO:
RETOURNER LES SOUMISSIONS À:

PWGSC/TPSGC Acquisitions
Sherwood Business Centre
161 St. Peters Road/
161, rue St. Peters
2nd Floor, Suite 204/
2ième étage, pièce 204
Charlottetown
Prince Edward Island
C1A 5P7
Bid Fax: (902) 566-7514

SOLICITATION AMENDMENT
MODIFICATION DE L'INVITATION

The referenced document is hereby revised; unless otherwise indicated, all other terms and conditions of the Solicitation remain the same.

Ce document est par la présente révisé; sauf indication contraire, les modalités de l'invitation demeurent les mêmes.

Comments - Commentaires

All enquiries are to be submitted in writing to the Contracting Authority, Darlene Reay, either by facsimile or by e-mail at:
darlene.reay@pwgsc.gc.ca.

Vendor/Firm Name and Address
Raison sociale et adresse du
fournisseur/de l'entrepreneur

Issuing Office - Bureau de distribution
Public Works and Government Services Canada
Sherwood Business Centre
161 St. Peters Road/
2nd Floor, Suite 204
Charlottetown
Prince Ed
C1A 5P7

Title - Sujet Wood Islands Ferry Terminal Infrast Wood Islands Ferry Terminal Infrastructure Rehabilitation – Phase 3 Wood Islands	
Solicitation No. - N° de l'invitation ED001-211613/A	Amendment No. - N° modif. 006
Client Reference No. - N° de référence du client ED001-211613	Date 2020-12-15
GETS Reference No. - N° de référence de SEAG PW-SPWC-008-4534	
File No. - N° de dossier PWC-0-43027 (008)	CCC No./N° CCC - FMS No./N° VME
Solicitation Closes - L'invitation prend fin at - à 02:00 PM Atlantic Standard Time AST on - le 2020-12-22 Heure Normale de l'Atlantique HNA	
F.O.B. - F.A.B. Plant-Usine: <input type="checkbox"/> Destination: <input checked="" type="checkbox"/> Other-Autre: <input type="checkbox"/>	
Address Enquiries to: - Adresser toutes questions à: Reay, D (PWC)	Buyer Id - Id de l'acheteur pwc008
Telephone No. - N° de téléphone (902) 314-7957 ()	FAX No. - N° de FAX (902) 566-7514
Destination - of Goods, Services, and Construction: Destination - des biens, services et construction:	

Instructions: See Herein

Instructions: Voir aux présentes

Delivery Required - Livraison exigée	Delivery Offered - Livraison proposée
Vendor/Firm Name and Address Raison sociale et adresse du fournisseur/de l'entrepreneur	
Telephone No. - N° de téléphone Facsimile No. - N° de télécopieur	
Name and title of person authorized to sign on behalf of Vendor/Firm (type or print) Nom et titre de la personne autorisée à signer au nom du fournisseur/ de l'entrepreneur (taper ou écrire en caractères d'imprimerie)	
Signature	Date

The following changes in the tender documents are effective immediately. This addendum will form part of the contract documents.

This Addendum is raised to provide the following answers to questions provided by bidders.

Q1

Bid Item #3 East Berth Fender Reinstatement

Is the intention to reuse the existing connection hardware, or is new required. (I.e. Chains, shackles, rubber elements)?

A1

Intention is to re-use existing hardware.

Q2

Bid Item #4 Remove and Replace 35 Tonne Bollard and Foundation (East)

Is the intention to remove the bollard only, or is there an existing foundation that must be demolished as well? If there is a foundation please provide details.

A2

The bollard and base shall be removed, there is no information on existing bollard base (foundation).

Q3

Bid Item #4 Remove and Replace 35 Tonne Bollard and Foundation (East)

Does the owner supplied 35 tonne bollard include the anchor bolt assembly?

A3

No "owner supplied" bollard for this location. Contractor to supply and install bollard and hardware.

Q4

Bid Item #13 Install 35 Tonne Bollard Outer East Dolphin

(in Unit Price Table referred to as Install new 35.0 tonne mooring Bollard (supplied by owner)

Does the owner supplied 35 tonne bollard include the anchor bolt assembly?

A4

Bollard only will be supplied, all hardware to be supplied and installed by contractor. *Anchors and the type / grade of anchor is listed in the specification Section 35 59 29 – Bollards.*

Q5

Bid Item #11 Reinstatement of Navigation Light and Aluminum Gangway

Is the intention to re-use the existing cables for hook up the navigational light?

A5

Yes

Q6

Bid Item #16 East Berth Steel Sheet Pile Repair

Will it be permitted to dock ferries at the West Berth only, while repairs to the East Berth Sheet Piles are undertaken?

A6

No, contractor to coordinate work with on-going ferry operations as per the ferry schedule.

Q7

Crane Requirements

Are there any restrictions on the size of crane that can be used on site?

A7

Contractor will be provided "record" drawings of the area they propose to set up work activity. It is the contractor's responsibility to have the structural analysis completed to ensure the existing infrastructure is not being overloaded.

Q8

In several Items on the Dolphins and East and West Berth, Fenders Panel and Rubber Tire are to be removed and replaced. There is no reference anywhere to repairs to be made to the Fenders which may be damaged. Do we remove and install as is or are there repairs on the Fenders to be conducted?

A8

Remove and reinstall the existing fenders as is.

Q9

Item 9 covers dismantling of the Fenders, Deck Slab, Wheel Guards, D rings, Navigation Light and Bollard. Items 10, 11, 12 and 13 deal with installing Rubber Tire Fenders, Navigation Light, Guard Rail and 35 Tonne Bollard.

My question is where is the concrete for the new Slab to be carried? I don't see a reference anywhere specs or drawings to install a new deck. If there is not a new deck nothing else can be installed.

A9

The new concrete deck and wheel guard for the outer east dolphin is carried under Item 24 on Page 11 of Section 01 29 00. Add 01 29 00 to Specification Reference at Item 24 of the Unit Price Table.