



DEMOLITION NOTES

- EXISTING ROOM SENSOR TO BE REMOVED. REMOVE WIRING BACK TO EMCS PANEL.
- EXISTING PNEUMATIC THERMOSTAT TO REMAIN. REMOVE FROM WALL AND ATTACH TO STRUCTURE ABOVE. COIL EXCESS PNEUMATIC TUBE UP NEATLY.
- REMOVE EXISTING UNIT HEATER, INCLUDING ALL ASSOCIATED CONTROLS, HANGERS, BRANCH PIPING, VALVES, INSULATION, THREADED ROD, ETC. CAP HEATING LINES AT MAINS.
- REMOVE EXISTING HEATING PIPING TO THE GLYCOL HEAT EXCHANGER IN MECHANICAL ROOM FL-137 ON FIRST FLOOR ABOVE. REMOVE ALL ASSOCIATED PIPING, VALVES, PUMP, INSULATION, HANGERS, THREADED ROD, CONTROLS, ETC. FROM HEADER IN BOILER ROOM TO HEAT EXCHANGER IN MECHANICAL ROOM FL-137.
- REMOVE EXISTING NPS 1 1/4 HEATING LINES TO DOMESTIC HOT WATER TANK IN MECHANICAL ROOM FL-137 ON FIRST FLOOR ABOVE. REMOVE ALL PIPING, INSULATION, VALVES, HANGERS, THREADED ROD, ETC. FROM HEADER IN BOILER ROOM TO HEAT EXCHANGER IN MECHANICAL ROOM FL-137.
- REMOVE EXISTING HEATING LINES TO SALT WATER HEADER ON FIRST FLOOR ABOVE. REMOVE ALL PIPING, VALVES, INSULATION, HANGERS, THREADED ROD, CONTROLS, ETC. FROM HEADER IN BOILER ROOM TO HEADER ON FIRST FLOOR.

GROUND FLOOR — HEATING DEMOLITION

SCALE : 1:100

0m 1m 2m 3m 4m 5m 6m 7m 8m 9m 10m



0	ISSUED FOR TENDER	DEC 14 2020
revisions		date
project	FISH LAB RENOVATION FACILITY FOR INTELLIGENT MARINE SYSTEMS B.I.O. DARTMOUTH, N.S. DEMOLITION	
drawing	MECHANICAL GROUND FLOOR HEATING DEMOLITION	

designed T.R.M.	conçu
date DECEMBER 14, 2020	
drawn R.P.A.	dessiné
date DECEMBER 14, 2020	
approved T.R.M.	approuvé
date DECEMBER 14, 2020	
Tender IAN SCELES	Soumission
PWGSB Project Manager	Administrateur de projets TPSGC
project number R.089911.001	no. du projet
drawing no. MD1.7	no. du dessin