
PART 1 - GENERAL

- | | |
|------------------------------------|---|
| 1.1 <u>Description of Work</u> | This Section includes but is not limited to the following:

.1 All normal removals as required to complete the work. All items to be verified by a site visit prior to submission of a tender. All available plans of the existing structure are available for viewing at the Project Manager's office, 2nd floor, 1713 Bedford Row, Halifax, N.S. However, due to COVID-19 restrictions, other electronic arrangements may be made. |
| 1.2 <u>Related Work</u> | .1 Refer to other specification sections for related information. |
| 1.3 <u>Submissions</u> | .1 Methodology:
.1 When requested provide methodology for carrying out the work |
| 1.4 <u>Protection</u> | .1 Prevent movement, settlement or damage of adjacent structures. Provided bracing and shoring as required. In event of damage, immediately replace such items or make repairs to approval of <i>Departmental Representative</i> and at no additional cost to <i>Departmental Representative</i> .

.2 Prevent debris from going adrift and becoming a menace to navigation.

.3 All damage to existing structures, roadways, pipelines, electrical systems not specified for removal to be repaired at the Contractor's cost to the satisfaction of the <i>Departmental Representative</i> . |
| 1.5 <u>Measurement for Payment</u> | .1 Sitework, demolition and removals will be measured in accordance with Section 01 29 00 . |
-

PART 3 - EXECUTION

- 3.1 Preparation
- .1 Inspect site and verify with *Departmental Representative* items designated for removal and items to be preserved.
 - .2 Locate and protect utility lines. Preserve in operating condition active utilities traversing site.
 - .3 Provide temporary power and lighting as shown on the plan or as required by the *Departmental Representative*.
 - .4 All repairs to damages as a result of Contractor's operations to be at Contractor's cost and to the satisfaction of the *Departmental Representative*.
- 3.2 Removal
- .1 Remove items indicated.
 - .2 Do not disturb adjacent structures designated to remain in place.
 - .3 At end of each day's work, leave work in safe condition so no part is in danger of toppling or falling.
- 3.3 Disposal of Material
- .1 Disposal of materials not destined for the designated containment cell will be the contractor's responsibility, and must be disposed of off-site.
 - .2 The material to be disposed is to be transported and disposed of in an environmentally acceptable manner to the satisfaction of the *Departmental Representative*, and in accordance with any local, Municipal, Provincial and Federal restrictions and regulations.
- 3.4 Restoration
- .1 Upon completion of work, remove debris, trim surfaces and leave work site clean.
-

Harbour Dredging

East Chezzetcook SCH

Halifax Regional Municipality, Nova Scotia

Project No. R.112425.001

Sitework, Demolition and Removals

Page 3

-
- .2 Reinstall areas and existing works outside areas of demolition to conditions that existed prior to commencement of work. Match condition of adjacent, undisturbed areas.